

**GENERAL NOTES**

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.
2. TREE REMOVALS SHOWN IN THE PLANS SHALL BE MARKED IN THE FIELD AND VERIFIED BY THE ENGINEER PRIOR TO REMOVAL BY THE CONTRACTOR. ALL REMAINING TREES SHALL BE PROTECTED BY THE CONTRACTOR FROM DAMAGE DUE TO HIS OPERATIONS.
3. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE LANDSCAPE ARCHITECT KATHY CINDRICH (815-434-6131) AT LEAST 14 DAYS IN ADVANCE OF TREE PLANTING. TREE PLANTING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER AND THE IDNR SITE SUPERINTENDANT DAVE HAHNE. TREE PLANTING LOCATIONS COULD INCLUDE THE LOCK 21 PARK SITE AND THE IDNR VISITORS CENTER, APPROXIMATELY 4.5 MILES NORTHWEST OF THE PROJECT SITE.
4. WHERE CLEANING OR PRUNING IS REQUIRED FOR PROPOSED IMPROVEMENTS, IT SHALL BE IN ACCORDANCE WITH SECTION 201 OF THE STANDARD SPECIFICATIONS EXCEPT THAT ANY COST FOR CLEARING OR PRUNING REQUIRED SHALL BE INCLUDED IN THE UNIT PRICE FOR EARTH EXCAVATION (WIDENING).
5. EXCESS EXCAVATION MAY BE DISPOSED OF WITHIN PARK BOUNDARIES AND A LOCATION APPROVED BY THE ENGINEER. THE CONTRACTOR SHALL SPECIFY TO THE ENGINEER, IN WRITING, HOW THE LANDSCAPE RESTORATION WILL BE ACCOMPLISHED. PLACEMENT OF FILL IN SUCH AREAS SHALL NOT COMMENCE UNTIL THE CONTRACTOR'S LANDSCAPE RESTORATION PLAN IS APPROVED BY THE ENGINEER AS STATED IN ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.
6. GRADING SHALL BE DONE BY HAND AROUND LIGHT POLES, UTILITY POLES, SIGN POSTS, SHRUBS, TREES OR OTHER NATURAL OR MAN-MADE OBJECTS WHERE SHALLOW FILLS OR CUTS ARE ADJACENT TO THE ITEMS. IT IS THE INTENT THAT THE LIMITS OF CONSTRUCTION BE SUCH AS TO PRESERVE IN THE ORIGINAL STATE AS MUCH AREA AS POSSIBLE. THE DECISION AS TO ITEMS TO REMAIN IN PLACE SHALL BE DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER CUBIC YARD FOR EARTH EXCAVATION (WIDENING), AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
7. SEEDING SHALL BE DONE ON ALL AREAS THAT ARE DISTURBED BY CONSTRUCTION OPERATIONS AS DIRECTED BY THE ENGINEER. SEEDING SHALL BE PAID FOR ONLY WITHIN THE PROPOSED CONSTRUCTION LIMITS. ALL AREAS DISTURBED BY THE CONTRACTOR OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE SEEDED, AS DIRECTED BY THE ENGINEER, AT THE CONTRACTORS'S EXPENSE.
8. THE EXISTING CONCRETE BLOCKS LOCATED ALONG THE MAIN CAMPGROUND ROAD AND THE THE EXISTING CONCRETE FENCE POSTS LOCATED THROUGHOUT THE PROJECT ARE HISTORIC ARTIFACTS AND SHALL BE PROTECTED TO PREVENT DAMAGE FROM THE CONTRACTOR'S OPERATIONS.
9. WHERE PROPOSED CONSTRUCTION ABUTS EXISTING APPURTENANCES, A SAW CUT SHALL BE MADE TO ACHIEVE A NEAT CONSTRUCTION JOINT. SAW CUTTING WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE FOR THE ITEM BEING CONSTRUCTED.
10. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF WORK; HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
11. FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.
12. THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:
 

|                                |                   |
|--------------------------------|-------------------|
| GRANULAR MATERIALS             | 2.05 TONS / CU YD |
| BITUMINOUS SURFACE TREATMENTS: |                   |
| PRIME COAT                     | 0.5 GAL / SQ YD   |
| COVER & SEAL COAT              | 0.5 GAL / SQ YD   |
| COVER COAT AGGREGATE           | 20 LB / SQ YD     |
| SEAL COAT AGGREGATE            | 20 LB / SQ YD     |
13. THE CONTRACTOR SHALL NOTIFY THE ILLINOIS DEPARTMENT OF NATURAL RESOURCES HENNEPIN CANAL PARKWAY SITE SUPERINTENDENT DAVE HAHNE, AT PHONE NUMBER 815-454-2328 AT LEAST TWO WEEKS IN ADVANCE OF MOVING EQUIPMENT, MATERIALS, OR WORK FORCES TO THE SITE.

|   |                                 |                |           |   |  |                           |            |        |                 |              |  |
|---|---------------------------------|----------------|-----------|---|--|---------------------------|------------|--------|-----------------|--------------|--|
| FILE NAME =   | USER NAME = OpenH&B Springfield | DESIGNED - MJO | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>GENERAL NOTES<br/>IDNR HENNEPIN CANAL LOCK 21</b> | F.A.<br>RTE.              | SECTION    | COUNTY | TOTAL<br>SHEETS | SHEET<br>NO. |  |
| L:\DDT\1106610\W0_4\Draw\CA00_Sheets\046211-sht-Gennote.dgn | 46211-sht-Gennote.dgn           | DRAWN - RAH    | REVISED - |   |  |                           | PARK ROADS | BUREAU | 28              | 2            |  |
| PLOT SCALE = 40.0000' / IN.                                 |                                 | CHECKED - BJD  | REVISED - |   |  | CONTRACT NO. 46211        |            |        |                 |              |  |
| PLOT DATE = 3/29/2012                                       |                                 | DATE - 3/30/12 | REVISED - |   |  | ILLINOIS FED. AID PROJECT |            |        |                 |              |  |
|   |                                 |                |           |   | SCALE:   | SHEET NO. 1 OF 1 SHEETS   |            | STA.   | TO STA.         |              |  |