

TREE REMOVAL

STATION/LOCATION	TREE REMOVAL (6 TO 15 UNITS)		TREE REMOVAL (OVER 15 UNITS)	
		(UNIT)		(UNIT)
BOAT RAMP ROAD				
11+10	73'LT	8		
13+18	15'LT	13		
13+21	14'LT		20	
13+21	17'LT	14		
13+23	12'LT		18	
13+23	12'LT		18	
14+00	18'LT	10		
14+06	23'LT	10		
14+12	24'LT	8		
MAIN CAMPGROUND ROAD				
25+06	31'LT	15		
EQUESTRIAN CAMPGROUND ROAD				
68+32	27'LT	8		
72+14	13'LT	8		
72+23	11'LT	12		
72+25	11'LT	12		
72+56	10'LT		18	
72+56	10'LT		18	
76+57	15'LT	8		
TOTALS		126	92	

EARTHWORK

STATION / LOCATION	EARTH EXCAVATION (WIDENING)	FOR INFORMATION ONLY			TOPSOIL EXCAVATION AND PLACEMENT	GRADING AND SHAPING DITCHES	
		EARTH EXCAVATION ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE			
	(CU YD)	(CU YD)	(CU YD)	WASTE (+) SHORTAGE (-)	(CU YD)	(FOOT)	
MAIN ENTRANCE							
30+00.00 - 34+45.00	100	75	3	72	63	100	
BOAT RAMP ROAD							
11+00.00 - 15+00.00	241	181	33	148	111	50	
MAIN CAMPGROUND ROAD							
20+00.00 - 21+00.00	132	99	84	15	42	50	
21+00.00 - 29+25.00	157	118	45	73	200	200	
EQUESTRIAN CAMPGROUND ROAD							
50+00.00 - 54+00.00	24	18	1	17	34		
54+00.00 - 62+50.00	96	72	1	71	51		
62+50.00 - 72+00.00	122	92	8	84	89		
72+00.00 - 80+51.12	145	109	26	83	108	100	
80+90.91 - 84+40.00	44	33	1	32	74	150	
TOTALS		1,061	796	202	594	772	650

PAVING

STATION / LOCATION	PREPARATION OF BASE	AGGREGATE BASE COURSE, TYPE A 12"	AGGREGATE BASE COURSE, TYPE A	AGGREGATE SHOULDERS, TYPE B 6"	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	COVER COAT AGGREGATE	SEAL COAT AGGREGATE
	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(GALLON)	(GALLON)	(TON)	(TON)
MAIN ENTRANCE								
30+00.00 - 34+45.00	863	280	125.0		548	1,643	21.9	11.0
BOAT RAMP ROAD								
11+00.00 - 15+00.00	1,059	524	159.7		700	2,099	28.0	14.0
MAIN CAMPGROUND ROAD								
20+00.00 - 21+00.00	150	106	23.9		105	315	4.2	2.1
21+00.00 - 29+25.00	1,263	736	218.3		957	2,869	38.2	19.1
EQUESTRIAN CAMPGROUND ROAD								
50+00.00 - 54+00.00	558	161	76.2		334	1,002	13.4	6.7
54+00.00 - 62+50.00	1,104	389	150.9	46	662	1,984	26.4	13.2
62+50.00 - 72+00.00	1,240	503	169.0	56	741	2,221	29.6	14.8
72+00.00 - 80+51.12	1,009	593	168.2	33	737	2,211	29.5	14.7
80+90.91 - 84+40.00	412	259	63.1		277	829	11.0	5.5
TOTALS		7,658	3,551	1,154.3	135	5,061	202.2	101.1