



TEMPORARY DITCH CHECKS:

| STA. | L.F. |
|----------|------|
| RT 15+15 | 6 |
| RT 16+30 | 6 |
| RT 17+40 | 6 |
| LT 17+50 | 6 |
| RT 18+00 | 6 |
| RT 18+70 | 6 |
| LT 21+00 | 6 |

GRADING AND SHAPING DITCHES:

| STA. | L.F. |
|---------------------|------|
| RT 15+00 - RT 15+15 | 15 |
| RT 15+30 - RT 17+40 | 210 |
| LT 15+35 - LT 17+50 | 215 |
| RT 18+00 - RT 20+00 | 200 |
| LT 20+90 - LT 21+00 | 10 |

PERIMETER EROSION BARRIER:

| STA. | L.F. |
|---------------------|------|
| LT 15+00 - LT 15+35 | 35 |
| RT 15+15 - RT 15+30 | 15 |
| LT 17+50 - LT 21+90 | 340 |
| RT 17+40 - RT 18+00 | 60 |
| RT 20+00 - RT 21+00 | 100 |

- TEMPORARY DITCH CHECK
- INLET AND PIPE PROTECTION
- PROPOSED RIPRAP
- PERIMETER EROSION CONTROL
- PAVEMENT PATCHING

| | | | |
|-------------|----------------------|-------------------|-----------|
| FILE NAME = | USER NAME = #USER# | DESIGNED - R.H.D. | REVISED - |
| #FILE# | | DRAWN - J.T.T. | REVISED - |
| | PLOT SCALE = #SCALE# | CHECKED - R.H.D. | REVISED - |
| | PLOT DATE = #DATE# | DATE - 4/4/12 | REVISED - |

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**WASHINGTON COUNTY CONSERVATION AREA
 MAIN ALIGNMENT**

SCALE: 1" = 20' SHEET NO. 18 OF 112 SHEETS STA. 15+00 TO STA. 21+00

| SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|------------|--------------------|-----------|
| | WASHINGTON | 112 | 18 |
| | | CONTRACT NO. 46223 | |
| ILLINOIS FED. AID PROJECT | | | |

JOB NO. 250-081-# VASCANELLES ENGINEERING CORP. DESIGN FIRM REGISTRATION NUMBER 184-002107