REMOVAL SCHEDULE

LOCATION	STATION	TO STATION	PAV'T. REMOVAL AREA SQ. YD.	GRADE & SHAPE DITCHES FT.	TIMBER CURB REMOVAL FT.	CRACK ROUTING FT.	EARTH EXC. SPECIAL CU. YD.
DAY USE LOOP							
LT	100+50	104+07			328		
RT	100+50	104+07			501		
RT	102+98	103+93				566	
RT	103+58	103+68					2.7
LT	104+07	112+56			665		
RT	104+07	112+56			597		
LT	112+56	117+22			204		
RT	112+56	117+22			264		
CAMPGROUND							
LT	200+15	200+75					4
RT	200+84	201+16					2
VISITOR CENTER							
	300+89	301+03	22				
CAMPGROUND TRAIL							
LT & RT	400+16.8	400+39					1
LINCOLN LEAGUE LANE							
LT & RT	600+11	600+32					21.5
LT & RT	600+31	601+12		81			
RT	600+43	601+70		28			
RT	602+51.64	602+78.08					15.5
		TOTAL	22	109	2559	566	46.7

PAVING SCHEDULE

LOCATION	STATION	TO STATION	PAV'T. SURFACE AREA SQ. YD.	8 INCH AGG. BASE CSE B SQ. YD.	CRACK FILLING POUND	(A2 SURFACE) BIT MATLS PR CT GAL.	(A2 SURFACE) COVER AND SEAL COAT GAL.	COVER COAT AGG TON	SEAL COAT AGG TON	8 IN. PCC PVT AREA SQ. YD.	SUB GRAN MAT B 4 IN. AREA SQ. YD.	TIMBER CURB FOOT
DAY USE LOOP												
	100+21	104+07.13	1351			506.6	472.9	13.5	16.9			
LT	100+50	104+07										370
RT	100+50	104+07										525
RT	102+98	103+93			566.0							
RT	103+58	103+68								8	8	
	104+07.13	112+55.53	1076			403.5	376.6	10.8	13.5			
LT	104+07	112+56										646
RT	104+07	112+56										617
	112+55.53	117+21.58	868			325.5	303.8	8.7	10.9			
LT	112+56	117+22										410
RT	112+56	117+22										448
CAMPGROUND												
	200+15	201+16	232			87.0	81.2	2.3	2.9			
LT	200+15	200+75		16.0								
RT	200+84	201+16		8.0								
VISITOR CENTER												
	300+89	301+03								22	22	
CAMPGROUND TRAIL												
	400+06	403+33	307			115.1	107.5	3.1	3.8			
LINCOLN LEAGUE LANE												
RT	602+51.64	602+78.08	69.5	69.5		26.1	24.3	0.7	0.9			
		TOTAL	3903.5	93.5	566.0	1463.8	1366.2	39.0	48.8	30	30	3016

LIST OF STANDARDS

280001-06 TEMPORARY EROSION CONTROL SYSTEMS
542301-03 PRECAST REINFORCED CONCRETE FLARED END SECTION
602601-02 PRECAST REINFORCED CONCRETE FLAT SLAB TOP
701006-03 OFF ROAD OPERATIONS, 2L, 2W, 15' FROM PAVEMENT EDGE
701011-02 OFF-ROAD MOVING OPERATIONS, 2L, 2W DAY ONLY
701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701901-02 TRAFFIC CONTROL DEVICES
B.L.R. 21-9 TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES

GENERAL NOTES

1) ALL ELEVATIONS ARE REFERENCED TO ELEVATIONS ESTABLISHED BY VASCONCELLES ENGINEERING CORP.

2) WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER AND AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. IF THE ENGINEER DECIDES TO HAVE THE CONTRACTOR RESET THE MONUMENT, THIS WORK WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04.

3) THE CONTRACTOR SHALL CONTACT J.U.L.I.E. PRIOR TO ANY EXCAVATION TO HAVE ALL PUBLIC AND PRIVATE UTILITIES LOCATED.

4) THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.26 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS (800) 892-0123. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED. SEE SPECIAL PROVISIONS FOR STATUS OF UTILITIES, WITH UTILITY COMPANIES LISTED.

5) ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.

6) ALL DETAILS IN THE PLANS SHALL GOVERN CONSTRUCTION OF THIS PROJECT, AND IN CASE OF CONFLICT WITH ANY STANDARD DRAWINGS INCLUDED, THE SAID DETAILS SHALL TAKE PRECEDENCE AND GOVERN.

SUMMARY OF QUANTITIES

100% STATE
0005

CODE *	PAY ITEM	UNITS	TOTAL
21400100*	GRADING AND SHAPING DITCHES	FOOT	109
28000305	TEMPORARY DITCH CHECKS	FOOT	12
28000500	INLET AND PIPE PROTECTION	EACH	2
28100105	STONE RIPRAP, CLASS A3	SQ YD	22.2
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	30
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	94
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1464
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	1386
40300500	COVER COAT AGGREGATE	TON	39
40300600	SEAL COAT AGGREGATE	TON	49
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	30
44000100	PAVEMENT REMOVAL	SQ YD	22
45100100	CRACK ROUTING (PAVEMENT)	FOOT	566
45100200	CRACK FILLING	POUND	566
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	20
54213447	END SECTIONS 12"	EACH	2
60100080*	FRENCH DRAINS	CU YD	11.3
60255500	MANHOLES TO BE ADJUSTED	EACH	1
67100100	MOBILIZATION	L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	9.2
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	474
X0322329*	TIMBER CURB REMOVAL	FOOT	2559
X0322878*	TIMBER CURB	FOOT	3016
X2020410*	EARTH EXCAVATION (SPECIAL)	CU YD	46.7
X0007217*	PAVER BLOCKS, SPECIAL	SQ FT	256

MISCELLANEOUS SCHEDULE

LOCATION	STATION	TO STATION	MOBILIZATION L SUM	TRAFFIC CONTROL & PROT. BLR 21 L SUM	MANHOLE TO BE ADJUSTED EACH	PAVER BLOCKS SPECIAL SQ. FT.	FRENCH DRAIN CU. YD.	P CUL CL A T 1 12" FT.	END SECTION 12" EACH	STONE RIPRAP CLASS A3 SQ. YD.	EROSION CONTROL INLET & PIPE PROT EACH	TEMP DITCH CHECK FT.	PAINT PVT MK LINE 6 FT.	PT PVT MK LTRS & SYMB SQ. FT.
ENTIRE PROJECT			1	1										
DAY USE LOOP														
RT	103+05	103+93											474	
RT	103+68	103+73												9.2
VISITOR CENTER														
	300+96				1									
HISTORICAL VILLAGE														
LT	502+50						11.3				1			
CAMPGROUND TRAIL														
LT & RT	400+16.8	400+39				256								
LINCOLN LEAGUE LANE														
LT	600+11	600+32								22.2				
RT	600+32											6		
RT	600+72											6		
RT	601+18							20	2					
RT	601.4										1			
		TOTAL	1	1	1	256	11.3	20	2	22.2	2	12	474	9.2

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - RHO	REVISED -
		DRAWN - JTT	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - RHO	REVISED -
	PLOT DATE = $DATE$	DATE - 4/4/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

LINCOLN'S NEW SALEM
SCHEDULE OF QUANTITIES

SCALE: NONE | SHEET NO. 2 OF 9 SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	LINCOLN'S NEW SALEM	MENARD	9	2
		CONTRACT NO.		
		ILLINOIS FED. AID PROJECT		