



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 7, 2012

SUBJECT: OR Route 0003 (Algonquin Bypass)
Section 18 A-2
McHenry County
Contract No. 60F72
Item No. 197, June 15, 2012 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised page vii of the Table of Contents to the Special Provisions.
3. Added pages 360-363 to the Special Provisions.
4. Revised sheets 1, 2, 6, 7, 13, 79, 84, 104-148, 177, 240, 255, 263, 345, 355, 355A-355C, 410, 680 & 767 of the Plans.
5. Added sheet 23A to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Bureau Chief of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Mike Renner; D.Carl Puzey;
Estimates

TBW/MS/III

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2000086	T-ACERX FREM AM 2-1/2	EACH	16.000				
A2001720	T-ACER SACR 2-1/2	EACH	9.000				
A2002020	T-AESCLUS GLA 2-1/2	EACH	2.000				
A2002320	T-BETULA NIGRA 2-1/2	EACH	14.000				
A2002720	T-CARYA OVATA 2-1/2	EACH	25.000				
A2002920	T-CELTIS OCCID 2-1/2	EACH	28.000				
A2004620	T-GLEDIT TRI IN 2-1/2	EACH	5.000				
A2005020	T-GYMNOCLA DIO 2-1/2	EACH	11.000				
A2005120	T-JUGLANS NIGRA 2-1/2	EACH	8.000				
A2005620	T-OSTRYA VIRG 2-1/2	EACH	14.000				
A2006420	T-QUERCUS ALBA 2-1/2	EACH	61.000				
A2006520	T-QUERCUS BICOL 2-1/2	EACH	15.000				
A2006720	T-QUERCUS MACR 2-1/2	EACH	80.000				
A2007120	T-QUERCUS RUBRA 2-1/2	EACH	19.000				
B2001166	T-CERCIS CAN CL 6'	EACH	10.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
B2001262	T-CORNUS ALT CL 4'	EACH	7.000				
B2001620	T-CRAT CRU-I TF 2-1/2	EACH	5.000				
B2010016	T-AMELAN CAN TF 2	EACH	6.000				
C2C01536	S-CORNUS RACEMOSA 3'C	EACH	13.000				
C2C018G5	S-ARON MEL CG 5G	EACH	54.000				
C2C020G3	S-CORNUS STOLO CG 3G	EACH	62.000				
C2C05724	S-RHUS AROMA 2'C	EACH	104.000				
C2C11736	S-VIBURN DENT 3'C	EACH	44.000				
C2002636	S-EUONY ALAT COMP 3'	EACH	37.000				
C2003336	S-HAMAMELIS VIRG 3'	EACH	1.000				
C2003500	S-HYDRA PAN TAR 2.5'	EACH	7.000				
C2004841	S-PHYSO OP CNTR GLO3'	EACH	37.000				
C2011265	S-THUJA OCCIDENTAL 4'	EACH	11.000				
C2011424	S-SYRINGA VULG 2'	EACH	43.000				
C2011425	S-SYRINGA VULG ALBA2'	EACH	25.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
C2012136	S-VIBURN X JUD 3'	EACH	37.000				
C2012736	S-VIBURN PRUN 3'	EACH	6.000				
D2000260	E-JUNIPER CHIN 5'	EACH	20.000				
D2001018	E-JUNIP HOR WIL 18	EACH	28.000				
D2001536	E-JUNIP VIRG 3'	EACH	62.000				
D2002136	E-PICEA PUNGENS 3'	EACH	61.000				
D2002172	E-PICEA PUNGENS 6'	EACH	3.000				
D2002936	E-PINUS STROBUS 3'	EACH	9.000				
K0012980	P PL ORNAMENT T QRT P	UNIT	14.770				
K0012990	P PL ORNAMENT T GAL P	UNIT	1.430				
K0012992	P PL ORNAMENT T 2G P	UNIT	3.460				
K0013000	P PL PRAIRI 2X4 DPPLG	UNIT	108.000				
K0013030	P PL WETLND 2X4 DPPLG	UNIT	26.000				
K0013090	P PL WOODLD T 2X4 DPG	UNIT	8.000				
K1004572	PRAIRIE SEEDING SPL	ACRE	2.250				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
K1005875	TREE TRANSPLANT	EACH	6.000				
XX004913	REMOV FOC FR CONDUIT	FOOT	1,939.000				
XX006903	ORNAM ST SIGN POST,C	EACH	12.000				
XX007023	STAIN CONC STRUCTURES	SQ YD	4,273.000				
XX007169	NON-PRESSURE CONN	EACH	2.000				
XX008003	FORM LINER TEX SUR SP	SQ FT	4,644.000				
XX008348	MORTAR EX STRUCTURE	EACH	2.000				
XZ127900	RETAINING WALL REMOV	FOOT	2,883.000				
X0301423	NOISE AB WALL GRD MT	SQ FT	9,670.000				
X0301797	GATE REMOVAL	EACH	2.000				
X0301852	DEWATERING STRUCT N1	EACH	1.000				
X0321620	SAN SEW REMOV 21	FOOT	13.000				
X0322208	TEMP STORM SEWER PLUG	EACH	3.000				
X0323045	STONE OUTCROPPING	SQ FT	690.000				
X0323716	ACCESS GATE DOUBLE 30	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0323760	SAN SEW SER 6 PVC CMP	EACH	6.000				
X0324056	REM EX WOOD BOLLARD	EACH	47.000				
X0324062	ENTRANCE SIGN	L SUM	1.000				
X0324085	EM VEH P S LSC 20 3C	FOOT	5,451.000				
X0324455	DRILL/SET SOLD P SOIL	CU FT	10,605.000				
*ADD X0324534	REM & REIN LT POLES	L SUM	1.000				
X0324599	ROD AND CLEAN EX COND	FOOT	843.000				
X0325110	BIAXIAL GEOGRID	SQ YD	1,445.000				
X0325751	DRIVE SOLDIER PILES	FOOT	172.000				
X0326694	PLUG EX STORM SEWERS	CU YD	5.000				
X0326744	PLUG PIPE PENETRATION	EACH	3.000				
X0326805	FOUNDATION REMOVAL	SQ FT	19,445.000				
X0326864	BRICK SIDEWALK REM	SQ FT	425.000				
X0327036	BIKE PATH REM	SQ YD	2,200.000				
X0327301	RELOCATE EX MAILBOX	EACH	14.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0327371	PLUG EXISTING PIPE	CU YD	0.500				
X0327410	CAST ALUM SP PED BASE	EACH	4.000				
X0327411	ORNAM ALUM LATTICE	FOOT	1,106.000				
X0327412	RAILROAD TIES REMOVED	FOOT	345.000				
X0327413	TEMP PED ENCLOSURE	L SUM	1.000				
X0327414	LT U T2 150W	EACH	6.000				
X0327415	LT U T2 250W	EACH	7.000				
X0327416	LT U T4 12' MH	EACH	18.000				
X0327417	LT U T4 14' MH	EACH	26.000				
X0327418	LT U T5	EACH	3.000				
X0350805	FOLD DOWN BOLLARDS	EACH	17.000				
X0350810	BOLLARD REMOVAL	EACH	3.000				
X0487700	SAN SEW REMOV 10	FOOT	561.000				
X0540000	BRICK PAVERS	SQ FT	1,853.000				
X0840000	SAN SEW REMOV 8	FOOT	537.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X2130010	EXPLOR TRENCH SPL	FOOT	500.000				
X2501800	SEEDING CL 4 MOD	ACRE	1.000				
X2502014	SEEDING CL 4A MOD	ACRE	1.000				
X2502019	SEEDING CL 4B SPL	ACRE	0.250				
X2502024	SEEDING CL 4B MOD	ACRE	0.500				
X2810900	CHANNEL BED AGGREGATE	SQ YD	1,835.000				
X2810950	POINT BAR AGGREGATE	SQ YD	134.000				
X4240430	PC CONC SIDEWALK 5 SP	SQ FT	19,344.000				
X5021510	COFFERDAMS SPL	EACH	4.000				
X5041800	CONCRETE ANCHORS	EACH	9.000				
X5091755	PARAPET RAILING SPL	FOOT	1,129.000				
X5510100	STORM SEWER REMOVAL	FOOT	371.000				
X5537800	SS CLEANED 12	FOOT	7.000				
X5537900	SS CLEANED 15	FOOT	333.000				
X5610004	D I WTR MN FITTINGS	POUND	1,925.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X5610646	PLUG WATER MAIN 6	EACH	1.000				
X5610704	WATER MAIN REMOV 4	FOOT	56.000				
X5610706	WATER MAIN REMOV 6	FOOT	16.000				
X5610708	WATER MAIN REMOV 8	FOOT	821.000				
X5610900	DIWM 8 DIAM REST JT	FOOT	144.000				
X5620124	WATER SERV LINE REM	FOOT	851.000				
X6022810	MAN SAN 4 DIA T1F CL	EACH	10.000				
X6022820	MAN SAN 5 DIA T1F CL	EACH	2.000				
X6026050	SANITARY MANHOLE ADJ	EACH	12.000				
X6026054	SAN MAN REMOVED	EACH	5.000				
X6026622	VV REMOVED	EACH	4.000				
X6028300	INLETS REMOVED SPL	EACH	1.000				
X6060200	CONC MED TSB6.24 MOD	SQ FT	7,471.000				
X6370050	CONC BAR WALL SPL	FOOT	356.000				
X6640300	CH LK FENCE REMOV	FOOT	1,019.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6650202	WOV W FENCE REMOV	FOOT	35.000				
X6700410	ENGR FLD OFF A SPL	CAL MO	30.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7240205	REMOV SIGN COMPLETE	EACH	3.000				
X7280105	TELES STL SIN SUP SPL	FOOT	100.000				
X7810300	REC REF PVT MARKER	EACH	56.000				
X8100105	CONDUIT SPLICE	EACH	1.000				
X8160401	UD4#62#8#6GXLPUSE1.5P	FOOT	781.000				
X8360215	LIGHT POLE FDN 24D OS	FOOT	96.000				
X8380084	BKWY DEVICE COUPLING	EACH	16.000				
X8510500	PT RDWY LP OVER 40'	EACH	4.000				
X8510850	PT NEW COM MA&P SPL	EACH	1.000				
X8570226	FAC T4 CAB SPL	EACH	6.000				
X8570231	FAC T5 CAB SPL	EACH	1.000				
X8600105	MASTER CONTROLLER SPL	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X8620200	UNINTER POWER SUP SPL	EACH	6.000				
X8710024	FOCC62.5/125 MM12SM24	FOOT	16,530.000				
X8770135	S C MAA&P 42 SPL	EACH	1.000				
X8950090	RELOC EX LIGHT CONTR	EACH	1.000				
Z0001202	CONC BLOCK REMOVAL	CU YD	6.000				
Z0007118	UNTREATED TIMBER LAG	SQ FT	9,057.000				
Z0007430	TEMP SIDEWALK	SQ FT	1,106.000				
Z0012450	CONCRETE STEPS	CU YD	2.000				
Z0013300	CONC REM SPEC	SQ YD	57.000				
Z0013302	SEGMENT CONC BLK WALL	SQ FT	10,073.000				
Z0013797	STAB CONSTR ENTRANCE	SQ YD	81.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0015000	CURB STOPS 1	EACH	9.000				
Z0018010	DRAINAGE SCUPPR DS-33	EACH	6.000				
Z0019600	DUST CONTROL WATERING	UNIT	8,500.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0022800	FENCE REMOVAL	FOOT	55.000				
Z0026402	FUR SOLDIER PILES HP	FOOT	172.000				
Z0026404	FUR SOLDIER PILES WS	FOOT	3,294.000				
Z0030260	IMP ATTN TEMP FRN TL3	EACH	1.000				
Z0030275	IMP ATTN TEMP SUN TL2	EACH	3.000				
Z0033020	LUM SFTY CABLE ASMBLY	EACH	125.000				
Z0033028	MAINTAIN LIGHTING SYS	CAL MO	18.000				
Z0033056	OPTIM TRAF SIGNAL SYS	EACH	2.000				
Z0034210	MECH ST EARTH RET WL	SQ FT	36,884.000				
Z0042002	POROUS GRAN EMB SUBGR	CU YD	20,831.000				
Z0044298	PRESS CONN EX WTR MN	EACH	1.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	3,293.000				
Z0048900	RR TRACK REMOV	FOOT	395.000				
Z0056608	STORM SEW WM REQ 12	FOOT	432.000				
Z0056610	STORM SEW WM REQ 15	FOOT	109.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0056616	STORM SEW WM REQ 24	FOOT	135.000				
Z0056900	SAN SEW 8	FOOT	1,117.000				
Z0057000	SAN SEW 10	FOOT	535.000				
Z0057400	SAN SEW 21	FOOT	23.000				
Z0062456	TEMP PAVEMENT	SQ YD	5,699.000				
Z0067500	STEEL CASINGS 16	FOOT	608.000				
Z0067700	STEEL CASINGS 20	FOOT	120.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	2.000				
Z0077900	WD POST & RAIL FENCE	FOOT	684.000				
20100110	TREE REMOV 6-15	UNIT	9,000.000				
20100210	TREE REMOV OVER 15	UNIT	4,046.000				
20101000	TEMPORARY FENCE	FOOT	7,396.000				
20101100	TREE TRUNK PROTECTION	EACH	75.000				
20101200	TREE ROOT PRUNING	EACH	50.000				
*REV 20200100	EARTH EXCAVATION	CU YD	231,021.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20201200	REM & DISP UNS MATL	CU YD	20,111.000				
20400800	FURNISHED EXCAVATION	CU YD	58,510.000				
20700220	POROUS GRAN EMBANK	CU YD	4,246.000				
20800150	TRENCH BACKFILL	CU YD	8,324.000				
21101615	TOPSOIL F & P 4	SQ YD	227,225.000				
25000100	SEEDING CL 1	ACRE	3.000				
25000115	SEEDING CL 1B	ACRE	0.500				
25000210	SEEDING CL 2A	ACRE	14.750				
25000310	SEEDING CL 4	ACRE	20.000				
25000312	SEEDING CL 4A	ACRE	2.750				
25000314	SEEDING CL 4B	ACRE	2.500				
25000322	SEEDING CL 5A	ACRE	2.750				
25000400	NITROGEN FERT NUTR	POUND	1,898.000				
25000600	POTASSIUM FERT NUTR	POUND	1,898.000				
25000775	SELECT MOWING STAKES	EACH	213.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25100115	MULCH METHOD 2	ACRE	6.000				
25100630	EROSION CONTR BLANKET	SQ YD	222,905.000				
25100900	TURF REINF MAT	SQ YD	494.000				
28000200	EARTH EXC - EROS CONT	CU YD	26.000				
28000250	TEMP EROS CONTR SEED	POUND	5,036.000				
28000305	TEMP DITCH CHECKS	FOOT	1,751.000				
28000400	PERIMETER EROS BAR	FOOT	21,524.000				
28000510	INLET FILTERS	EACH	254.000				
28001000	AGGREGATE - EROS CONT	TON	742.000				
28100103	STONE RIPRAP CL A2	SQ YD	425.000				
28100105	STONE RIPRAP CL A3	SQ YD	25.000				
28100107	STONE RIPRAP CL A4	SQ YD	128.000				
28100109	STONE RIPRAP CL A5	SQ YD	1,348.000				
28200200	FILTER FABRIC	SQ YD	3,128.000				
28500400	ARTICUL BLOCK REV MAT	SQ YD	180.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
30300112	AGG SUBGRADE IMPR 12	SQ YD	117,849.000				
30300124	AGG SUBGRADE IMPR 24	SQ YD	3,545.000				
31101200	SUB GRAN MAT B 4	SQ YD	1,921.000				
31101400	SUB GRAN MAT B 6	SQ YD	11,985.000				
*REV 31101800	SUB GRAN MAT B 10	SQ YD	10,088.000				
31102000	SUB GRAN MAT C	CU YD	689.000				
31200502	STAB SUBBASE HMA 4.5	SQ YD	56,647.000				
*REV 35501287	HMA BASE CSE 2 1/4	SQ YD	10,214.000				
40201000	AGGREGATE-TEMP ACCESS	TON	11,086.000				
40600100	BIT MATLS PR CT	GALLON	13,983.000				
40600300	AGG PR CT	TON	35.000				
40600895	CONSTRUC TEST STRIP	EACH	1.000				
40600982	HMA SURF REM BUTT JT	SQ YD	65.000				
40603335	HMA SC "D" N50	TON	1,663.000				
40603595	P HMA SC "F" N90	TON	644.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40701846	HMA PAVT FD 8 1/4	SQ YD	12,926.000				
40701966	HMA PAVT FD 14 1/4	SQ YD	1,352.000				
40702700	FURNISH PROFILOGRAPH	L SUM	1.000				
42000416	PCC PVT 9 3/4 JOINTD	SQ YD	97,445.000				
42001300	PROTECTIVE COAT	SQ YD	131,273.000				
42001420	BR APPR PVT CON (PCC)	SQ YD	3,063.000				
42300200	PCC DRIVEWAY PAVT 6	SQ YD	382.000				
42300400	PCC DRIVEWAY PAVT 8	SQ YD	1,414.000				
42400800	DETECTABLE WARNINGS	SQ FT	823.000				
44000100	PAVEMENT REM	SQ YD	38,455.000				
44000160	HMA SURF REM 2 3/4	SQ YD	4,194.000				
44000200	DRIVE PAVEMENT REM	SQ YD	17,380.000				
44000300	CURB REM	FOOT	845.000				
44000500	COMB CURB GUTTER REM	FOOT	13,843.000				
44000600	SIDEWALK REM	SQ FT	9,002.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44003100	MEDIAN REMOVAL	SQ FT	50.000				
44004250	PAVED SHLD REMOVAL	SQ YD	5,347.000				
44201761	CL D PATCH T1 10	SQ YD	4.000				
44201765	CL D PATCH T2 10	SQ YD	70.000				
44201769	CL D PATCH T3 10	SQ YD	213.000				
44201771	CL D PATCH T4 10	SQ YD	2,508.000				
48100500	AGGREGATE SHLDS A 6	SQ YD	1,181.000				
48101500	AGGREGATE SHLDS B 6	SQ YD	1,583.000				
48203021	HMA SHOULDERS 6	SQ YD	77.000				
48300415	PCC SHOULDERS 9 3/4	SQ YD	6,041.000				
50100100	REM EXIST STRUCT	EACH	1.000				
50104400	CONC HDWL REM	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	585.000				
50200100	STRUCTURE EXCAVATION	CU YD	6,926.000				
50200300	COFFERDAM EXCAVATION	CU YD	2,033.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50200450	REM/DISP UNS MATL-STR	CU YD	4,533.000				
50201101	COFFERDAM TYP 1 LOC 1	EACH	1.000				
50201102	COFFERDAM TYP 1 LOC 2	EACH	1.000				
50201103	COFFERDAM TYP 1 LOC 3	EACH	1.000				
50201104	COFFERDAM TYP 1 LOC 4	EACH	1.000				
50201121	COFFERDAM TYP 2 LOC 1	EACH	1.000				
50201122	COFFERDAM TYP 2 LOC 2	EACH	1.000				
50300225	CONC STRUCT	CU YD	1,208.600				
50300255	CONC SUP-STR	CU YD	3,323.000				
50300260	BR DECK GROOVING	SQ YD	4,699.000				
50300285	FORM LINER TEX SURF	SQ FT	38,455.000				
50300300	PROTECTIVE COAT	SQ YD	8,559.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	8,084.000				
50800205	REINF BARS, EPOXY CTD	POUND	727,260.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50800515	BAR SPLICERS	EACH	452.000				
50900105	ALUM RAILING TY L	FOOT	715.000				
51100100	SLOPE WALL 4	SQ YD	317.000				
51201800	FUR STL PILE HP14X73	FOOT	11,115.000				
51202305	DRIVING PILES	FOOT	11,115.000				
51203800	TEST PILE ST HP14X73	EACH	8.000				
51204650	PILE SHOES	EACH	155.000				
51500100	NAME PLATES	EACH	4.000				
52000110	PREF JT STRIP SEAL	FOOT	462.000				
52100010	ELAST BEARING ASSY T1	EACH	30.000				
52100520	ANCHOR BOLTS 1	EACH	60.000				
52100530	ANCHOR BOLTS 1 1/4	EACH	60.000				
542A0253	P CUL CL A 1 48	FOOT	23.000				
54210182	PIPE ELBOW 12	EACH	6.000				
54210184	PIPE ELBOW 15	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54213657	PRC FLAR END SEC 12	EACH	42.000				
54213660	PRC FLAR END SEC 15	EACH	3.000				
54213663	PRC FLAR END SEC 18	EACH	5.000				
54213669	PRC FLAR END SEC 24	EACH	2.000				
54213675	PRC FLAR END SEC 30	EACH	4.000				
54213681	PRC FLAR END SEC 36	EACH	2.000				
54215991	R C PIPE ELBOW 36	EACH	2.000				
54247130	GRATING-C FL END S 24	EACH	2.000				
54247150	GRATING-C FL END S 30	EACH	4.000				
54247170	GRATING-C FL END S 36	EACH	2.000				
550A0050	STORM SEW CL A 1 12	FOOT	4,603.000				
550A0070	STORM SEW CL A 1 15	FOOT	436.000				
550A0090	STORM SEW CL A 1 18	FOOT	334.000				
550A0120	STORM SEW CL A 1 24	FOOT	61.000				
550A0140	STORM SEW CL A 1 30	FOOT	415.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
550A0340	STORM SEW CL A 2 12	FOOT	4,748.000				
550A0360	STORM SEW CL A 2 15	FOOT	585.000				
550A0380	STORM SEW CL A 2 18	FOOT	1,415.000				
550A0410	STORM SEW CL A 2 24	FOOT	344.000				
550A0430	STORM SEW CL A 2 30	FOOT	430.000				
550A0450	STORM SEW CL A 2 36	FOOT	1,502.000				
550A0640	STORM SEW CL A 3 12	FOOT	81.000				
550A0750	STORM SEW CL A 3 36	FOOT	214.000				
550A4500	SS CL A 1 EQRS 36	FOOT	146.000				
550A5300	SS CL A 2 EQRS 36	FOOT	105.000				
55100200	STORM SEWER REM 6	FOOT	21.000				
55100500	STORM SEWER REM 12	FOOT	2,191.000				
55100700	STORM SEWER REM 15	FOOT	536.000				
55100900	STORM SEWER REM 18	FOOT	551.000				
55101100	STORM SEWER REM 21	FOOT	93.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
55101200	STORM SEWER REM 24	FOOT	282.000				
55101300	STORM SEWER REM 27	FOOT	126.000				
55101400	STORM SEWER REM 30	FOOT	40.000				
55101600	STORM SEWER REM 36	FOOT	68.000				
56100600	WATER MAIN 6	FOOT	374.000				
56100700	WATER MAIN 8	FOOT	2,340.000				
56105000	WATER VALVES 8	EACH	6.000				
56200300	WATER SERV LINE 1	FOOT	228.000				
56200500	WATER SERV LINE 1 1/2	FOOT	518.000				
56200700	WATER SERV LINE 2	FOOT	145.000				
56201400	CORP STOPS 1	EACH	2.000				
56400100	FIRE HYDNPTS TO BE MVD	EACH	3.000				
56400300	FIRE HYDNPTS TO BE ADJ	EACH	1.000				
56400500	FIRE HYDNPTS TO BE REM	EACH	5.000				
56400820	FIRE HYD W/AUX V & VB	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
56500200	DOM WAT SER BOX MOVED	EACH	2.000				
56500700	DOM WAT SER BOX REM	EACH	9.000				
56500800	DOM WAT SER BOX	EACH	10.000				
58700300	CONCRETE SEALER	SQ FT	3,823.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	1,097.000				
60100060	CONC HDWL FOR P DRAIN	EACH	4.000				
60107600	PIPE UNDERDRAINS 4	FOOT	3,542.000				
60108100	PIPE UNDERDRAIN 4 SP	FOOT	156.000				
60200105	CB TA 4 DIA T1F OL	EACH	2.000				
60200205	CB TA 4 DIA T1F CL	EACH	3.000				
60200805	CB TA 4 DIA T8G	EACH	13.000				
60201005	CB TA 4 DIA T10F&G	EACH	2.000				
60201310	CB TA 4 DIA T20F&G	EACH	18.000				
60201340	CB TA 4 DIA T24F&G	EACH	62.000				
60203805	CB TA 5 DIA T1F OL	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60203905	CB TA 5 DIA T1F CL	EACH	1.000				
60204505	CB TA 5 DIA T8G	EACH	3.000				
60205040	CB TA 5 DIA T24F&G	EACH	18.000				
60205310	CB TA 6 DIA T24F&G	EACH	1.000				
60206600	CB TB T7G	EACH	1.000				
60206905	CB TC T1F OL	EACH	3.000				
60207005	CB TC T1F CL	EACH	1.000				
60207605	CB TC T8G	EACH	8.000				
60208240	CB TC T24F&G	EACH	86.000				
60218400	MAN TA 4 DIA T1F CL	EACH	32.000				
60219510	MAN TA 4 DIA T20F&G	EACH	1.000				
60219540	MAN TA 4 DIA T24F&G	EACH	1.000				
60221100	MAN TA 5 DIA T1F CL	EACH	17.000				
60222240	MAN TA 5 DIA T24F&G	EACH	1.000				
60223800	MAN TA 6 DIA T1F CL	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60224446	MAN TA 7 DIA T1F CL	EACH	2.000				
60224459	MAN TA 8 DIA T1F CL	EACH	1.000				
60224468	MAN TA 9 DIA T8G	EACH	1.000				
60234200	INLETS TA T1F OL	EACH	1.000				
60237470	INLETS TA T24F&G	EACH	6.000				
60248700	VV TA 4 DIA T1F CL	EACH	7.000				
60248900	VV TA 5 DIA T1F CL	EACH	1.000				
60250200	CB ADJUST	EACH	8.000				
60255500	MAN ADJUST	EACH	15.000				
60255800	MAN ADJ NEW T1F CL	EACH	1.000				
60256940	MAN ADJ NEW T24F&G	EACH	1.000				
60257900	MAN RECONST	EACH	1.000				
60260100	INLETS ADJUST	EACH	12.000				
60261540	INLETS ADJ NEW T24F&G	EACH	2.000				
60265700	VV ADJUST	EACH	9.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60500040	REMOV MANHOLES	EACH	18.000				
60500050	REMOV CATCH BAS	EACH	31.000				
60500060	REMOV INLETS	EACH	50.000				
60500105	FILL MANHOLES	EACH	1.000				
60600095	CLASS SI CONC OUTLET	CU YD	22.700				
60600605	CONC CURB TB	FOOT	1,770.000				
60602800	CONC GUTTER TB	FOOT	480.000				
*REV 60603800	COMB CC&G TB6.12	FOOT	5,221.000				
60604400	COMB CC&G TB6.18	FOOT	1,115.000				
60605000	COMB CC&G TB6.24	FOOT	32,356.000				
60608600	COMB CC&G TM6.06	FOOT	347.000				
60618300	CONC MEDIAN SURF 4	SQ FT	13,120.000				
60619600	CONC MED TSB6.12	SQ FT	69.000				
60620000	CONC MED TSB6.24	SQ FT	21,515.000				
60900515	CONC THRUST BLOCKS	EACH	5.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63000001	SPBGR TY A 6FT POSTS	FOOT	24.000				
63000003	SPBGR TY A 9FT POSTS	FOOT	1,148.000				
63100045	TRAF BAR TERM T2	EACH	5.000				
63100070	TRAF BAR TERM T5	EACH	3.000				
63100085	TRAF BAR TERM T6	EACH	7.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	7.000				
63200310	GUARDRAIL REMOV	FOOT	2,049.000				
63700275	CONC BAR 2F 42HT	FOOT	75.000				
66400305	CH LK FENCE 6	FOOT	320.000				
66900200	NON SPL WASTE DISPOSL	CU YD	728.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	1.000				
67100100	MOBILIZATION	L SUM	1.000				
67201100	SEAL ABAN MONIT WELLS	EACH	10.000				
70102620	TR CONT & PROT 701501	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70102625	TR CONT & PROT 701606	L SUM	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	55.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	36.400				
70300220	TEMP PVT MK LINE 4	FOOT	15,421.000				
70300240	TEMP PVT MK LINE 6	FOOT	107.000				
70300260	TEMP PVT MK LINE 12	FOOT	81.000				
70300510	PAVT MARK TAPE T3 L&S	SQ FT	146.000				
70300520	PAVT MARK TAPE T3 4	FOOT	53,195.000				
70300540	PAVT MARK TAPE T3 6	FOOT	2,639.000				
70300560	PAVT MARK TAPE T3 12	FOOT	315.000				
70300570	PAVT MARK TAPE T3 24	FOOT	44.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	2,223.000				
70400100	TEMP CONC BARRIER	FOOT	1,335.000				
72000100	SIGN PANEL T1	SQ FT	890.000				
72000200	SIGN PANEL T2	SQ FT	82.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72400100	REMOV SIN PAN ASSY TA	EACH	75.000				
72800100	TELES STL SIN SUPPORT	FOOT	1,406.000				
78000100	THPL PVT MK LTR & SYM	SQ FT	494.000				
78000200	THPL PVT MK LINE 4	FOOT	9,075.000				
78000400	THPL PVT MK LINE 6	FOOT	2,051.000				
78000600	THPL PVT MK LINE 12	FOOT	430.000				
78000650	THPL PVT MK LINE 24	FOOT	169.000				
78001100	PT PVT MK LTRS & SYMB	SQ FT	146.000				
78001110	PAINT PVT MK LINE 4	FOOT	5,870.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	1,672.000				
78008210	POLYUREA PM T1 LN 4	FOOT	26,183.000				
78008230	POLYUREA PM T1 LN 6	FOOT	8,036.000				
78008240	POLYUREA PM T1 LN 8	FOOT	7,482.000				
78008250	POLYUREA PM T1 LN 12	FOOT	4,252.000				
78008270	POLYUREA PM T1 LN 24	FOOT	740.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78100100	RAISED REFL PAVT MKR	EACH	1,076.000				
78200410	GUARDRAIL MKR TYPE A	EACH	22.000				
78200510	BAR WALL MKR TYPE A	EACH	12.000				
78201000	TERMINAL MARKER - DA	EACH	7.000				
78300100	PAVT MARKING REMOVAL	SQ FT	2,132.000				
80400100	ELECT SERV INSTALL	EACH	4.000				
80400200	ELECT UTIL SERV CONN	L SUM	1.000		20,000.000		20,000.000
80500010	SERV INSTALL GRND MT	EACH	2.000				
80500020	SERV INSTALL POLE MT	EACH	2.000				
81023300	CON ENC C 2 PVC 2X1	FOOT	38.000				
81028200	UNDRGRD C GALVS 2	FOOT	12,171.000				
81028210	UNDRGRD C GALVS 2 1/2	FOOT	1,895.000				
81028220	UNDRGRD C GALVS 3	FOOT	328.000				
81028240	UNDRGRD C GALVS 4	FOOT	4,821.000				
81100320	CON AT ST 1 PVC GS	FOOT	703.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81200120	CON EMB STR 2 GALVS	FOOT	271.000				
81200230	CON EMB STR 2 PVC	FOOT	4,915.000				
81300220	JUN BX SS AS 6X6X4	EACH	17.000				
81300530	JUN BX SS AS 12X10X6	EACH	16.000				
81304600	JUN BOX EM S 18X12X6	EACH	16.000				
81400100	HANDHOLE	EACH	38.000				
81400200	HD HANDHOLE	EACH	13.000				
81400300	DBL HANDHOLE	EACH	9.000				
81603020	UD 3#10#10GXLPUSE 3/4	FOOT	738.000				
81603040	UD 2#6 #8G XLPUSE 1	FOOT	2,268.000				
81603055	UD 3#8 #8G XLPUSE 1	FOOT	3,096.000				
81603090	UD 3#4#6GXLPUSE 1 1/4	FOOT	22,547.000				
81702110	EC C XLP USE 1C 10	FOOT	3,384.000				
81702120	EC C XLP USE 1C 8	FOOT	7,792.000				
81702130	EC C XLP USE 1C 6	FOOT	3,671.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81702140	EC C XLP USE 1C 4	FOOT	9,546.000				
81702150	EC C XLP USE 1C 2	FOOT	771.000				
81702220	EC C XLP USE 1C 350	FOOT	480.000				
81702460	EC C XLP USE 3-1C 3/0	FOOT	620.000				
82102310	LUM SV HOR MT 310W	EACH	125.000				
82107090	UNDERPAS LUM 50W HPS	EACH	2.000				
82107100	UNDERPAS LUM 70W HPS	EACH	11.000				
82107200	UNDERPAS LUM 100W HPS	EACH	4.000				
82500330	LT CONT PEDM 240V 60	EACH	1.000				
82500350	LT CONT BASEM 240V100	EACH	1.000				
82500360	LT CONT BASEM 480V100	EACH	1.000				
82500420	LT CONT BASM 480V200D	EACH	1.000				
83050730	LT P A 47.5MH 8DA	EACH	112.000				
83600200	LIGHT POLE FDN 24D	FOOT	920.000				
83600300	LIGHT POLE FDN 30D	FOOT	140.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
83800205	BKWY DEV TR B 15BC	EACH	92.000				
84200500	REM LT UNIT SALV	EACH	11.000				
84200804	REM POLE FDN	EACH	11.000				
84500120	REMOV ELECT SERV INST	EACH	2.000				
84500130	REMOV LTG CONTR FDN	EACH	1.000				
85000200	MAIN EX TR SIG INSTAL	EACH	4.000				
85100100	PAINT EX TR SIG EQUIP	EACH	1.000				
85100500	PT NEW TRAF SIG POST	EACH	26.000				
85100600	PT NEW MA&P < 40FT	EACH	3.000				
85100701	PT NEW MA&P >=40FT	EACH	4.000				
85100800	PT NEW COM MA&P <40FT	EACH	1.000				
85100901	PT NEW COM MA&P>=40FT	EACH	6.000				
86400100	TRANSCEIVER - FIB OPT	EACH	7.000				
87300925	ELCBL C TRACER 14 1C	FOOT	16,369.000				
87301215	ELCBL C SIGNAL 14 2C	FOOT	1,815.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87301225	ELCBL C SIGNAL 14 3C	FOOT	4,497.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	14,222.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	4,799.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	15,341.000				
87301805	ELCBL C SERV 6 2C	FOOT	673.000				
87301900	ELCBL C EGRDC 6 1C	FOOT	5,564.000				
87502480	TS POST GALVS 14	EACH	14.000				
87502500	TS POST GALVS 16	EACH	10.000				
87502520	TS POST GALVS 18	EACH	2.000				
87700170	S MAA & P 26	EACH	1.000				
87700180	S MAA & P 28	EACH	1.000				
87700270	S MAA & P 46	EACH	2.000				
87700290	S MAA & P 50	EACH	1.000				
87702860	STL COMB MAA&P 26	EACH	1.000				
87702880	STL COMB MAA&P 30	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87702940	STL COMB MAA&P 42	EACH	1.000				
87702970	STL COMB MAA&P 48	EACH	2.000				
87702985	STL COMB MAA&P 52	EACH	1.000				
87703000	STL COMB MAA&P 55	EACH	1.000				
87704150	STL COMB MAA&P 44 SPL	EACH	1.000				
87704170	STL COMB MAA&P 48 SPL	EACH	1.000				
87704403	S C MAA&P DMA 34 & 48	EACH	1.000				
87800100	CONC FDN TY A	FOOT	96.000				
87800150	CONC FDN TY C	FOOT	16.000				
87800205	MOD EX TY D FDN	EACH	1.000				
87800400	CONC FDN TY E 30D	FOOT	47.000				
87800415	CONC FDN TY E 36D	FOOT	150.000				
87900200	DRILL EX HANDHOLE	EACH	5.000				
88030020	SH LED 1F 3S MAM	EACH	33.000				
88030050	SH LED 1F 3S BM	EACH	13.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
88030080	SH LED 1F 4S MAM	EACH	2.000				
88030100	SH LED 1F 5S BM	EACH	5.000				
88030110	SH LED 1F 5S MAM	EACH	4.000				
88030210	SH LED 2F 3S BM	EACH	5.000				
88030220	SH LED 2F 5S BM	EACH	1.000				
88030240	SH LED 2F 1-3 1-5 BM	EACH	6.000				
88102717	PED SH LED 1F BM CDT	EACH	9.000				
88102757	PED SH LED 3F BM CDT	EACH	1.000				
88200210	TS BACKPLATE LOU ALUM	EACH	44.000				
88500100	INDUCTIVE LOOP DETECT	EACH	79.000				
88600100	DET LOOP T1	FOOT	517.000				
88600700	PREFORM DETECT LOOP	FOOT	3,649.000				
88700200	LIGHT DETECTOR	EACH	15.000				
88700300	LIGHT DETECTOR AMP	EACH	4.000				
88800100	PED PUSH-BUTTON	EACH	11.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60F72

State Job # - C-91-329-10

Project Number

Route

County Name - MCHENRY--

OR 0003

Code - 111 - -

*REVISED: JUNE 7, 2012

District - 1 - -

Section Number - 18A-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
89000100	TEMP TR SIG INSTALL	EACH	1.000				
89501400	REL EM VEH PR SYS D U	EACH	1.000				
89501410	REL EM VEH PR SYS P U	EACH	3.000				
89502300	REM ELCBL FR CON	FOOT	10,479.000				
89502375	REMOV EX TS EQUIP	EACH	4.000				
89502376	REBUILD EX HANDHOLE	EACH	1.000				
89502380	REMOV EX HANDHOLE	EACH	21.000				
89502385	REMOV EX CONC FDN	EACH	9.000				

WARM MIX ASPHALT (BDE)	279
PERMIT REQUIREMENTS AND BEST MANAGEMENT PRACTICES.....	284
FLY ASH RESTRICTION.....	284
ENGINEER'S FIELD OFFICE TYPE A (SPECIAL)	285
CAST ALUMINUM SPLIT PEDESTAL BASE.....	286
PAINT ROADWAY LIGHT POLE OVER 40 FEET	287
PAINT NEW COMBINATION MAST ARM AND POLE, (SPECIAL).....	288
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, SPECIAL	289
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)	316
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	319
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	323
STORM WATER POLLUTION PREVENTION PLAN.....	326
CONSTRUCTION OF A SEDIMENT TRAP	336
MENTOR-PROTÉGÉ PROGRAM (BDE)	346
PROJECT LABOR AGREEMENT - QUARTERLY EMPLOYMENT REPORT	346
PROJECT LABOR AGREEMENT	347
REMOVE AND REINSTALL LIGHT POLES.....	360
USACOE-REGIONAL PERMIT FOR CRYSTAL CREEK WORK	361

REMOVE AND REINSTALL LIGHT POLES

Description. This work shall consist of removing and reinstalling three (3) existing light poles that are located in the parking lot of the United States Post Office on Algonquin Road. The light poles are located in the existing employee parking lot on the west side of the building. These poles will be installed on new foundations at the locations shown on the plans or as directed by the Engineer. The relocated light fixtures will be powered in the same manner as the existing fixtures with new wire being pulled and tying into the existing system where feasible.

Method of Measurement. This work will be measured for payment per lump sum.

Basis of Payment. This work will be paid for at the contract unit price per each for REMOVE AND REINSTALL LIGHT POLES. This price shall be payment in full for removing, storing, reinstalling, burying new wire and connecting to the existing system, and shall include all labor, materials, and equipment necessary to complete the work as specified herein.

Added 06/07/12

USACOE-REGIONAL PERMIT FOR CRYSTAL CREEK WORK



REPLY TO
ATTENTION OF

DEPARTMENT OF THE ARMY
CHICAGO DISTRICT, CORPS OF ENGINEERS
111 NORTH CANAL STREET
CHICAGO, ILLINOIS 60606-7206

August 2, 2011

Technical Services Division
Regulatory Branch
LRC-2003-12161

SUBJECT: Authorization for the Realignment of Crystal Creek and Associated Wetland Creation and Enhancement within Towne Park, Algonquin, McHenry County, Illinois

Michele Zimmerman
Village of Algonquin
110 Meyer Drive
Algonquin, Illinois 60102

Dear Ms. Zimmerman:

The U.S. Army Corps of Engineers, Chicago District, has completed its review of your notification for authorization under the Regional Permit Program (RPP), submitted on your behalf by Applied Ecological Services. This office has verified that your proposed activity complies with the terms and conditions of Regional Permit 5 (Wetland and Stream Restoration and Enhancement) and 7 (Temporary Construction Activities) and the overall RPP under Category I of the Regional Permit Program dated April 1, 2007. The activity may be performed without further authorization from this office provided the activity is conducted in compliance with the terms and conditions of the RPP.

This verification is valid until the RPP is modified, reissued, or revoked. The RPP is scheduled to be modified, reissued, or revoked prior to April 1, 2012. We will issue a public notice when the Regional Permits are reissued so it is incumbent upon you to remain informed of changes to the RPP when they occur. Furthermore, if you commence or are under contract to commence this activity before the date that the relevant regional permit is modified or revoked, you will have twelve (12) months from the date of the modification or revocation of the RPP to complete the activity under the present terms and conditions of this regional permit(s).

This verification covers only your activity as described in your notification and as shown on the plans titled "Final Engineering Plans for Crystal Creek – Stream Restoration, Protection and Enhancement – Algonquin, Illinois" dated May 28, 2010, prepared by Applied Ecological Services. Caution must be taken to prevent construction materials and activities from impacting waters of the United States beyond the scope of this authorization. If you anticipate changing the design or location of the activity, you should contact this office to determine the need for further authorization. Please note that work involving the existing bridge and abutments located within regulated wetlands and waters are not covered by this authorization.

Added 06/07/12

The following conditions are a requirement of your permit:

1. Work in the waterway should be timed to take place during low or no-flow conditions. Low flow conditions are flow at or below the normal water elevation.
2. Water shall be isolated from the in-stream work area using a cofferdam constructed of non-erodible materials (steel sheets, aqua barriers, rip rap and geotextile liner, etc.). Earthen cofferdams are not permissible.
3. Work shall not be performed in the water, except for the placement of the materials necessary for the construction of the cofferdam. The cofferdam must be constructed from the upland area and no equipment may enter the water at any time. If the installation of the cofferdam cannot be completed from shore and access is needed to reach the area to be coffered, other measures, such as the construction of a causeway, will be necessary to ensure that equipment does not enter the water. Once the cofferdam is in place and the isolated area is dewatered, equipment may enter the coffered area to perform the required work.
4. If bypass pumping is necessary, the intake hose shall be placed on a stable surface or floated to prevent sediment from entering the hose. The bypass discharge shall be placed on a non-erodible, energy dissipating surface prior to rejoining the stream flow and shall not cause erosion. Filtering of bypass water is not necessary unless the bypass water has become sediment-laden as a result of the current construction activities.
5. During dewatering of the coffered work area, all sediment-laden water must be filtered to remove sediment. Possible options for sediment removal include baffle systems, anionic polymers systems, dewatering bags, or other appropriate methods. Water shall have sediment removed prior to being re-introduced to the downstream waterway. A stabilized conveyance from the dewatering device to the waterway must be identified in the plan. Discharge water is considered clean if it does not result in a visually identifiable degradation of water clarity.
6. The portion of the side slope that is above the observed water elevation shall be stabilized as specified in the plans prior to accepting flows. The substrate and toe of slope that has been disturbed due to construction activities shall be restored to proposed or pre-construction conditions and fully stabilized prior to accepting flows.
7. You shall fully implement the restoration plan titled, "Long-term Maintenance and Monitoring Plan – Village of Algonquin – Crystal Creek Tributary Stream Restoration, Protection, and Enhancement", dated May 27, 2011, prepared by Applied Ecological Services, within the first year of project construction. The stream and wetlands shall meet performance criteria in accordance with the standards outlined in the approved document referenced above.

This authorization is contingent upon implementing and maintaining soil erosion and sediment controls in a serviceable condition throughout the duration of the project. You shall

Added 06/07/12

comply with the McHenry County Soil and Water Conservation District's (SWCD) written and verbal recommendations regarding the soil erosion and sediment control (SESC) plan and the installation and maintenance requirements of the SESC practices on-site. You shall notify this office and the SWCD of any changes or modifications to the approved plan set. Please be aware that field conditions during project construction may require the implementation of additional SESC measures for further protection of aquatic resources. If you fail to implement corrective measures, this office may require more frequent site inspections to ensure the installed SESC measures are acceptable.

You shall complete the following requirements:

1. You shall notify the McHenry County SWCD of any changes or modifications to the approved plan set. Field conditions during project construction may require the implementation of additional SESC measures. If you fail to implement corrective measures, this office may require more frequent site inspections to ensure the installed SESC measures are acceptable.

This verification does not obviate the need to obtain all other required Federal, state, or local approvals before starting work. Please note that Section 401 Water Quality Certification has been issued by IEPA for this RP. Enclosed are the IEPA Section 401 Water Quality Certification conditions. If you have any questions regarding Section 401 certification, please contact Mr. Dan Heacock at IEPA Division of Water Pollution Control, Permit Section #15, by telephone at (217) 782-3362.

For a complete copy of the RPP program or any additional information on the RPP program, please access our website: www.lrc.usace.army.mil/co-r. Once you have completed the authorized activity, please sign and return the enclosed compliance certification. If you have any questions, please contact Mr. Soren Hall of my staff by telephone at 312-846-5532, or email at Soren.G.Hall@usace.army.mil.

Sincerely,



Keith L. Wozniak
Chief, West Section
Regulatory Branch

Enclosures

Copy Furnished w/out Enclosures:

Applied Ecological Services (William Stoll)
McHenry County Soil and Water Conservation District (Ed Weskerna)

Added 06/07/12