

EROSION CONTROL																						
STATION	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET FILTERS	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	MULCH, METHOD 2	AGGREGATE (EROSION CONTROL)	FILTER FABRIC	ARTICULATED BLOCK REVTMENT MAT	TURF REINFORCEMENT MAT	STONE RIPRAP, CLASS A3	STONE RIPRAP, CLASS A4										
	28000305	28000400	28000510	25100630	28000250	25100115	28001000	28200200	28500400	25100900	28100105	28100107										
	(FOOT)	(FOOT)	(EACH)	(SQ YD)	(POUND)	(ACRE)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)										
STAGE 1A																						
ALGONQUIN RD. 50+00 TO 53+00		278	2	280	6																	
53+00 TO 67+00		1773	29	15222	465	1.51	87	139	4													
67+00 TO 72+00		343	1	259	6																	
IL RTE 31 120+73 TO 127+75		4031	8	35157	723		131	213	10	494												
RAMP C 1+00 TO 5+00	51																					
MCCD 20+00 TO 25+00	160																					
STAGE 1B																						
ALGONQUIN RD. 50+00 TO 53+00		55	3	414	9																	
53+00 TO 67+00	34	815	29	28075	755	1.74	262	465	55		5											
67+00 TO 72+00	8	20	4	146	3																	
IL RTE 31 111+00 TO 117+50		1319		4367	122	0.32		35	30													
117+50 TO 129+65		1492	6	28578	735	1.45					5											
RAMP D 4+00 TO 12+00	8																					
12+00 TO 16+50	34																					
RAMP A 0+00 TO 15+00	84																					
MCCD 6+00 TO 20+00	126																					
CREEK RELOCATION		1730		8435	7			425														
STAGE 1C																						
IL RTE 31 111+00 TO 117+50	17	863	2	3497	129	0.57		6														
117+50 TO 128+00	51	1675	12	7944	204	0.40			5													
STAGE 2A																						
IL RTE 31 115+40 TO 126+00																						
126+00 TO 138+60																						
138+60 TO 153+00	253		5	6867	142			5	4													
153+00 TO 166+00	160		11	13402	277			20	16													
166+00 TO 178+00	84	421	16	17646	365							43										
RAMP A 0+00 TO 9+00		15																				
9+00 TO 21+50	152		6	7192	149		87	169	28													
21+50 TO 30+00	34		3	3573	74		44	82	12													
RAMP B 0+00 TO 10+00																						
10+00 TO 15+00																						
RAMP C 1+00 TO 7+00																						
7+00 TO 15+00											5											
RAMP D 0+00 TO 10+50	236		4	4645	96		87	154	16		5											
10+50 TO 17+00											5											
QUARRY ACCES 60+00 TO 67+00	143	1095		5456	113							65										
STAGE 2B																						
IL RTE 31 168+00 TO 176+00				9623	199																	
TOTALS											1633	15925	141	200778	4578	6.00	698	1713	180	494	20	108

NOTE:
FOR REMAINING EROSION CONTROL QUANTITIES
SEE SHEET NO. 44A

FILE NAME = ...\\D160F72-sht-schedule-06.dgn	USER NAME = ctb	DESIGNED - DTE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES				O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - DTE	REVISED -						0003	18A-2	MCHENRY	825	44
		CHECKED - GAB	REVISED -		SCALE: SHEET NO. 6 OF 11 SHEETS STA. TO STA.				CONTRACT NO. 60F72				
		DATE - 5/3/2012	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								