



LEGEND

ITEM	ABBREVIATION	QUANTITY
CI	T-CERCIS CAN CL 6'	10
JH	E-JUNIP HOR WIL 18	28
EA	S-EUONYMUS ALATUS 3'	28
HP	S-HYDRA PAN TAR 2.5'	7
PO	S-PHYSO OPULIFOLIUS 3'	29
SP	S-SYRINGA VULGARIS 2'	34
SW	S-SYRINGA VULGARIS ALBA	14
VJ	S-VIBURN X JUD 3'	25
*	P PL ORNAMENT T QRT P	7.74
**	P PL ORNAMENT T GAL P	0.73
***	P PL ORNAMENT T 2G P	2.06

* PERENNIAL PLANTS, ORNAMENTAL TYPE, QUART POT, PAID FOR AS 100 POTS PER UNIT

ITEM	DESCRIPTION	SHEET TOTAL	QUANTITY
EP	ECHINACEA PURPUREA 'MAGNUS'	102	1.20
CG	COREOPSIS GRANDIFLORA 'SUNRAY'	65	0.65
HC	HEMEROCALLIS 'CHICAGO APACHE'	62	0.62
HM	HEMEROCALLIS 'PARDON ME'	30	0.30
HS	HEMEROCALLIS 'STELLA DE ORO'	97	0.97
LB	LEUCANTHEMUM X SUPERBUM 'BECKY'	128	1.28
MJ	MONARDA DIDYMA 'JACOB CLINE'	45	0.45
MR	MONARDA DIDYMA 'RASPBERRY WINE'	35	0.35
NR	NEPETA RACEMOSA 'WALKER'S LOW'	90	0.90
PF	PAEONIA 'FESTIVA MAXIMA'	35	0.35
PK	PAEONIA 'KANSAS'	35	0.35
SN	SALVIA NEMOROSA 'MAY NIGHT'	50	0.50
TOTAL		774	7.74

** PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT, PAID FOR AS 100 POTS PER UNIT

ITEM	DESCRIPTION	SHEET TOTAL	QUANTITY
PA	PEROVSKIA ATRIPLICIFOLIA	30	0.30
LS	LIATRIS SPICATA	43	0.43
TOTAL		73	0.73

*** PERENNIAL PLANTS, ORNAMENTAL TYPE, 2-GALLON POT, PAID FOR AS 100 POTS PER UNIT

ITEM	DESCRIPTION	SHEET TOTAL	QUANTITY
GB	MISCANTHUS SINENSIS 'GOLD BAR'	42	0.42
SF	MISCANTHUS SINENSIS 'SILBERFEDER'	100	1.00
AF	MISCANTHUS SINENSIS PURPURASCENS	64	0.64
TOTAL		206	2.06



PLANTING DETAILS

HUNTINGTON DRIVE

FILE NAME = ...\\D160F72-sht-landscp-details-03.dgn	USER NAME = okw	DESIGNED - KTK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LANDSCAPING PLAN	O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 40.0000' / in.	CHECKED - KTK	REVISOR - ARA	REVISOR -			0003	18A-2	MCHENRY	825	259	
PLOT DATE = 5/2/2012	DATE - 5/3/2012	REVISOR -	REVISOR -			CONTRACT NO. 60F72					
						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					

SCALE: 1" = 20' SHEET NO. 14 OF 18 SHEETS STA. 99+00 TO STA. 112+00