

GENERAL NOTES

1. Fasteners shall be AASHTO M164 Type 1, mechanically galvanized bolts. Bolts $\frac{7}{8}$ in. ϕ , holes $\frac{5}{16}$ in. ϕ , unless otherwise noted.
2. Calculated weight of Structural Steel = 164,820 lbs (AASHTO M270 GR. 50)
Calculated weight of Structural Steel = 13,260 lbs (AASHTO M270 GR. 36)
3. No field welding is permitted except as specified in the contract documents.
4. Reinforcement bars designated (E) shall be epoxy coated.
5. If the Contractor elects to use cantilever forming brackets on the exterior beams or girders, the brackets shall be placed at the same locations as required for the hardwood blocks in Article 503.06(b) of the Standard Specifications. If additional cantilever forming brackets are required, hardwood blocking shall be wedged between the exterior and first interior beam at each of these additional bracket locations.
6. Concrete Sealer shall be applied to the designated areas of the backwalls and bridge seats of the abutments.
7. The Organic Zinc Rich Primer / Epoxy / Urethane Paint System shall be used for painting of new structural steel except where otherwise noted. The entire system shall be shop applied, with the exception that masked off connection surfaces, field installed fasteners and damaged areas shall be touched up in the field. The color of the final finish coat for all steel surfaces shall be Gray, Munsell No. 5B 7/1.
8. The embankment configuration shown shall be the minimum that must be placed and compacted prior to construction of the abutments.
9. Neither the MSE wall cast-in-place concrete facing, anchorage slab & parapet, approach slabs, nor approach roadway pavements shall be constructed until after the roadway embankment and reinforced select fill have been in place for 1 month, after which time less than 1 inch of the total anticipated $3\frac{3}{4}$ inches settlement is assumed to remain, without the prior approval of the Engineer. The settlement period may be shortened at the discretion of the Engineer if the monitoring data indicates a lesser than predicted settlement.
10. Slipforming of the parapets is not allowed.
11. Layout of slope protection system may be varied to suit ground conditions in the field as directed by the Engineer.

INDEX OF SHEETS

- SC1 General Plan & Elevation
- SC2 General Data
- SC3 Riprap Details
- SC4 Top of Slab Elevations I
- SC5 Top of Slab Elevations II
- SC6 Top of Approach Slab Elevations
- SC7 Superstructure
- SC8 Superstructure Details I
- SC9 Superstructure Details II
- SC10 Ornamental Aluminum Lattice
- SC11 Architectural Details
- SC12 Bridge Approach Slab
- SC13 Bridge Approach Slab Details
- SC14 Parapet Railing, Special
- SC15 Preformed Joint Strip Seal
- SC16 Drainage Scuppers, DS-33
- SC17 Framing Plan
- SC18 Plate Girder Details
- SC19 Bearing Details
- SC20 Abutments
- SC21 Abutment Details
- SC22 Pile Details
- SC23 MSE Walls
- SC24 MSE Wall Details
- SC25 Anchorage Slabs
- SC26 Bar Splicer Assembly Details
- SC27 Boring Logs I
- SC28 Boring Logs II
- SC29 Boring Logs III

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Stone Riprap, Class A5	Sq. Yd.	-	362	362
Filter Fabric	Sq. Yd.	-	362	362
Cofferdam Excavation	Cu. Yd.	-	297	297
Cofferdam (Type 1) (Location 3)	Each	-	1	1
Cofferdam (Type 1) (Location 4)	Each	-	1	1
Concrete Structures	Cu. Yd.	-	98.4	98.4
Concrete Superstructures	Cu. Yd.	317.8	-	317.8
Bridge Deck Grooving	Sq. Yd.	713	-	713
Form Liner Textured Surface	Sq. Ft.	-	1,775	1,775
Protective Coat	Sq. Yd.	944	-	944
Furnishing and Erecting Structural Steel	L. Sum	0.15	-	0.15
Stud Shear Connectors	Each	1,020	-	1,020
Reinforcement Bars, Epoxy Coated	Pound	175,760	9,850	185,610
Bar Splicers	Each	-	68	68
Furnishing Steel Piles HP14x73	Foot	-	1,599	1,599
Driving piles	Foot	-	1,599	1,599
Test Pile Steel HP14x73	Each	-	2	2
Pile Shoes	Each	-	27	27
Name Plates	Each	1	-	1
Preformed Joint Strip Seal	Foot	70	-	70
Elastomeric Bearing Assembly, Type I	Each	5	-	5
Anchor Bolts, 1"	Each	10	-	10
Anchor Bolts, 1 1/4"	Each	10	-	10
Concrete Sealer	Sq. Ft.	-	581	581
Geocomposite Wall Drain	Sq. Yd.	-	34	34
Parapet Railing, Special	Foot	269	-	269
Drainage Scuppers, DS-33	Each	1	-	1
Mechanically Stabilized Earth Retaining Wall	Sq. Ft.	-	2,846	2,846
Staining Concrete Structures	Sq. Yd.	-	197	197
Form Liner Textured Surface, Special	Sq. Ft.	596	-	596
Ornamental Aluminum Lattice	Foot	263	-	263

5/25/2012 2:04:20 PM I:\2154\cad\sheet\Roadway\20-STRUCTURES & WALLS\04-SN_056-0079\0560079-60F72-02-cd_rev2.dgn



450 E Devon Ave, Suite 300
 Itasca, Illinois 60143
 Tel: 630.773.3900 Fax: 630.773.3975
 www.civiltechinc.com

DRAWN	- M. LANGE	REVISED	- 5/4/12 K.L.B.
DESIGNED	- D. ATKINS	REVISED	-
CHECKED	- G. HATLESTAD	REVISED	-
DATE	- 5/3/2012	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL DATA
NB EXIT RAMP (RAMP B) OVER CRYSTAL CREEK
STRUCTURE NO. 056-0079

O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0003	18A-2	MCHENRY	825	527
CONTRACT NO. 60F72				
ILLINOIS FED. AID PROJECT				

SHEET NO. SC2 OF SC29 SHEETS