



PLAN

EAST EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
End N. Appr. Pav't	4+39.81	-22.00	757.83
A	4+49.81	-22.00	758.23
B	4+59.81	-22.00	758.63
Begin N. Appr. Pav't	4+69.81	-22.00	759.03
Begin S. Appr. Pav't	6+18.20	-22.00	764.49
C	6+28.20	-22.00	764.78
D	6+38.20	-22.00	765.05
End S. Appr. Pav't	6+48.20	-22.00	765.31

EAST EDGE OF PAVEMENT

Location	Station	Offset	Theoretical Grade Elevations
End N. Appr. Pav't	4+37.63	-16.00	757.65
A	4+47.63	-16.00	758.05
B	4+57.63	-16.00	758.45
Begin N. Appr. Pav't	4+67.63	-16.00	758.85
Begin S. Appr. Pav't	6+16.02	-16.00	764.33
C	6+26.02	-16.00	764.62
D	6+36.02	-16.00	764.90
End S. Appr. Pav't	6+46.02	-16.00	765.16

RAMP C, & PGL

Location	Station	Offset	Theoretical Grade Elevations
End N. Appr. Pav't	4+31.81	0.00	757.16
A	4+41.81	0.00	757.56
B	4+51.81	0.00	757.96
Begin N. Appr. Pav't	4+61.81	0.00	758.36
Begin S. Appr. Pav't	6+10.19	0.00	763.91
C	6+20.19	0.00	764.20
D	6+30.19	0.00	764.49
End S. Appr. Pav't	6+40.19	0.00	764.76

WEST EDGE OF SHOULDER

Location	Station	Offset	Theoretical Grade Elevations
End N. Appr. Pav't	4+28.90	8.00	756.88
A	4+38.90	8.00	757.28
B	4+48.90	8.00	757.68
Begin N. Appr. Pav't	4+58.90	8.00	758.08
Begin S. Appr. Pav't	6+07.28	8.00	763.65
C	6+17.28	8.00	763.95
D	6+27.28	8.00	764.24
End S. Appr. Pav't	6+37.28	8.00	764.52

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

TOP OF APPROACH SLAB ELEVATIONS  
SB ENTR. RAMP (RAMP C) OVER CRYSTAL CREEK  
STRUCTURE NO. 056-0080

O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0003	18A-2	MCHENRY	825	560
CONTRACT NO. 60F72				

SHEET NO. SD6 OF SD30 SHEETS

ILLINOIS FED. AID PROJECT

5/2/2012 4:21:20 PM I:\2154\cad\sheet\Roadway\20-Structures & Walls\05-SN\_056-0080\_0560080-60F72-06-APE.dgn

DRAWN	- M. LANGE	REVISED	-
DESIGNED	- D. ATKINS	REVISED	-
CHECKED	- G. HATLESTAD	REVISED	-
DATE	- 5/3/2012	REVISED	-