

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
				ROADWAY AND DRAINAGE	RETAINING WALL SN 022-W045	PUMP STATION 47
				0004	0040	0040
				URBAN	URBAN	URBAN
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	22,830		22,830	
X0325405	FILL EXISTING STORM SEWERS	CU YD	67	67		
X0326694	PLUG EXISTING STORM SEWERS	CU YD	0.5	0.5		
X0335700	PUMP STATION GENERAL WORK	L SUM	1			1
* X0783300	PUMP STATION ELECTRICAL WORK	L SUM	1			1
* X0783500	PUMP STATION MECHANICAL WORK	L SUM	1			1
X2020502	BRACED EXCAVATION	CU YD	2,730			2,730
X4402302	CURB REMOVAL (PARTIAL)	FOOT	170	170		
X6028050	TEMPORARY MANHOLE	EACH	5	5		
* X6640308	CHAIN LINK GATES, (SPECIAL)	EACH	3	3		
* X6640570	CHAIN LINK FENCE, 8' (SPECIAL)	FOOT	143	143		
* X6640585	CHAIN LINK FENCE, ATTACHED TO STRUCTURE, SPECIAL	FOOT	105	105		
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
Z0004522	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6"	SQ YD	356	356		

* SPECIALTY ITEM

USER NAME : #USER#	DESIGNED - <i>DMS</i>	REVISED - <i>04-06-2012</i>
	DRAWN - <i>KEA</i>	REVISED -
PLOT SCALE : #SCALE#	CHECKED - <i>PJO</i>	REVISED -
PLOT DATE : #DATE#	DATE - <i>03-22-2012</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338/IL 59	2011-035-I	DUPAGE	181	68
CONTRACT NO. 60P41			ILLINOIS FED. AID PROJECT	