

INDEX OF SHEETS

- S1. General Plan and Elevation
- S2. General Notes, Bill of Materials, and Index of Sheets
- S3. Center Break Details - I
- S4. Center Break Details - II

GENERAL NOTES:

1. Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work; however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
2. The removal and reattachment of the guardrail, hand rail, steel railings, traffic barrier terminal, etc. required for repair work (e.g. Center Break Adjustment) shall be included in the contract unit price of the work item being performed.
3. The existing structural steel coating contains lead. The Contractor shall take appropriate precautions to deal with the presence of lead on this project.
4. Fasteners shall be ASTM A325 Type 1, Mechanical Galvanized Bolts.
5. Existing structural steel shall only be cleaned and painted as required by the special provision "Cleaning and Painting Contact Surface Areas of Existing Steel Structures."

TOTAL BILL OF MATERIAL

ITEM DESCRIPTION	UNIT	QUANTITY
Center Break Adjustment	Each	3

FILE NAME =	USER NAME =	DESIGNED - AMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, BILL OF MATERIALS, AND INDEX OF SHEETS STRUCTURE NO. 099-9903	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		CHECKED - JMH	REVISED -			341	2011-065-BR	WILL	33	29	
	PLOT SCALE =	DRAWN - PRH	REVISED -			CONTRACT NO. 60P84					
	PLOT DATE =	CHECKED - AMS	REVISED -			ILLINOIS FED. AID PROJECT					
					SHEET NO. S2 OF S4 SHEETS						