



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 7, 2012

SUBJECT: FAP Route 341 (IL 72)
Project HSIP-0341(055)
Section 2011-071-N
Cook & Kane Counties
Contract No. 60P90
Item No. 013, June 15, 2012 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised pages 4 & 5 of the Special Provisions, revising the Completion Date.
3. Revised sheets 1-8 & 34-37 of the Plans
4. Deleted sheets 38-42 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Bureau Chief of Design and Environment

A handwritten signature in cursive, reading "Ted B. Walschleger" followed by "P.E." in a smaller font.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Mike Renner; Estimates

TBW/MS/III

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER -

60P90

State Job # - C-91-628-11

County Name - COOK- KANE-

Code - 31 - 89 -

District - 1 - 1 -

Section Number - 2011-071-N

Project Number
HSIP-0341/055/

Route
FAP 341

*REVISED: JUNE 7, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*DELETE X0323927	MAINTAIN LIGHTING SYS	EACH	1.000				
X0324085	EM VEH P S LSC 20 3C	FOOT	1,170.000				
X5537800	SS CLEANED 12	FOOT	132.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X8360110	LIGHT POLE FDN SPL	FOOT	27.000				
X8570226	FAC T4 CAB SPL	EACH	1.000				
X8620200	UNINTER POWER SUP SPL	EACH	2.000				
X8710024	FOCC62.5/125 MM12SM24	FOOT	2,144.000				
X8950305	REMOV EX SIG HEAD	EACH	12.000				
Z0018500	DRAINAGE STR CLEANED	EACH	11.000				
Z0030850	TEMP INFO SIGNING	SQ FT	78.000				
*DELETE Z0033020	LUM SFTY CABLE ASMBLY	EACH	12.000				
*ADD Z0033028	MAINTAIN LIGHTING SYS	CAL MO	4.000				
Z0033046	RE-OPTIMIZE SIG SYS 2	EACH	2.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60P90

State Job # - C-91-628-11

County Name - COOK- KANE-

Code - 31 - 89 -

District - 1 - 1 -

Section Number - 2011-071-N

Project Number
HSIP-0341/055/

Route
FAP 341

*REVISED: JUNE 7, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20200100	EARTH EXCAVATION	CU YD	793.000				
20800150	TRENCH BACKFILL	CU YD	12.000				
21101615	TOPSOIL F & P 4	SQ YD	2,862.000				
21400100	GRADING & SHAP DITCH	FOOT	392.000				
25000400	NITROGEN FERT NUTR	POUND	3.900				
25000500	PHOSPHORUS FERT NUTR	POUND	3.900				
25000600	POTASSIUM FERT NUTR	POUND	3.900				
25200110	SODDING SALT TOLERANT	SQ YD	2,862.000				
28000305	TEMP DITCH CHECKS	FOOT	125.000				
28000400	PERIMETER EROS BAR	FOOT	1,367.000				
28000510	INLET FILTERS	EACH	25.000				
30300112	AGG SUBGRADE IMPR 12	SQ YD	1,394.000				
31200502	STAB SUBBASE HMA 4.5	SQ YD	438.000				
35501314	HMA BASE CSE 7 1/2	SQ YD	816.000				
40600215	P BIT MATLS PR CT	TON	2.400				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60P90

State Job # - C-91-628-11

County Name - COOK- KANE-

Code - 31 - 89 -

District - 1 - 1 -

Section Number - 2011-071-N

Project Number
HSIP-0341/055/

Route
FAP 341

*REVISED: JUNE 7, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600300	AGG PR CT	TON	12.000				
40600400	MIX CR JTS FLANGEWYS	TON	9.000				
40600825	P LEV BIND MM N50	TON	36.000				
40600982	HMA SURF REM BUTT JT	SQ YD	61.000				
40600985	PCC SURF REM BUTT JT	SQ YD	429.000				
40603240	P HMA BC IL19.0 N90	TON	103.000				
40603595	P HMA SC "F" N90	TON	676.000				
42000511	PCC PVT 10 1/2 JOINTD	SQ YD	438.000				
42001300	PROTECTIVE COAT	SQ YD	751.000				
42400200	PC CONC SIDEWALK 5	SQ FT	76.000				
44000100	PAVEMENT REM	SQ YD	29.000				
44000157	HMA SURF REM 2	SQ YD	4,462.000				
44000500	COMB CURB GUTTER REM	FOOT	1,030.000				
44003100	MEDIAN REMOVAL	SQ FT	4,460.000				
44004250	PAVED SHLD REMOVAL	SQ YD	534.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60P90

State Job # - C-91-628-11

County Name - COOK- KANE-

Code - 31 - 89 -

District - 1 - 1 -

Section Number - 2011-071-N

Project Number
HSIP-0341/055/

Route
FAP 341

*REVISED: JUNE 7, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44201765	CL D PATCH T2 10	SQ YD	120.000				
44213204	TIE BARS 3/4	EACH	270.000				
44300200	STRIP REF CR CON TR	FOOT	829.000				
48101200	AGGREGATE SHLDS B	TON	78.000				
54390160	INSERT CUL LIN 21	FOOT	145.000				
*ADD 60107600	PIPE UNDERDRAINS 4	FOOT	75.000				
60211800	CB TD 4 DIA T1F CL	EACH	2.000				
60212813	CB TD 4 DIA T23F&G	EACH	1.000				
60237460	INLETS TA T23F&G	EACH	1.000				
60250500	CB ADJ NEW T1F CL	EACH	1.000				
60255500	MAN ADJUST	EACH	1.000				
60500060	REMOV INLETS	EACH	3.000				
60604400	COMB CC&G TB6.18	FOOT	501.000				
60619600	CONC MED TSB6.12	SQ FT	1,759.000				
66900200	NON SPL WASTE DISPOSL	CU YD	563.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60P90

State Job # - C-91-628-11

County Name - COOK- KANE-

Code - 31 - 89 -

District - 1 - 1 -

Section Number - 2011-071-N

Project Number
 HSIP-0341/055/

Route
 FAP 341

*REVISED: JUNE 7, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	2.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				
70102635	TR CONT & PROT 701701	L SUM	1.000				
70300100	SHORT TERM PAVT MKING	FOOT	365.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	219.000				
70300220	TEMP PVT MK LINE 4	FOOT	4,018.000				
70300240	TEMP PVT MK LINE 6	FOOT	1,410.000				
70300260	TEMP PVT MK LINE 12	FOOT	665.000				
70300280	TEMP PVT MK LINE 24	FOOT	128.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	61.000				
72000100	SIGN PANEL T1	SQ FT	49.000				
72800100	TELES STL SIN SUPPORT	FOOT	41.000				
*REV 78000100	THPL PVT MK LTR & SYM	SQ FT	328.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60P90

State Job # - C-91-628-11
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 2011-071-N

Project Number
 HSIP-0341/055/

Route
 FAP 341

*REVISED: JUNE 7, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78000200	THPL PVT MK LINE 4	FOOT	4,018.000				
*REV 78000400	THPL PVT MK LINE 6	FOOT	1,477.000				
78000600	THPL PVT MK LINE 12	FOOT	665.000				
78000650	THPL PVT MK LINE 24	FOOT	128.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	37.000				
78008210	POLYUREA PM T1 LN 4	FOOT	400.000				
78008230	POLYUREA PM T1 LN 6	FOOT	400.000				
78008270	POLYUREA PM T1 LN 24	FOOT	36.000				
78100100	RAISED REFL PAVT MKR	EACH	86.000				
78300100	PAVT MARKING REMOVAL	SQ FT	2,263.000				
78300200	RAISED REF PVT MK REM	EACH	25.000				
*DELETE 80400100	ELECT SERV INSTALL	EACH	1.000				
*DELETE 80400200	ELECT UTIL SERV CONN	L-SUM	1.000		3,000.000		3,000.000
80500020	SERV INSTALL POLE MT	EACH	1.000				
81028200	UNDRGRD C GALVS 2	FOOT	40.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60P90

State Job # - C-91-628-11
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 2011-071-N

Project Number
 HSIP-0341/055/

Route
 FAP 341

*REVISED: JUNE 7, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*REV 81028220	UNDRGRD C GALVS 3	FOOT	145.000				
81028240	UNDRGRD C GALVS 4	FOOT	158.000				
81400100	HANDHOLE	EACH	2.000				
81400200	HD HANDHOLE	EACH	1.000				
81603040	UD 2#6 #8G XLPUSE 1	FOOT	385.000				
*DELETE 81603050	UD 3#6 #8G XLPUSE 1	FOOT	2,550.000				
*DELETE 82402400	LUM SV HOR MT 400W	EACH	12.000				
*DELETE 82500330	LT CONT PEDM 240V 60	EACH	1.000				
*DELETE 83050810	LT P A 47.5MH 15MA	EACH	12.000				
*DELETE 83600200	LIGHT POLE FDN 24D	FOOT	108.000				
*DELETE 83800205	BKWY DEV TR B 15BC	EACH	12.000				
84200804	REM POLE FDN	EACH	3.000				
84400105	RELOC EX LT UNIT	EACH	3.000				
*ADD 8440405	RELOC EX WOOD POLES	EACH	1.000				
86400100	TRANSCEIVER - FIB OPT	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60P90

State Job # - C-91-628-11

County Name - COOK- KANE-

Code - 31 - 89 -

District - 1 - 1 -

Section Number - 2011-071-N

Project Number
HSIP-0341/055/

Route
FAP 341

*REVISED: JUNE 7, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87301215	ELCBL C SIGNAL 14 2C	FOOT	3,034.000				
87301225	ELCBL C SIGNAL 14 3C	FOOT	1,587.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	5,112.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	529.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	4,851.000				
87301805	ELCBL C SERV 6 2C	FOOT	96.000				
87301900	ELCBL C EGRDC 6 1C	FOOT	567.000				
87502440	TS POST GALVS 10	EACH	1.000				
87502480	TS POST GALVS 14	EACH	1.000				
87700180	S MAA & P 28	EACH	1.000				
87700200	S MAA & P 32	EACH	1.000				
87700210	S MAA & P 34	EACH	1.000				
87700260	S MAA & P 44	EACH	1.000				
87800100	CONC FDN TY A	FOOT	8.000				
87800150	CONC FDN TY C	FOOT	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60P90

State Job # - C-91-628-11

County Name - COOK- KANE-

Code - 31 - 89 -

District - 1 - 1 -

Section Number - 2011-071-N

Project Number
 HSIP-0341/055/

Route
 FAP 341

*REVISED: JUNE 7, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87800400	CONC FDN TY E 30D	FOOT	10.000				
87800415	CONC FDN TY E 36D	FOOT	35.000				
88030020	SH LED 1F 3S MAM	EACH	12.000				
88030050	SH LED 1F 3S BM	EACH	5.000				
88030100	SH LED 1F 5S BM	EACH	1.000				
88030110	SH LED 1F 5S MAM	EACH	2.000				
88030210	SH LED 2F 3S BM	EACH	1.000				
88030240	SH LED 2F 1-3 1-5 BM	EACH	1.000				
88030310	SH LED 3F 3S BM	EACH	1.000				
88102717	PED SH LED 1F BM CDT	EACH	2.000				
88200210	TS BACKPLATE LOU ALUM	EACH	14.000				
88500100	INDUCTIVE LOOP DETECT	EACH	8.000				
88600100	DET LOOP T1	FOOT	496.000				
88600700	PREFORM DETECT LOOP	FOOT	129.000				
88700200	LIGHT DETECTOR	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60P90

State Job # - C-91-628-11

County Name - COOK- KANE-

Code - 31 - 89 -

District - 1 - 1 -

Section Number - 2011-071-N

Project Number
 HSIP-0341/055/

Route
 FAP 341

*REVISED: JUNE 7, 2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
88700300	LIGHT DETECTOR AMP	EACH	3.000				
88800100	PED PUSH-BUTTON	EACH	2.000				
89000100	TEMP TR SIG INSTALL	EACH	1.000				
89502300	REM ELCBL FR CON	FOOT	2,144.000				
89502375	REMOV EX TS EQUIP	EACH	1.000				
89502380	REMOV EX HANDHOLE	EACH	2.000				
89502385	REMOV EX CONC FDN	EACH	5.000				

MAINTENANCE OF ROADWAYS

Effective: September 30, 1985

Revised: November 1, 1996

Beginning on the date that work begins on this project, the Contractor shall assume responsibility for normal maintenance of all existing roadways within the limits of the improvement. This normal maintenance shall include all repair work deemed necessary by the Engineer, but shall not include snow removal operations. Traffic control and protection for maintenance of roadways will be provided by the Contractor as required by the Engineer.

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the Standard Specifications.

STATUS OF UTILITIES TO BE ADJUSTED

Effective: January 30, 1987

Revised: July 1, 1994

Utility companies involved in this project have provided the following estimated dates:

<u>Name of Utility</u>	<u>Type</u>	<u>Location</u>	<u>Estimated Dates for Start and Completion of Relocation or Adjustments</u>
AT&T	Aerial pole	- SE corner of IL 72 & Beverly, 1 aerial drop crossing Beverly	During construction.
AT&T	Duct Run	East side of Beverly Rd crossing IL 72 to the north.	During construction.

The above represents the best information available to the Department and is included for the convenience of the bidder. The applicable portions of Articles 105.07 and 107.31 of the Standard Specifications shall apply.

COMPLETION DATE PLUS WORKING DAYS

Effective: September 30, 1985

Revised: January 1, 2007

Revise Article 108.05 (b) of the Standard Specifications as follows:

"When a completion date plus working days is specified, the Contractor shall complete all contract items and safely open all roadways to traffic by 11:59 PM on, December 31, 2012 except as specified herein.

The Contractor will be allowed to complete all clean-up work and punch list items within 5 working days after the completion date for opening the roadway to traffic. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the working days allowed for clean up work a punch list items.

Revised 06/07/12

Temporary lane closures for this work may be allowed at the discretion of the Engineer.

(*The interim completion date for all road and drainage work shall be October 31, 2012.*)

Article 108.09 or the Special Provision for "Failure to Complete the Work on Time", if included in this contract, shall apply to both the completion date and the number of working days.

AGGREGATE SUBGRADE IMPROVEMENT (D-1)

Effective: February 22, 2012

Add the following Section to the Standard Specifications:

"SECTION 303. AGGREGATE SUBGRADE IMPROVEMENT

303.01 Description. This work shall consist of constructing an aggregate subgrade improvement.

303.02 Materials. Materials shall be according to the following.

Item	Article/Section
(a) Coarse Aggregate	1004.06
(b) Reclaimed Asphalt Pavement (RAP) (Notes 1, 2)	1031

Note 1. Crushed RAP, from either full depth or single lift removal, may be mechanically blended with aggregate gradations CS 01 or CS 02 but shall not exceed 40 percent of the total product. The top size of the RAP shall be less than 4 in. (100 mm) and well graded.

Note 2. RAP having 100 percent passing the 1 1/2 in. (37.5 mm) sieve and being well graded, may be used as capping aggregate in the top 3 in. (75 mm) when aggregate gradations CS 01 or CS 02 are used in lower lifts.

303.03 Equipment. The vibratory machine shall be according to Article 1101.01, or as approved by the Engineer.

303.04 Soil Preparation. The stability of the soil shall be according to the Department's Subgrade Stability Manual for the aggregate thickness specified.

303.05 Placing Aggregate. The maximum nominal lift thickness of aggregate gradations CS 01 or CS 02 shall be 24 in. (600 mm).

303.06 Capping Aggregate. The top lift of the aggregate subgrade shall consist of a minimum 3 in. (75 mm) of aggregate gradations CA 06 or CA 10. When Reclaimed Asphalt Pavement (RAP) is used, it shall be crushed and screened where 100 percent is passing the 1 1/2 in. (37.5 mm) sieve and being well graded. Gap graded, single size, maximum size of 5/8 in, 1/2 in. or 3/8 in. will not be permitted.

303.07 Compaction. All aggregate lifts shall be compacted to the satisfaction of the Engineer. If the moisture content of the material is such that compaction cannot be obtained, sufficient water shall be added so that satisfactory compaction can be obtained.

Revised 06/07/12