

SUMMARY OF QUANTITIES

LS3EL LS3EL LS3EL LS3EL LS3EL 07POL

CONSTRUCTION TYPE CODE

ROADWAY BEVERLY RD	BEVERLY RD TRAFFIC SIGNAL	ROCK RD DR TRAFFIC SIGNAL	INTERCONNECT	BEVERLY RD LIGHTING RELOC. COOK	EMERGENCY VEHICLE PRE-EMPTION (EVP) DEVICE COOK
COOK	COOK	KANE	COOK	COOK	COOK
90% FED 10% STATE	90% FED 6.67% STATE 3.33% VHE	90% FED 6.67% STATE 3.33% VED	90% FED 10% STATE	90% FED 10% STATE	100% VHE
0005	0021 .01	0021 .01	0021 .02	0021 .03	0021 .01

VHE = VILLAGE OF HOFFMAN ESTATES
VED = VILLAGE OF EAST DUNDEE

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	793
20000150	TRENCH BACKFILL	CU YD	12
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	2862
21400100	GRADING AND SHAPING DITCHES	FOOT	392
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3.9
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3.9
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3.9
25200110	SODDING, SALT TOLERANT	SO YD	2862
28000305	TEMPORARY DITCH CHECKS	FOOT	125
28000400	PERIMETER EROSION BARRIER	FOOT	1367
28000510	INLET FILTERS	EACH	25
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	1394
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SO YD	438
35501314	HOT-MIX ASPHALT BASE COURSE, 7 1/2"	SO YD	816
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	2.4
40600300	AGGREGATE (PRIME COAT)	TON	12
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	9
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	36
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SO YD	61
40600985	CONCRETE SURFACE REMOVAL-BUTT JOINT	SO YD	429
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N90	TON	103
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	676
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SO YD	438
42001300	PROTECTIVE COAT	SO YD	751
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	76
44000100	PAVEMENT REMOVAL	SO YD	29
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	4462
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1030

FILE NAME: p:\2009\vee09086-ver-or phi\cadd\0308-IL72-Beverly\Shs\03-0168P98-ah-t-500.dgn
 PLOT SCALE: 1"=40'-0"
 USER NAME: Millenria Professional Services

Rev. 6-4-12

SPECIALTY ITEM Rex.



200 225D Street, Suite 216, Lombard, IL 60148
 630.785.8110 voice, 630.839.2566 fax
 www.mps-ll.com
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 4/6/2012	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**IL 72 - HIGGINS RD
 AT BEVERLY RD AND AT ROCK ROAD DR**

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
341	2011-071-N	COOK/KANE	96	3
CONTRACT NO. 60P90			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

SCALE: SHEET NO. OF SHEETS STA. TO STA.

p:\2009\vee09086-ver-or phi\cadd\0308-IL72-Beverly\Shs\03-0168P98-ah-t-500.dgn