

**SUMMARY OF QUANTITIES**

**CONSTRUCTION TYPE CODE**

BEVERLY RD LIGHTING RELOC.  
COOK  
90% FED.  
10% STATE

VHE = VILLAGE OF HOFFMAN ESTATES  
VED = VILLAGE OF EAST DUNDEE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY BEVERLY RD	BEVERLY RD TRAFFIC SIGNAL	ROCK RD DR TRAFFIC SIGNAL	INTERCONNECT	BEVERLY RD LIGHTING RELOC. COOK	EMERGENCY VEHICLE PRE-EMPTION (EVP) DEVICE COOK
				90% FED 10% STATE	90% FED 6.67% STATE 3.33% VHE	90% FED 6.67% STATE 3.33% VED	90% FED 10% STATE	90% FED. 10% STATE	100% VHE
44003100	MEDIAN REMOVAL	SO FT	4460	0005 4460	0021	0021	0021	0021	0021
44004250	PAVED SHOULDER REMOVAL	SO YD	534	534					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	120	120					
44213204	TIE BARS 3/4"	EACH	270	270					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	829	829					
48101200	AGGREGATE SHOULDER, TYPE B	TON	78	78					
54390160	INSERTION CULVERT LINER 21"	FOOT	145	145					
60107600	PIPE UNDERDRAINS 4"	FOOT	75	75					
60211800	CATCH BASINS, TYPE D, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
60212813	CATCH BASINS, TYPE D, 4' -DIAMETER, TYPE 23 FRAME AND GRATE	EACH	1	1					
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	1	1					
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1					
60500060	REMOVING INLETS	EACH	3	3					
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	501	501					
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SO FT	1759	1759					
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	563	563					
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1			1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	365	365					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	219	219					

FILE NAME : p:\2009\me9086.var\var\_phi\lead\W038\_IL72.Beverly\Shs\03-0168P90-ahc-500.dgn  
 USER : JIN  
 DATE : 4/16/2012



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.705.0110 voice, 630.839.2566 fax  
 www.mps-ill.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 4/16/2012	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**IL 72 - HIGGINS RD  
 AT BEVERLY RD AND AT ROCK ROAD DR**

**SUMMARY OF QUANTITIES**

F.A.P. RTE. 341	SECTION 2011-071-N	COUNTY COOK/KANE	TOTAL SHEETS 96	SHEET NO. 4
CONTRACT NO. 60P90			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

Rev. 6-4-12 • SPECIALTY ITEM

p:\2009\me9086.var\var\_phi\lead\W038\_IL72.Beverly\Shs\03-0168P90-ahc-500.dgn