

SCHEDULE OF QUANTITIES

	DESIGNATION	UNIT	TOTAL QUANTITY
▲	ELECTRIC SERVICE INSTALLATION	EACH	1
	ELECTRIC UTILITY SERVICE CONNECTION	L-SUM	1
	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	222
	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	385
▲	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2700
	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	12
	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	1
	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	12
	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	108
	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	12
	REMOVAL OF POLE FOUNDATION	EACH	3
	RELOCATE EXISTING LIGHTING UNIT	EACH	3
	* MAINTENANCE OF LIGHTING SYSTEM	CAL MO	4
	* LIGHT POLE FOUNDATION, SPECIAL	FOOT	27
▲	* LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	12

* DESIGNATES SPECIAL PROVISIONS

FILE NAME = I:\projects\projects 2011\millema\various\ill rte 72 at beverly rd\0168P90-Lighting 2.dgn
 PLOT SCALE = AS SCALE
 USER NAME =



GANDHI AND ASSOCIATES, INC.
 ENGINEERS AND PLANNERS
 6035 N. NORTHWEST HIGHWAY
 SUITE 305
 CHICAGO, ILLINOIS 60631 TEL. (773) 774-590

DESIGNED - SM	REVISED - ▲ 05/24/12- ADDENDUM
DRAWN - SM	REVISED -
CHECKED - PKG/MA	REVISED -
DATE - 5/24/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 72 - HIGGINS RD
AT BEVERLY RD AND AT ROCK ROAD DR

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
341	2011-071-N	COOK/KANE	56	35
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 60P90	

I:\projects\projects 2011\millema\various\ill rte 72 at beverly rd\0168P90-Lighting 2.dgn