

**SUMMARY OF QUANTITIES**

**URBAN**

**CONSTRUCTION TYPE CODE**

VHE = VILLAGE OF HOFFMAN ESTATES  
VED = VILLAGE OF EAST DUNDEE

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY BEVERLY RD	BEVERLY RD TRAFFIC SIGNAL	ROCK RD DR TRAFFIC SIGNAL	INTERCONNECT	BEVERLY RD LIGHTING	EMERGENCY VEHICLE PRE-EMPTION (EVP) DEVICE
				COOK	COOK	KANE	COOK	COOK	COOK
				90% FED 10% STATE	90% FED 6.67% STATE 3.33% VHE	90% FED 6.67% STATE 3.33% VED	90% FED 10% STATE	100% VHE	100% VHE
				0005	0021	0021	0021	0021	0021
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4018	4018					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1410	1410					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	665	665					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	128	128					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	61	61					
72000100	SIGN PANEL - TYPE 1	SO FT	49	29	20				
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	41	41					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	219	219					
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4018	4018					
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1410	1410					
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	665	665					
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	128	128					
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SO FT	37	37					
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	400	400					
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	400	400					
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	36	36					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	86	86					
78300100	PAVEMENT MARKING REMOVAL	SO FT	2263	2263					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	25	25					
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1					1	
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1					1	
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1				
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	40		40				
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	367		145			222	
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	158		158				
81400100	HANDHOLE	EACH	2		2				
81400200	HEAVY-DUTY HANDHOLE	EACH	1		1				
81603040	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA <b>POLYETHYLENE</b>	FOOT	385					385	

• SPECIALTY ITEM

FILE NAME = p:\2009\m09086\var\var phi\cadd\w038.il72.Beverly\Shets\03-0168P98-ant-S00.dgn  
 PLOT SCALE = 2.0000 / 1 IN.  
 USER NAME = Millennium Professional Services



290 22ND Street, Suite 216, Lombard, IL 60148  
 630.785.8118 voice, 630.839.2566 fax  
 www.mps-il.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 4/6/2012	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**IL 72 - HIGGINS RD**  
**AT BEVERLY RD AND AT ROCK ROAD DR**  
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 341	SECTION 2011-071-N	COUNTY COOK/KANE	TOTAL SHEETS 56	SHEET NO. 5
CONTRACT NO. 60P90			FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT	

p:\2009\m09086\var\var phi\cadd\w038.il72.Beverly\Shets\03-0168P98-ant-S00.dgn