

LS3EL,01

LS3EL,02

LS3EL,03

LS3EL,04

SUMMARY OF QUANTITIES

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL	GOLF ROAD AT LAWLER AVENUE	GOLF ROAD AT LAVERGNE AVENUE	GROSS POINT ROAD AT CHURCH STREET	U.S. RTE 41 (SKOKIE BOULEVARD) AT CHURCH STREET	U.S. RTE 41 (SKOKIE BOULEVARD) AT GROSS POINT ROAD	INTERCONNECT	LIGHTING - GROSS POINT ROAD AT CHURCH STREET	LIGHTING - U.S. RTE 41 (SKOKIE BOULEVARD) AT GROSS POINT ROAD
				90% FEDERAL 5% STATE 5% VILLAGE OF SKOKIE	90% FEDERAL 5% STATE 5% VILLAGE OF SKOKIE	90% FEDERAL 5% STATE 5% VILLAGE OF SKOKIE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% VILLAGE OF SKOKIE	90% FEDERAL 10% VILLAGE OF SKOKIE
				TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	INTERCONNECT	LIGHTING	LIGHTING
				0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN
20200100	EARTH EXCAVATION	CU YD	19	6	8	3	2				
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	46	15	17	8	6				
31101600	SUBBASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	111					111			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8,005	905	780	1,770	1,550	3,000			
42400800	DETECTABLE WARNINGS	SQ FT	572	80	76	116	104	196			
44000100	PAVEMENT REMOVAL	SQ YD	107					107			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	610	116		187	154	153			
44000600	SIDEWALK REMOVAL	SQ FT	5,325	655	590	1,705	1,515	860			
44003100	MEDIAN REMOVAL	SQ FT	795					795			
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	14					14			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	2	2		1	2			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	789	116	119	187	154	213			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	135					135			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1,000					1,000			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8.00	1.50	1.50	1.50	1.50	1.50	0.50		
67100100	MOBILIZATION	L SUM	1.00	0.20	0.20	0.20	0.20	0.20			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.00	0.20	0.20	0.20	0.20	0.20			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1.00	0.20	0.20	0.20	0.20	0.20			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.00	0.20	0.20	0.20	0.20	0.20			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.00	0.20	0.20	0.20	0.20	0.20			
** 72000100	SIGN PANEL - TYPE 1	SQ FT	87.00	27.00	30.00	15.00	15.00				

*100% OF THE COST SHALL BE PAID BY VILLAGE OF SKOKIE (07PDL,01,0021) ** SPECIALTY ITEM

FILE NAME = 4085.877-TR1.dwg	USER NAME = ZACH WALLSTEN	DESIGNED - JRD	REVISED -
		DRAWN - ZCW	REVISED -
		CHECKED - KLB	REVISED -
		DATE - 3/22/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES (SHEET 1 OF 5)			
SCALE: N.A.	SHEET NO. OF SHEETS	STA.	TO STA.

FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VARIES	2011-209-TS	COOK	52	3
CONTRACT #:			60R47	
ILLINOIS FED. AID PROJECT				

GHA #4085.877