

SUMMARY OF QUANTITIES		URBAN		ILL ROUTE 58 (GOLF ROAD) AT DEE ROAD		ILL ROUTE 58 (GOLF ROAD) AT WESTERN AVENUE		INTERCONNECT - ILL ROUTE 58 (GOLF ROAD) FROM POTTER ROAD TO GREENWOOD AVENUE	
		TYPE		TRAFFIC SIGNALS		TRAFFIC SIGNALS		INTERCONNECT	
CODE NO.	ITEM	UNIT	TOTAL	90% FEDERAL 5% STATE 2.5% VILLAGE 2.5% TOWNSHIP	0021 100% VILLAGE OF NILES	90% FEDERAL 5% STATE 5% VILLAGE	0021 100% VILLAGE OF NILES	0021 100% STATE	0021 100% VILLAGE OF NILES
20200100	EARTH EXCAVATION	CU YD	45	15		30			
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	128	40		88			
** 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2,890	1,310		1,580			
** 42400800	DETECTABLE WARNINGS	SQ FT	204	96		108			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	341	178		163			
44000600	SIDEWALK REMOVAL	SQ FT	1,760	965		795			
44003100	MEDIAN REMOVAL	SQ FT	115			115			
** 44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	8			8			
** 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	178	178					
** 60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	158			158			
60624600	CORRUGATED MEDIAN	SQ FT	47			47			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5.00	2.00		2.00		1.00	
67100100	MOBILIZATION	L SUM	1.00	0.40		0.40		0.20	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.00	0.40		0.40		0.20	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1.00	0.40		0.40		0.20	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.00	0.40		0.40		0.20	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.00	0.40		0.40		0.20	
** 72000100	SIGN PANEL - TYPE 1	SQ FT	28.50	12.00		16.50			
** 72000200	SIGN PANEL - TYPE 2	SQ FT	50.00	25.00		25.00			
** 78008200	POLYUREA PAVEMENT MARKING TYPE I- LETTERS AND SYMBOLS	SQ FT	145.60	72.80		72.80			
** 78008230	POLYUREA PAVEMENT MARKING TYPE I- LINE 6"	FOOT	65			65			
** 78008250	POLYUREA PAVEMENT MARKING TYPE I- LINE 12"	FOOT	978	450		528			
** 78008270	POLYUREA PAVEMENT MARKING TYPE I- LINE 24"	FOOT	231	114		117			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	360	130		230			
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2	1		1			
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	914	526		388			
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	68	22		46			
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	112	47		65			
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	771	368		403			
81400100	HANDHOLE	EACH	5	2		3			
81400200	HEAVY-DUTY HANDHOLE	EACH	5	3		2			
81400300	DOUBLE HANDHOLE	EACH	4	2		2			
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3					3	
86400100	TRANSCIVER - FIBER OPTIC	EACH	2	1		1			
87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	5,903					5,903	
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5,903					5,903	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2,212	1,049		1,163			
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2,896	1,387		1,509			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3,462	1,634		1,828			

\*\* 66900200 NON-SPECIAL WASTE DISPOSAL CU YD 26 10.4 15.6  
 \*\* 66900450 SPECIAL WASTE PLANS AND REPORTS L SUM 1 0.5 0.5  
 \*\* 66900530 SOIL DISPOSAL ANALYSIS EACH 5 2 3

\* 100% VILLAGE OF NILES  
 \*\* SPECIALTY ITEMS

Rev.

FILE NAME = 4085.879-TR1.dwg	USER NAME = ZACH WALLSTEN	DESIGNED - JRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES - ILL ROUTE 58 (GOLF ROAD) F.A.P. 339 AT DEE ROAD & WESTERN AVENUE (1 OF 2)	F.A.P. RTE. 339	SECTION 2011-211-TS	COUNTY COOK	TOTAL SHEETS 26	SHEET NO. 3
PLOT SCALE = 1" = .0833'	PLOT DATE = 2/1/2012	DRAWN - ZCW	REVISED -			SCALE N.A.	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT # 60R51	
CHECKED - KLB	DATE - 2/1/2012	REVISED -	REVISED -			ILLINOIS FED. AID PROJECT		CHA #4085.879		