ROUTE: III	_ 83 (Valley Vie	w Dr. to Bluff R	d.)				
CROSS S	TREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD)
Valley View Dr.	Bluff Rd.	N/B	1	12	20	240	27
		N/B	2	12	20	240	27
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	25	300	33
		N/B	2	12	25	300	33
		N/B	1	12	20	240	27
		N/B	2	12	20	240	27
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	Joint	3	200	600	67
		N/B	Joint	3	210	630	70
		N/B	1	6	30	180	20
		N/B	1	12	10	120	13
		N/B	2	12	10	120	13
		N/B	1 2	12	6	72 72	8
		N/B N/B		12	6	72	
		N/B	1 2	12 12	6 6	72	8
		N/B	∠ Joint	3	60	180	20
	Bluff Rd.	N/B	2	6	20	120	13
Valley View Dr.	Diuli Ku.	S/B	1	6	15	90	10
		S/B S/B	1	12	10	120	13
		S/B	2	12	10	120	13
		S/B	1	12	10	120	13
		S/B	2	12	10	120	13
		S/B	Joint	3	100	300	33
		S/B	1	12	25	300	33
		S/B	2	12	30	360	40
		S/B	1	12	40	480	53
		S/B	2	12	40	480	53
		S/B	1	12	8	96	11
		S/B	2	12	8	96	11
		S/B	1	12	25	300	33
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	1	12	10	120	13
		S/B	2	12	10	120	13
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	1	12	15	180	20
		S/B	2	12	15	180	20
		S/B	2	6	15	90	10
	Bluff Rd.	S/B	1	12	6	72	8
		TOTALS:			1198		974

ROUTE	IL 83 (Midway Dr	. to 63rd St.)					
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIF
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD
Midway Dr.		N/B	1	12	6	72	8
Wildway DI.		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	15	180	20
		N/B	1	12	10	120	13
		N/B	2	12	10	120	13
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	2	12	50	600	67
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	1	12	8	96	11
		N/B	2	12	40	480	53
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	15	180	20
		N/B	2	12	15	180	20
		N/B	1	12	8	96	11
		N/B	2	12	8	96	11
		N/B	1	12	10	120	13
		N/B	2	12	10	120	13
		N/B	1	12	10	120	13
		N/B	2	12	10	120	13
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B		12	6	72	8
			1				
		N/B	2	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	1	12	15	180	20
	63rd St.	N/B	2	12	15	180	20

Continued on next sheet

FILE NAME =	USER NAME = pencep1	DESIGNED -	REVISED -		PATCHING SCHEDULE IL 83					F.A	SECTION	COUNTY	TOTAL SHEET	
c:\pw_work\pwidot\pencepl\d0303630\Dl39	12-Design.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS							VAR.	2012-013 RS	DUPAGE	31 14
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION									CONTRACT NO. 60T59	
	PLOT DATE = 4/10/2012	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			