ROUTE:	ROUTE: IL 83 (IL 64 to Devon Ave.)			(Continued)			
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD)
Hillside Dr.		N/B	1	12	6	72	. 8
		N/B	2	12	6	72	8
		N/B	3	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	3	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	3	12	6	72	8
		N/B	1	12	6	72	8
	Thorndale ave.	N/B	2	12	6	72	8
horndale ave.		N/B	3	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	3	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
		N/B	3	12	6	72	8
		N/B	1	12	6	72	8
		N/B	2	12	6	72	8
	Devon Ave.	N/B	3	12	6	72	8
Devon ave		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B S/B	2	12 12	6 6	72 72	8 8
		S/B	3	12	6	72	8
		S/B	2	12	50	600	67
	Thorndale ave	S/B	3	6	50	300	33
Thorndale ave	momuale ave	S/B	1	12	30	360	40
mornale ave		S/B	1	12	10	120	13
		S/B	2	12	10	120	13
		S/B	2	12	15	180	20
		S/B	3	12	15	180	20
		S/B	3	6	100	600	67
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
	Foster ave	S/B	1	12	6	72	8

NOO1L.	IL 83 (IL 64 to Dev	on / (vc.)		(Continued)			
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
Thorndale ave		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B S/B	2	12	6	72	8
	-	S/B S/B	3	12	6	72 72	8
		S/B S/B		12	6	72	8
	-		1				
		S/B	2	12	6	72	8
	-	S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
	Foster ave	S/B	2	12	6	72	8
Foster ave		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
	 	S/B	2	12	6	72	8
		S/B	3	12	6	72	8
	 	S/B	1	12	6	72	8
	 	S/B	2	12	6	72	8
		S/B S/B	3	12	6	72	8
		S/B S/B	1	12	6	72	8
	-						
		S/B	2	12	6	72	8
	1	S/B	3	12	6	72	8
	-	S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
	1		3	12	6	72	8
		1 5/5					
		S/B S/B	1	12	6	72	8

SCALE:

FILE NAME =	USER NAME = pencepl	DESIGNED -	REVISED -
c:\pw_work\pwidot\pencepl\d0303630\DI39	12-Design.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -
	PLOT DATE = 4/10/2012	DATE -	REVISED -

STATE OF ILLINOIS							
DEPARTMENT	0F	TRANSPORTATION					

PATCHING SCHEDULE IL 83					F.A RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
					VAR.	2012-013 RS	DUPAGE	31	17	
	IL 03							CONTRACT	NO. 6	OT59
	SHEET	OF	SHEETS	STA.	TO STA.	THE INDIS FED. AID PROJECT				