ROUTE:	IL 83 (IL 64 to Dev	on Ave.)	(Continued)				
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
TROW	10	(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD
Foster ave		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	1	12	20	240	27
		S/B	2	12	20	240	27
		S/B	3	12	20	240	27
		S/B	1	12	6	72	8
		S/B	2	12 12	6	72 72	8
		S/B S/B	3 1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	3	12	30	360	40
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	3	2	80	160	18
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	90	1080	120
		S/B	3	12	10	120	13
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
	Cha	S/B	2	12	6	72	8
hamus - J D	Sherwood Dr.	S/B	3	12	6	72	8
herwood Dr.		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B S/B	3 1	12 12	6 6	72 72	8 8
				1 17 1	6		

ROUTE:	IL 83 (IL 64 to Dev	on Ave.)		(Continued)			
		,		,			
CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD
Sherwood Dr.		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3 1	12	6	72	<u>8</u> 8
		S/B		12	6	72	
		S/B	2	12	6	72 72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	1	12	6	72	8
		S/B	2	12	6	72	8
		S/B	3	12	6	72	8
		S/B	3	5	50	250	28
		S/B	3	6	80	480	53
		S/B	3	6	100	600	67
	IL 64	S/B	3	6	120	720	80
		TOTALS:			4605		5208
					FT		SY

Continued on next sheet

FILE NAME =	USER NAME = pencepl	DESIGNED -	REVISED -
c:\pw_work\pwidot\pencepl\d0303630\D139	12-Design.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -
	PLOT DATE = 4/10/2012	DATE =	REVISED -

STATE OF ILLINOIS							
DEPARTMENT	0F	TRANSPORTATION					

PATCHING SCHEDULE						F.A RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	IL 83						VAR.	2012-013 RS	DUPAGE	31	18
									CONTRACT	NO. 6	60T59
	SCALE:	SHEET	OF	SHEETS	STA.	TO STA.		ILLINOIS FED. A	ID PROJECT		