ROOTE	: Dundee Rd. (Sanders R							
CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR	
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA	
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD	
Sanders Rd.		WB	1,2	24	3	72	8	
		WB	1,2,med	36	3	108	12	
		WB	1,2,med	36	3	108	12	
		WB	1,2,med	36	3	108	12	
		WB	1,2,med	36	3	108	12	
		WB	1	3	200	600	67	
		WB	1,2,med	30	3	90	10	
		WB	1,2,med	30	3	90	10	
		WB	1,2	26	3	78	9	
		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
	Tollway Bridge	WB	1	3	75	225	25	
Tollway Bridge		WB	1,2	24	3	72	8	
· · ·		WB	1,2	27	3	81	9	
		WB	1	3	100	300	33	
		WB	1,2	26	3	78	9	
		WB	1,2	24	3	72	8	
		WB	1,2	26	3	78	9	
		WB	1,2	26	3	78	9	
		WB	1,2	26	3	78	9	
		WB	1,2	26	3	78	9	
		WB	1,2	26	3	78	9	
		WB	1,2	26	3	78	9	
		WB	1	3	200	600	67	
		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
		WB	1,2	28	3	84	9	
		WB	1,2	30	3	90	9	
		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
	Portwine Rd.	WB	1,2	24	3	72	8	
Portwine Rd.		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
		WB	1,2	26	3	78	9	
		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
		WB	1,2	24	3	72	8	
	Des Plaines R. Bridge	WB	1,2	24	3	72	8	

ROUTE	: Dundee Rd. (Sanders R	d. to Milwauk	ee Ave.)	Continued)			
CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD
Sanders Rd.		EB	1,2	26	3	78	9
		EB	1,2	24	3	72	8
	Tollway Bridge	EB	1,2	24	3	72	8
Tollway Bridge		EB	1,2	24	3	72	8
· ·		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	26	3	78	9
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	3	250	750	83
	Portwine Rd.	EB	1,2	24	3	72	8
Portwine Rd.		EB	1,2	24	3	72	8
		EB	1	3	100	300	33
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1,2	24	3	72	8
		EB	1	3	200	600	67
	Des Plaines R. Bridge	EB	1,2	24	3	72	8
		TOTALS:			1323		937
					FT		SY

FILE NAME =	USER NAME = chrzasclr	DESIGNED -	REVISED -		PATCHING SCHEDULE DUNDEE RD.					F.A RTF.	SECTION	COUNTY	TOTAL SHEET SHEETS NO.
c:\pw_work\pwidot\chrzasclr\d0303692\D14		DRAWN -	REVISED -	STATE OF ILLINOIS						VAR.	2012-016 RS	СООК	33 18
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	DONDEL ND.						CONTRACT NO. 60T		
	PLOT DATE = 4/10/2012	DATE -	REVISED -		SCALE:	SHEET	OF SHEETS STA. TO STA.		. TO STA.	ILLINOIS FED. AID PROJECT			