

ROUTE: Asbury Ave. (Oakton St. to Howard St.)							
CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
Oakton		SB	1,2	2	300	600	67
		SB	1,2	2	50	100	11
		SB	1,2	2	700	1400	156
		SB	1,2	2	150	300	33
		SB	2	2	200	400	44
		SB	1,2	2	300	600	67
		NB	1,2	2	50	100	11
		NB	2	2	50	100	11
		NB	2	2	200	400	44
		NB	2	2	150	300	33
		NB	2	2	200	400	44
		NB	2	2	200	400	44
		NB	2	2	200	400	44
		NB	1,2	2	1000	2000	222
	Howard	NB	1,2	2	50	100	11
<b>TOTALS:</b>					<b>3600</b>		<b>800</b>
					<b>FT</b>		<b>SY</b>

ROUTE: Dempster St. (Fowler Ave. to Dodge Ave.)							
CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
Fowler		EB	2	2	100	200	22
		WB	2	2	100	200	22
		WB	2	4	10	40	4
		WB	2	2	200	400	44
		WB	2	2	200	400	44
		WB	2	2	150	300	33
		WB	2	2	150	300	33
		WB	2	2	50	100	11
		EB	2	2	100	200	22
		EB	2	2	200	400	44
		EB	2	2	200	400	44
		EB	2	2	200	400	44
		EB	1	10	10	100	11
	Dodge	EB	2	10	50	500	56
<b>TOTALS:</b>					<b>1720</b>		<b>438</b>
					<b>FT</b>		<b>SY</b>

FILE NAME =	USER NAME = chrzesclr	DESIGNED -	REVISED -
c:\pwork\pwork\chrzesclr\d0303692\010012-Design.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>PATCHING SCHEDULE ASBURY AVE. &amp; DEMPSTER ST.</b>			
SCALE:	SHEET	OF	SHEETS
	STA.	TO	STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2012-016 RS	COOK	33	24
			CONTRACT NO. 60T62	
ILLINOIS FED. AID PROJECT				