

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				95TH ST AT CICERO AVE	95TH ST AT KOSTNER AVE
				90% FED 10% STATE	90% FED 10% STATE
				TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	5		5
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		4
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	17	4	13
88500100	INDUCTIVE LOOP DETECTOR	EACH	22	13	9
88600100	DETECTOR LOOP, TYPE I	FOOT	516		516
** 88700200	LIGHT DETECTOR	EACH	6	4	2
** 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2	1	1
88800100	PEDESTRIAN PUSH-BUTTON	EACH	16	8	8
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1
89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	1	1	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1019		1019
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	715		715
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2	1	1

\* SPECIALTY ITEMS                      \*\* 100% VILLAGE OF OAK LAWN

FILE NAME =  
MICROST1\352898\03-SUMMARY.DGN

USER NAME = JGC  
PLOT SCALE = NONE  
PLOT DATE = 10-21-11

DESIGNED - BPT  
DRAWN - JGC  
CHECKED - BPT  
DATE - 10-21-11

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
(SHEET 4 OF 6)**

SCALE: N.T.S.    SHEET NO. OF SHEETS    STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
029	2012-028 1S	COOK	26	6
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		CONTRACT NO. 60T81		