

15													
SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION													
QUENTIN AVENUE, LONG GROVE ROAD													
STATION	DISTANCE	EARTH EXCAVATION (CUT)	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SUBGRADE (PGES)	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	UNSUITABLE AREA	POROUS GRANULAR EMBANKMENT, SUBGRADE (PGES)	FURNISHED EXCAVATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL <sup>(1)</sup>	POROUS GRANULAR EMBANKMENT, SUBGRADE (PGES)	FURNISHED EXCAVATION <sup>(2)</sup>
(XX+XX)	(FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	(SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	AVG. (SQ. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)	(CU. FT.)
37+00	50	13	363	107	426	15	383	109	458	725	19,150	5,425	22,875
37+50	50	16	403	110	489	18	252	55	414	900	12,600	2,750	20,675
38+00	50	20	101	0	338	16	96	0	319	800	4,800	0	15,950
38+50	50	12	91	0	300	16	92	0	275	775	4,600	0	13,725
39+00	50	19	93	0	249	23	86	0	195	1,125	4,275	0	9,750
39+50	50	26	78	0	141	60	100	40	91	2,975	5,000	1,975	4,550
40+00	50	93	122	79	41	80	119	80	41	4,000	5,925	4,000	2,025
40+50	50	67	115	81	40	70	117	81	37	3,475	5,850	4,050	1,850
41+00	50	72	119	81	34	59	75	78	23	2,925	3,750	3,875	1,150
41+50	50	45	31	74	12	35	54	96	60	1,725	2,700	4,800	3,000
42+00	50	24	77	118	108	49	87	105	84	2,425	4,325	5,250	4,175
42+50	50	73	96	92	59	84	83	46	91	4,175	4,125	2,300	4,525
43+00	50	94	69	0	122	104	70	0	111	5,200	3,500	0	5,525
43+50	50	114	71	0	99	125	53	0	72	6,225	2,650	0	3,600
44+00	50	135	35	0	45	78	36	0	43	3,875	1,775	0	2,150
44+50	50	20	36	0	41	12	22	0	25	600	1,100	0	1,225
45+00	35	4	8	0	8	2	4	0	4	70	140	0	140
0+00	Intersection	0	0	0	0	32	37	35	3	1,575	1,825	1,725	150
0+50	50	63	73	69	6	47	63	78	28	2,325	3,125	3,875	1,400
1+00	50	30	52	86	50	38	60	84	46	1,875	3,000	4,175	2,275
1+50	50	45	68	81	41	35	79	82	52	1,725	3,950	4,075	2,575
2+00	50	24	90	82	62	15	93	116	60	750	4,650	5,800	2,975
2+50	50	6	96	150	57	6	657	116	657	275	32,825	5,800	32,850
3+00	50	5	1,217	82	1,257	3	1,031	41	1,261	125	51,525	2,050	63,050
3+50	50	0	844	0	1,265	2	684	0	1,216	75	34,175	0	60,800
4+00	25	3	523	0	1,167	3	320	0	955	63	8,000	0	23,875
4+25	25	2	117	0	743	3	102	0	531	75	2,550	0	13,275
4+50	20	4	87	0	319	10	87	0	228	190	1,740	0	4,550
4+70	30	15	87	0	136	19	84	0	147	570	2,505	0	4,410
5+00	50	23	80	0	158	22	84	0	148	1,075	4,200	0	7,375
5+50	50	20	88	0	137	17	86	0	126	825	4,275	0	6,275
6+00	50	13	83	0	114	27	105	51	73	1,325	5,250	2,550	3,650
6+50	50	40	127	102	32	62	103	133	49	3,075	5,150	6,625	2,450
7+00	50	83	79	163	66	47	94	165	45	2,350	4,700	8,225	2,225
7+50	50	11	109	166	23	8	164	135	325	375	8,175	6,750	16,225

DATE \_\_\_\_\_  
 BY \_\_\_\_\_  
 SURVEYED \_\_\_\_\_  
 PLOTTED \_\_\_\_\_  
 NOTE BOOK \_\_\_\_\_  
 AREAS CHECKED \_\_\_\_\_

DATE \_\_\_\_\_  
 BY \_\_\_\_\_  
 ORIGINAL SURVEY \_\_\_\_\_  
 PLOTTED \_\_\_\_\_  
 NOTE BOOK \_\_\_\_\_  
 AREAS CHECKED \_\_\_\_\_

**CIVILTECH**  
 450 E Devon Ave, Suite 300  
 Itasca, Illinois 60143  
 Tel: 630.773.3900 Fax: 630.773.3975  
 www.civiltechinc.com

DESIGNED - JRR  
 DRAWN - JRR  
 CHECKED - RTM  
 DATE - 10/24/2011

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SHEET NO. 4 OF 10 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
364	02-00051-08-WR	LAKE	188	19
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63649	