

16 SCHEDULE OF CONCRETE CURB, TYPE B (60600605)		
FROM	TO	LENGTH (FOOT)
38+00	43+80	27
43+08	1+30	191
1+30	5+00	61
<b>PROJECT TOTAL</b>		<b>279</b>

18 SCHEDULE OF PROTECTIVE COAT (42001300)		
FROM	TO	AREA (SQ YD)
19+71	23+00	226
23+00	28+00	343
28+00	33+00	651
33+00	38+00	685
38+00	43+80	838
43+80	1+30	440
1+30	5+00	668
5+00	9+00	548
9+00	14+00	749
14+00	19+00	906
19+00	24+00	333
101+80	105+00	9
107+00	110+20	224
<b>PROJECT TOTAL</b>		<b>6,620</b>

17 SCHEDULE OF CATCH BASINS								
STRUCTURE #	STATION	OFFSET	60200805	60201110	60201340	60205040	60207605	60208240
			CB TA 4 DIA T8G	CB TA 4 DIA T11VF&G	CB TA 4 DIA T24F&G	CB TA 5 DIA T24F&G	CB TC T8G	CB TC T24F&G
2	22+50	41.9 RT			1			
5	25+00	41.9 RT			1			
8	27+50	41.9 RT			1			
10	27+43	53.9 RT					1	
12	28+40	42.1 RT			1			
15	28+94	57.3 RT						1
16	29+85	70.1 RT						1
18	30+30	42.3 RT			1			
23	32+80	46.6 RT			1			
26	34+50	22.4 LT				1		
27	34+50	50.1 RT				1		
32	35+76	21.9 LT			1			
33	36+10	22.4 LT				1		
35	35+76	51.7 RT			1			
36	36+10	52.8 RT				1		
43	38+01	20.1 RT			1			
44	38+01	55.6 RT			1			
49	40+50	8.2 RT		1				
50	40+50	59.9 RT			1			
55	43+80	65.1 RT			1			
56	43+97	7.9 RT		1				
58	45+18	53.2 LT						1
59	0+81	67.8 RT						1
63	2+54	29.8 RT			1			
64	2+54	71.6 RT			1			
66	2+69	94.0 RT	1					
69	3+25	71.9 RT			1			
72	3+96	29.7 RT			1			
73	4+10	29.7 RT			1			
75	4+10	71.9 RT			1			
81	4+50	29.6 RT			1			
82	4+50	71.9 RT			1			
84	5+25	29.6 RT		1				
85	5+15	29.5 RT		1				
87	6+00	29.7 RT		1				
90	6+78	128.1 RT			1			
91	7+38	107.0 RT						1
92	8+20	41.4 RT		1				
93	8+20	71.6 RT			1			
97	8+90	40.2 RT		1				
98	8+90	70.5 RT			1			
102	9+60	38.3 RT		1				
103	9+60	68.6 RT			1			
106	10+40	35.1 RT		1				
107	10+40	65.4 RT			1			
110	11+25	30.6 RT		1				
111	11+25	61.0 RT			1			
113	12+60	15.0 RT			1			
114	12+60	53.8 RT			1			
117	13+50	6.1 RT			1			
118	13+50	51.0 RT			1			
123	17+00	39.9 RT			1			
126	18+00	24.7 RT			1			
130	19+30	21.7 RT			1			
134	20+00	34.0 RT	1					
136	20+64	19.9 RT			1			
138	22+00	19.1 LT						1
140	23+35	20.6 LT			1			
145	107+13	25.9 LT			1			
<b>PROJECT TOTAL</b>			<b>2</b>	<b>10</b>	<b>36</b>	<b>4</b>	<b>1</b>	<b>6</b>

19 SCHEDULE OF TREE REMOVAL				
FROM	TO	(20100110)	(20100210)	(X2010350)
		6 TO 15 UNITS DIAMETER (UNITS)	OVER 15 UNITS DIAMETER (UNITS)	TREE REMOVAL, ACRES (SPECIAL) (ACRES)
19+71	23+00			
23+00	28+00	56	101	
28+00	33+00	297	156	
33+00	38+00	193		
38+00	43+80	136	73	
43+80	1+30		42	
1+30	5+00	176		
5+00	9+00	235	24	
9+00	14+00	55		
14+00	19+00	271	74	
19+00	24+00	6	0	
101+80	105+00			
107+00	110+20	62		
DETENTION AREA				1.50
<b>PROJECT TOTAL</b>		<b>1,487</b>	<b>470</b>	<b>1.50</b>

20 SCHEDULE OF PRECAST REINFORCED CONCRETE FLARED END SECTIONS								
STATION	OFFSET	STRUCTURE #	12"	15"	18"	24"	36"	42"
			(54213657)	(54213660)	(54213663)	(54213669)	(54213681)	(54213687)
32+61	37.1 LT	20					1	
36+10	39.0 LT	30					1	
36+10	74.6 RT	38						1
39+25	35.6 LT	46		1				
39+53	35.6 LT	47		1				
41+27	34.9 LT	52		1				
41+62	34.9 LT	53		1				
3+97	51.6 LT	83A	1					
4+32	110.5 RT	79					1	
4+28	110.5 RT	67			1			
8+97	56.1 LT	95				1		
8+62	111.4 RT	96				1		
14+00	53.6 LT	120				1		
14+04	87.2 RT	121				1		
18+87	36.0 LT	128		1				
19+25	36.0 LT	133		1				
34+50	104.7 RT	29					1	
36+05	84.9 RT	39				1		
35+42	114.1 RT	41				1		
32+53	63.6 RT	41C		1				
32+77	88.3 RT	41D		1				
<b>PROJECT TOTAL</b>			<b>1</b>	<b>8</b>	<b>1</b>	<b>6</b>	<b>4</b>	<b>1</b>

DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 SURVEYED: \_\_\_\_\_ PLOTTED: \_\_\_\_\_  
 ORIGINAL SURVEY: \_\_\_\_\_ NOTE BOOK: \_\_\_\_\_  
 NO. \_\_\_\_\_ AREAS CHECKED: \_\_\_\_\_

DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 SURVEYED: \_\_\_\_\_ PLOTTED: \_\_\_\_\_  
 ORIGINAL SURVEY: \_\_\_\_\_ NOTE BOOK: \_\_\_\_\_  
 NO. \_\_\_\_\_ AREAS CHECKED: \_\_\_\_\_