

26		SCHEDULE OF TEMPORARY PAVEMENT MARKING				
STATION		LETTERS AND SYMBOLS (70300210)	4" (70300220)	6" (70300240)	12" (70300260)	24" (70300280)
FROM	TO	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
19+71	34+00	219	18,838	1,063	177	141
34+00	3+00	562	15,583	2,367	25	250
3+00	15+00	438	13,489	2,181	119	267
15+00	23+45		11,879	31	305	57
101+80	110+20	256	10,771	1,277	17	127
PROJECT TOTAL		1,475	70,560	6,919	643	842

27		SCHEDULE OF INLETS			
STRUCTURE #	STATION	OFFSET	60236825	60237470	
			INLETS TA	INLETS TA	
			T11VF&G	T24F&G	
1	22+50	21.1' LT		1	
4	25+00	21.1' LT		1	
7	27+50	21.1' LT		1	
11	28+40	23.6' LT		1	
17	30+30	21.1' LT		1	
22	32+80	21.1' LT		1	
31	35+66	21.1' LT		1	
34	35+66	50.8' RT		1	
42	38+01	21.1' LT		1	
48	40+50	21.1' LT		1	
62	2+54	21.1' LT		1	
68	3+25	29.1' RT		1	
71	3+82	29.0' RT		1	
74	3+94	71.1' RT		1	
80	4+60	29.0' RT		1	
100	9+00	39.2' RT	1		
101	9+70	37.2' RT	1		
101A	9+60	21.1' LT		1	
105	10+50	33.8' RT	1		
109	11+35	29.2' RT	1		
113A	12+60	21.1' LT		1	
116	13+50	21.1' LT		1	
122	17+00	24.9' LT		1	
125	18+00	25.9' LT		1	
129	19+30	22.9' LT		1	
135	20+64	19.7' LT		1	
144	107+13	29.7' RT		1	
PROJECT TOTAL			4	23	

28		SCHEDULE OF PERMANENT PAVEMENT MARKINGS						
STATION		LETTERS AND SYMBOLS (78000100)	LINE 4" (78000200)	LINE 6" (78000400)	LINE 8" (78000500)	LINE 12" (78000600)	LINE 24" (78000650)	PAINT RAISED MEDIAN (X7800100)
FROM	TO	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)
19+71	34+00	364	11,654	1,294	516	1,414	152	202
34+00	3+00	584	1,238	3,466		138	472	617
3+00	15+00	1,134	1,536	4,268	242	1,646	310	740
15+00	24+50	178	6,782	470	782	50	209	209
101+80	110+20	292	7,100	592	4,154	1,302	130	0
PROJECT TOTAL		2,552	28,310	10,090	4,912	5,282	1,114	1,768

29		SCHEDULE OF AGGREGATE SUBGRADE, 12" (Z0001050)	
FROM	TO	AREA (SQ YD)	
19+71	23+00	2,525	
23+00	28+00	3,832	
28+00	33+00	5,156	
33+00	38+00	3,754	
38+00	43+80	5,550	
43+80	1+30	2,575	
1+30	5+00	4,072	
5+00	9+00	5,193	
9+00	14+00	4,625	
14+00	19+00	3,323	
19+00	24+00	742	
101+80	105+00	260	
107+00	110+20	2,049	
PROJECT TOTAL		43,656	

30		SCHEDULE OF MANHOLES					
STRUCTURE #	STATION	OFFSET	60218400	60219000	60221100	60223800	60224039
			MAN TA 4DIA T1F CL	MAN TA 4DIA T8G	MAN TA 5DIA T1F CL	MAN TA 6DIA T1F CL	MAN TA 6DIA T24F&G
3	22+50	49.5' RT	1				
6	25+00	49.5' RT	1				
9	27+50	49.5' RT				1	
13	28+40	49.5' RT			1		
14	28+81	49.6' RT					1
19	30+27	50.2' RT			1		
21	32+87	31.3' LT			1		
24	32+80	54.4' RT			1		
25	34+50	32.0' LT			1		
28	34+50	57.2' RT			1		
37	36+10	59.9' RT				1	
41B	35+84	84.4' RT			1		
45	38+01	63.1' RT			1		
51	40+50	67.2' RT			1		
54	43+80	72.6' RT			1		
60	0+81	77.6' RT			1		
65	2+54	79.0' RT			1		
66A	4+26	94.0' RT	1				
70	3+25	79.5' RT			1		
76	4+10	79.5' RT			1		
78	4+21	36.3' LT			1		
83	4+50	79.5' RT			1		
86	5+15	79.4' RT			1		
88	6+00	79.3' RT			1		
89	6+50	91.9' RT			1		
94	8+20	82.7' RT			1		
99	8+90	79.8' RT			1		
104	9+60	77.9' RT			1		
108	10+40	74.6' RT			1		
112	11+25	70.3' RT			1		
115	12+60	63.3' RT			1		
119	13+50	60.2' RT	1				
124	17+00	50.0' RT	1				
127	18+00	36.0' RT	1				
131	19+30	36.0' RT		1			
137	20+64	36.0' RT	1				
139	22+00	36.0' RT	1				
141	23+43	30.2' RT	1				
146	107+13	32.3' LT			1		
PROJECT TOTAL			9	1	26	2	1

31		SCHEDULE OF STONE RIPRAP AND FILTER FABRIC		
FROM	TO	(28100101) CLASS A1 (SQ YD)	(28100107) CLASS A4 (SQ YD)	(28200200) FILTER FABRIC (SQ YD)
18+00	23+00	0	0	0
23+00	28+00	0	0	0
28+00	33+00	0	0	0
33+00	38+00	4	0	5
28+00	43+80	0	0	0
43+80	1+30	0	0	0
1+30	5+00	8	8	10
5+00	9+00	26	10	31
9+00	14+00	0	0	0
14+00	19+00	6	2	7
19+00	24+00	8	0	10
101+50	105+00	8	0	10
107+00	111+00	0	0	0
DETENTION POND		84	64	96
PROJECT TOTAL		144	84	168

32		SCHEDULE OF ITEMS TO BE REMOVED		
STATION		60500040	60500050	60500060
FROM	TO	MANHOLES	CATCH BASINS	INLETS
19+71	23+00			
23+00	28+00	3	3	1
28+00	33+00	6	4	3
33+00	38+00	1		
38+00	43+80			1
43+08	1+30	2	4	2
1+30	5+00	2	1	2
5+00	9+00		3	1
9+00	14+00		2	
14+00	19+00	1		4
19+00	23+45	1		
101+80	105+00			
107+00	110+20			
PROJECT TOTAL		16	17	14

DATE: _____
 BY: _____
 SURVEYED: _____
 PLOTTED: _____
 DATE: _____
 NO. _____
 FINAL SURVEY: _____
 NOTE BOOK: _____
 AREAS CHECKED: _____

DATE: _____
 BY: _____
 SURVEYED: _____
 PLOTTED: _____
 DATE: _____
 NO. _____
 ORIGINAL SURVEY: _____
 NOTE BOOK: _____
 AREAS CHECKED: _____