

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
			Construction Code 0005
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,726
40600300	AGGREGATE (PRIMECOAT)	TON	55
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	80
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,145
40600895	CONSTRUCTING TEST STRIP	EACH	2
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX"D",N70	TON	3,053
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	78
42400800	DETECTABLE WARNINGS	SQ FT	8
44000159	HOT MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	27,260
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	325
44003100	MEDIAN REMOVAL	SQ FT	40
60603800	COMBINATION CONCRETE CURB AND GUTTER , TYPE B-6.12	FOOT	175
60604400	COMBINATION CONCRETE CURB AND GUTTER , TYPE B-6.18	FOOT	150
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	40
67100100	MOBILIZATION	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,800
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	364
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	1,850
70300240	TEMPORARY PAVEMENT MARKING- LINE 6"	FOOT	2,450
70300280	TEMPORARY PAVEMENT MARKING- LINE 24"	FOOT	216
*78000100	THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	364
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,850
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,450
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	216
XX006395	SHOTCRETE CURB AND GUTTER REPAIR	FOOT	300
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	9
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	48

NOTES: * DENOTES SPECIALTY ITEM

USER NAME -	DESIGNED - ISS	REVISED - -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION 11-00057-00-RS	COUNTY WILL	TOTAL SHEETS 20	SHEET NO. 2
PLOT SCALE -	DRAWN - ISS	REVISED - -		SHEET NO. 2 OF 20 SHEETS					CONTRACT NO. 63706
PLOT DATE = 1/20/2012	CHECKED - PP	REVISED - -							ILLINOIS FED. AID PROJECT