

SUMMARY OF QUANTITIES				0005 ROADWAY 70% STP 30% LA	0021 ROADWAY 100% LA	0021 SAFETY 70% STP 30% LA
* CODE NO	PAY ITEM	UNIT	QUANTITY			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	80	80		
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	204	204		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3	2.5		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3	2.5		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	2.5		
25200110	SODDING, SALT TOLERANT	SQ YD	204	204		
25200200	SUPPLEMENTAL WATERING	UNIT	1	0.6		
28000510	INLET FILTERS	EACH	17	17		
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1,618	1,618		
35800100	PREPARATION OF BASE	SQ YD	14,410	14,410		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,923	2,923		
40600300	AGGREGATE (PRIME COAT)	TON	59	59		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	30		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	893	893		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	50	50		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	154	154		
40600990	TEMPORARY RAMP	SQ YD	204	204		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,637	1,637		
42001300	PROTECTIVE COAT	SQ YD	1,454	1,454		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	112	112		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	10,131	10,131		
42400800	DETECTABLE WARNINGS	SQ FT	552	552		
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	1,565	1,565		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	192	192		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	835	835		
44000600	SIDEWALK REMOVAL	SQ FT	10,683	10,683		
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	365	365		
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	365	365		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	365	365		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	365	365		
60236825	INLETS, TYPE A, TYPE IIV FRAME AND GRATE	EACH	2	2		
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1		
60404805	FRAMES AND GRATES, TYPE IIV	EACH	2	2		
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	10	10		
60500060	REMOVING INLETS	EACH	2	2		
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	835	835		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	688	688		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	129	129		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,188	3,188		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	707	707		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	28	28		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	110	110		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	95	95		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	187	187		
• 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1		

SUMMARY OF QUANTITIES				0005 ROADWAY 70% STP 30% LA	0021 ROADWAY 100% LA	0021 SAFETY 70% STP 30% LA
* CODE NO	PAY ITEM	UNIT	QUANTITY			
• 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	11.25	11.25		
• 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1		
• 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	29	29		
• 73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	2	2		
• 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	213	213.2		
• 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	5,792	5,792		
• 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	1,195	1,195		
• 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	46	46		
• 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	205	205		
• 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	228	228		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	63	63		
• 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	154		154	
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	378	378		
• 89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	2	2		
• X0325714	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	2			2
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	10	10		
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1		
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	12,845	12,845		
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	42	42		
• X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	213		213.2	
• X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	5,792		5,792	
• X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	1,195		1,195	
• X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	46		46	
• X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	205		205	
• X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	228		228	
XX000445	SAWCUT AND SEAL NEW JOINTS	FOOT	4,178		4,178	
Z0004522	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6"	SQ YD	80	80		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	17	17		
Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	34	34		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	902	902		
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	25	25		

• SPECIALTY ITEM

FILE NAME = g:\CH\1\0873\Road\Sheets\0-103-SumQty.shh  
 USER NAME = USER  
 PLOT SCALE = 64.9432 ft / IN.  
 PLOT DATE = 4/5/2012

DESIGNED - CEC  
 DRAWN - CEC  
 CHECKED - DWB  
 DATE - 03/26/2012  
 REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

YORK STREET RESURFACING  
 SUMMARY OF QUANTITIES

NOT TO SCALE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE. 2678 SECTION 12-00180-00-RS COUNTY DUPAGE TOTAL SHEETS 18 SHEET NO. 3 CONTRACT NO. 63708  
 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT