

SUMMARY OF QUANTITIES

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY 80% FEDERAL 20% LOCAL 0004	SIGNALS 80% FEDERAL 20% LOCAL 0021	LIGHTING 80% FEDERAL 20% LOCAL 0021
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4,162	4,162		
20400800	FURNISHED EXCAVATION	CU YD	169	169		
20800150	TRENCH BACKFILL	CU YD	71	71		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,051	4,051		
25000210	SEEDING, CLASS 2A	ACRE	0.84	0.84		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	51	51		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	51	51		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	51	51		
25100630	EROSION CONTROL BLANKET	SQ YD	4,051	4,051		
28000305	TEMPORARY DITCH CHECKS	FOOT	100	100		
28000400	PERIMETER EROSION BARRIER	FOOT	1,200	1,200		
28000500	INLET AND PIPE PROTECTION	EACH	2	2		
28000510	INLET FILTERS	EACH	14	14		
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	3,040	3,040		
31101600	SUBBASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	75	75		
31200100	STABILIZED SUBBASE 4"	SQ YD	3,040	3,040		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	7	7		
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10-1/2" (JOINTED)	SQ YD	2,400	2,400		
42001300	PROTECTIVE COAT	SQ YD	2,901	2,901		
42400800	DETECTABLE WARNINGS	SQ FT	65	65		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	325	325		
44000100	PAVEMENT REMOVAL	SQ YD	910	910		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	75	75		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,540	1,540		
44004250	PAVED SHOULDER REMOVAL	SQ YD	854	854		
44200986	CLASS B PATCHES, TYPE III, 11"	SQ YD	65	65		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	158	158		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1		
54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	EACH	2	2		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	416	416		
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	24	24		
55100700	STORM SEWER REMOVAL 15"	FOOT	10	10		
55100900	STORM SEWER REMOVAL 18"	FOOT	95	95		
60107600	PIPE UNDERDRAINS 4"	FOOT	1,364	1,364		
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60200405	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 4 FRAME AND GRATE	EACH	2	2		
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1		
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1		
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	5	5		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	205	205		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,325	1,325		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1,102	1,102		
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	584	584		
* 63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	25	25		

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: HRGreen.com
 CLIENT: HRGreen.com
 DATE PLOTTED: 4/11/2012 3:46:46 PM
 FILE NAME: 0177-sum.dgn
 PLOT DRIVER: pct.plt
 PLOT TABLE: Standard-Trans.tbl



USER NAME = jmelhu	DESIGNED - JRM	REVISED -
PLOT SCALE = N.T.S.	DRAWN -	REVISED -
PLOT DATE = 4/11/2012	CHECKED - TEH	REVISED -
	DATE - 4/11/12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
IL 59 & SHOE FACTORY RD	
SCALE: N.T.S.	SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE. 338	SECTION 10-00084-00-CH	COUNTY COOK	TOTAL SHEETS 63	SHEET NO. 3
CONTRACT NO. 63711			ILLINOIS FED. AID PROJECT	