

EARTHWORK SCHEDULE

LOCATION	20200100 EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT (25% SHRINKAGE)	EMBANKMENT	EARTH BALANCE WASTE (+) OR SHRINKAGE (-)	21101625 TOPSOIL FURNISH AND PLACE, 6"
	(CY)	(CY)	(CY)	(CY)	(SY)
IL 2 (SOUTH OF US 20)					
Sta. 216+00 TO 222+00	1,591	1,193	2,801	-1,608	3,564
Sta. 222+00 TO 228+00	2,694	2,020	1,593	427	4,094
Sta. 228+00 TO 234+00	4,242	3,182	640	2,542	3,388
Sta. 234+00 TO 240+00	2,845	2,134	1,260	874	4,731
Sta. 240+00 TO 246+00	2,293	1,719	1,268	451	3,422
IL 2 (NORTH OF US 20)					
Sta. 276+00 TO 282+00	154	115	0	115	284
Sta. 282+00 TO 288+00	562	422	3	418	584
Sta. 288+00 TO 294+00	1,993	1,495	1,374	121	2,680
Sta. 294+00 TO 300+00	4,516	3,387	6,205	-2,818	5,648
Sta. 300+00 TO 306+00	6,953	5,214	0	5,214	2,777
Sta. 306+00 TO 312+00	1,301	976	560	416	1,949
Sta. 312+00 TO 318+00	3,931	2,948	470	2,478	1,769
Sta. 318+00 TO 324+00	1,124	843	757	85	1,610
Sta. 324+00 TO 330+00	5,490	4,118	117	4,001	2,731
Sta. 330+00 TO 336+00	6,484	4,863	113	4,750	3,237
Sta. 336+00 TO 342+00	180	135	0	135	0
PELLY ROAD					
Sta. 104+00 TO 110+00	351	263	48	215	604
SW RAMP					
Sta. 26015+50 TO 26019+50	1,143	857	4	853	1,649
SE RAMP					
Sta. 10+00 TO 15+00	681	511	41	469	700
Sta. 15+00 TO 19+00	1,823	1,368	233	1,135	2,933
SEMINOLE					
Sta. 50+50 TO 51+30	88	66	3	63	101
SPRINGFIELD AVE					
Sta. 24+00 TO 30+00	233	175	38	137	71
Sta. 30+00 TO 33+00	842	632	30	602	640
SHELL ACCESS					
Sta. 2000+00 TO 2006+00	244	183	3	180	208
HARRISON AVE					
Sta. 34+00 TO 36+00	2,072	1,554	11	1,543	638
Sta. 36+00 TO 42+00	1,856	1,392	2,680	-1,288	4,465
PRAIRIE ROAD					
Sta. 7+00 TO 11+00	566	425	0	425	348
SUB-TOTAL	56,253	42,190	20,253	21,937	54,824
Excavation for Culvert at 295+00	4,950	3,713	0	3,713	0
TOTAL	61,203	45,902	20,253	25,649	54,824

FILE NAME =	USER NAME = petp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP 742 (IL 2) EARTHWORK SCHEDULE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
g:\2010\trans\b10\001\dgn\cover and schedule\01500-EARTHWORK SCHEDULE.dgn		DRAWN -	REVISED -			742	34R	WINNEBAGO	491	34	
PLOT SCALE = 10.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64515					
PLOT DATE = 1/17/2012		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		