

SCHEDULE OF QUANTITIES

28000305 TEMPORARY DITCH CHECKS

FOOT	LOCATION	OFFSET	REMARKS
	IL ROUTE 2		
8	218+40	RT	
8	221+00	RT	
8	222+00	RT	
8	225+60	LT	
8	228+00	LT	
24	228+00 231+00	RT	100' SPACING
8	233+00	RT	
72	234+00 241+50	LT	100' SPACING
56	234+00 240+00	RT	100' SPACING
8	243+00	LT	
8	243+90	LT	
	HARRISON AVENUE		
40	36+35 37+75	RT	35' SPACING
96	36+40 37+50	LT	10' SPACING
24	37+90 38+70	LT	40' SPACING
	SW RAMP		
16	26017+25 26018+00	RT	80' SPACING
	SE RAMP		
48	14+00 16+50	RT	45' SPACING
56	14+75 16+50	LT	35' SPACING
496	TOTAL		

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	OFFSET	REMARKS
	IL ROUTE 2		
1	219+63	RT	
1	224+50	LT	
1	224+67	RT	
1	227+00	LT	
1	227+18	RT	
1	229+30	RT	
1	232+11	RT	
1	243+41	LT	
1	294+50	LT	
1	317+32	LT	
1	322+25	RT	
1	325+50	CL	
1	327+10	CL	
1	333+25	CL	
1	337+25	CL	
	HARRISON AVENUE		
1	27+30	CL	
1	37+91	RT	
1	38+71	LT	
	SW RAMP		
1	26018+24	RT	
	SE RAMP		
1	16+76	LT	
20	TOTAL		

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION	OFFSET	REMARKS
	IL ROUTE 2		
582	217+78 223+40	LT	
305	243+00 244+95	LT	
248	243+65 245+81	RT	
433	265+90 269+98	RT	
144	270+41 271+63	RT	
419	278+14 282+55	RT	
154	283+02 284+65	RT	
72	285+30 286+00	RT	
115	287+50 289+00	LT	
248	287+75 289+78	RT	
1,015	289+95 299+40	LT	
928	290+16 298+70	RT	
926	305+52 315+13	RT	
647	307+00 314+00	LT	
1,194	316+28 327+26	RT	
556	317+36 322+95	LT	
184	332+63 334+37	RT	
71	333+25 333+96	LT	
	HARRISON AVE.		
200	30+00 32+00	LT	
96	32+14 32+38	LT	
308	35+00 37+94	RT	
287	38+60 41+21	RT	
301	39+00 41+14	LT	
	SW RAMP		
185	26016+50 26018+26	LT	
	TEMP ACCESS ROAD		
160	2000+80 2001+60	LT/RT	
9,778	TOTAL		

28100107 STONE RIPRAP, CLASS A4

SQ YD	LOCATION	OFFSET	REMARKS
12	218+62	RT	
18	223+00	LT	
30	TOTAL		

28500400 ARTICULATED BLOCK REVETMENT MAT

SQ YD	LOCATION	OFFSET	REMARKS
2	333+86	LT	
2	337+23	LT	
4	TOTAL		

30300112 AGGREGATE SUBGRADE IMPROVEMENT 12"

SQ YD	LOCATION	OFFSET	REMARKS
	IL ROUTE 2		
132	217+06 218+79.63	MEDIAN	
3,866	219+44.60 223+61.11	MAINLINE & PELLY RD	
5,806	223+61.11 229+00	MAINLINE & PELLY RD	
8,946	237+50 244+95	MAINLINE	
725	267+03.5 271+63.40	RT TURN LN	
2,262	287+50 289+94.80	MAINLINE & SEMINOLE AVE	
9,337	289+94.80 302+00	MAINLINE & SEMINOLE AVE	
11,955	305+50 315+77.18	MAINLINE	
15,945	315+77.18 333+50.85	MAINLINE	
261	333+50.85 337+32.51	MEDIAN CURB & GUTTER LT/RT	
	SPRINGFIELD / HARRISON		
928	24+65 32+00	LT TURN LN+MEDIAN	
339	29+52.70 32+00	WB TAPER+LANES	
5,648	35+00.51 41+04.19	MAINLINE	
	S. MAIN STREET		
234	222+81.6 223+90.4	HAMMERHEAD	
234	224+06.5 224+41.6	HAMMERHEAD	
	SW RAMP		
573	26016+50 26019+25.98		
	SE RAMP		
796	13+85.20 18+38.25		
	AQUAMARINE DRIVE		
153	219+11.30	70.2' RT	
	ONYX PARKWAY		
302	228+84.39	RT	
	FAITH CENTER PARKING LOT		
1,674	231+81.09	LT	
	EXPRESS LANE		
521	38+38.96	106' RT	
	PRAIRIE ROAD		
587	9+90 11+04	MAINLINE	
	SW RAMP SHOULDERS		
175	26016+50 26019+08.82	RT	
120	26016+50 26019+06.12	LT	
	SE RAMP SHOULDERS		
258	13+85.20 18+38.25	RT	
202	13+85.20 18+38.25	LT	
	TEMPORARY SHELL ACCESS ROAD		
741	2000+00.00 2002+43.36		IL RTE 2 STA.314+74.68 RT
72,720	TOTAL		

30300118 AGGREGATE SUBGRADE IMPROVEMENT 18"

SQ YD	LOCATION	OFFSET	REMARKS
	IL ROUTE 2		
8,300	229+00 237+50	MAINLINE	
405	231+81	102' LT	FAITH CENTER ENTRANCE
8,705	TOTAL		

30300124 AGGREGATE SUBGRADE IMPROVEMENT 24"

SQ YD	LOCATION	OFFSET	REMARKS
2,773	302+00 305+50	MAINLINE	
2,773	TOTAL		

35102000 AGGREGATE BASE COURSE, TYPE B 8"

SQ YD	LOCATION	OFFSET	REMARKS
587	278+13.86 282+53.13	RT	BIKEPATH
881	283+04.02 289+71.51	RT	BIKEPATH
1,747	290+18.30 303+35.14	RT	BIKEPATH
1,513	303+68.31 315+00.87	RT	BIKEPATH
2,364	316+43.08 334+16.00	RT	BIKEPATH
7,092	TOTAL		

FILE NAME =	USER NAME = pstp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP 742 (IL 2) SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
G:\2010\TRANS\B10100\IDON\Cover and Schedules\081500-SCHEDULES.dgn		DRAWN -	REVISED -		742	34R	WINNEBAGO	491	37			
PLOT SCALE = 1/8"=1'-0"		CHECKED -	REVISED -		CONTRACT NO. 64515			ILLINOIS FED. AID PROJECT				
PLOT DATE = 1/31/2012		DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.					