PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / NOTE BOOK / NO. / DATE / BY

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / NOTE BOOK / NO. / STRUCTURE NO(S)/PINS CHKD

MATCH LINE STA 288+00

MATCH LINE STA 294+00

15-03-301-003
JASON & LISA NILLES
3605 S. MAIN ST.

House

15-03-151-011
GEORGE/NICK TZEMOPOULOS
3447 S. MAIN ST.

15-03-327-003
3608 S. MAIN ST.

House

15-03-327-001
DAVID & MARIE VERSACK
420 SEMINOLE AVE.
℄ SEMINOLE AVE

15-03-177-009
KELLY M & KATHY M DOTSON
4XX SEMINOLE AVE.

15-03-177-008
PAUL J & CATHY M CARTER
415 SEMINOLE AVE.

15-03-176-005
MARIE JURKOWSKI
3504 S. MAIN ST.

SEMINOLE AVE

EXIST GRAVEL

CE

TEMPORARY EASEMENT

PROPOSED R.O.W.

EXISTING R.O.W.

TEMPORARY EASEMENT
PROPOSED R.O.W.

CONSTRUCTION LIMITS

EXIST CONC

EXIST HMA

EXIST GRAVEL

288+36.91
31.00' LT

+41.5 TEMPORARY PAVEMENT

COMB CC&G TB6.24

STA. 289+94.80 (IL RTE 2)=
STA. 50+00 (SEMINOLE AVE.)

IL RTE 2 S.B.

IL RTE 2 N.B.

℄ IL RTE 2

+65.7 TEMPORARY PAVEMENT

+50 TEMPORARY PAVEMENT

+75 TEMPORARY PAVEMENT

5' TYP BOC

288 289 290+00 291 292 293

31' 39' 50+00 90°

+41. 39.3' RT
FIRE HYDNTS TO BE MVD
+47 VV ADJUST

1' STUB

SIGN TO BE SAVED

+57.8, 31'RT

+47.9, 39'RT

MB

BM = 416

EXIST CONC

EXIST HMA

15" CMP

EXISTING R.O.W.

PROPOSED R.O.W.

TEMPORARY EASEMENT

PC CONC SIDEWALK 5 (110 SF)
DETECTABLE WARNINGS
(IDOT STD.424001-06)

PCCONC SIDEWALK 5 (188 SF)
DETECTABLE WARNINGS
(IDOT ISTD.424001-06)

30'R 50'R 13' 13'

+81.8 81'RT

+84.2 104.1'RT

+86.34 124.1'RT

+86.32 130.8'RT

+07.8 81'RT

+06.6 95.84'RT

+06.54 130.86'RT

CONSTRUCTION LIMITS

10' MULTI-USE PATH

SAVE

REFER TO DRAINAGE PLANS FOR CULVERT AND STORM SEWER PROPOSED AND REMOVAL ITEMS.

X = TREE REMOVAL

PE +13 PE +29 PE +69 PE +34 PE +73

EXIST GRAVEL

SCALE IN FEET
0 20 40

750 745 740 735 730 725

VPI STA. 290+00.00
ELEVATION 740.44

-0.57% -1.83% -1.83%

EXISTING ℄ GRADE LINE

PROFILE GRADE LINE

+55.00 EL. 735.77

+95.00 EL. 741.04

+05.00 EL. 738.52

EXISTING 15" RCP STORM SEWER

EXISTING 15" RCP STORM SEWER

EXISTING 15" RCP STORM SEWER

SSD = 963'
ex = -0.33'
K = 167
210.00' V.C.

STAGE 1
STA. 288+00.00 TO STA. 294+00.00
EARTH EXC. = 878 CU.YDS.
EMBANK = 384 CU.YDS.
WASTE = 341 CU.YDS.

STAGE 2
STA. 288+00.00 TO STA. 294+00.00
EARTH EXC. = 838 CU.YDS.
EMBANK = 990 CU.YDS.
SHORTAGE = 170 CU.YDS.

STAGE 3
STA. 288+00.00 TO STA. 294+00.00
EARTH EXC. = 277 CU.YDS.
EMBANK = 0 CU.YDS.
WASTE = 208 CU.YDS.

288+00	288+50	289+00	289+50	290+00	290+50	291+00	291+50	292+00	292+50	293+00	293+50	294+00
741.50	741.44	741.36	741.27	741.18	741.07	740.93	740.80	740.66	740.48	740.30	740.10	739.86
741.50	741.45	741.36	741.24	741.13	741.01	740.88	740.72	740.51	740.34	740.11		

739.76	739.41	739.11	738.82	738.53	738.20	737.85	737.50	737.14	736.82	736.50	736.19	735.92	735.71	735.51	735.30	735.20	735.10	735.03
739.58	739.28	738.96	738.61	738.24	737.88	737.51	737.14	736.78	736.41	736.04	735.68	735.35	735.06	734.81	734.61	734.45	734.33	734.26

FILE NAME =	USER NAME = patp	DESIGNED - CJS	REVISED -
g:\2010\trans\b[0t001\dgn\plan and profile\il2\D01500PLN13.dgn	DRAWN - TSG	REVISED -	
	PLOT SCALE = 20.0000 ' / IN.	CHECKED - FJH	REVISED -
	PLOT DATE = 1/25/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 742 (IL 2)
PLAN AND PROFILE

SCALE: 1" = 20' | SHEET NO. OF SHEETS | STA. 288+00 TO STA. 294+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	34R	WINNEBAGO	491	70
		CONTRACT NO. 64515		
	ILLINOIS FED. AID PROJECT			