


LEGEND

	EXISTING ROADWAY LIGHTPOLE AND LUMINAIRE TO BE REMOVED, SALVAGE
	PROPOSED DECORATIVE LIGHT POLE AND LUMINAIRE ALUMINUM, 40 FT. M.H., PULSE START METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SEE NOTE 13 ON SHEET 301)
	IC - PROPOSED UNDERGROUND CONDUIT, HDPE SDR-11, 1/2" DIA. WITH PULL STRING AND TRACER WIRE
	PROPOSED UTILITY POLE (BY OTHERS)
	PROPOSED LIGHTING CONTROLLER, 100 AMP, 480V
	HH = PROPOSED HANDHOLE PER IDOT STD 814001
	CHH = PROPOSED HANDHOLE, COMPOSITE CONCRETE TYPE AS INDICATED

	PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, BORED AND PULLED, SIZE AND CONDUCTORS AS INDICATED.
	L - PROPOSED UNIT DUCT, 600V, 2-1C No.6, 1/C No.6 GROUND, (XLP-TYPE USE), 1/4" DIA. POLYETHYLENE
	FO - PROPOSED UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA. WITH PULL STRING AND TRACER WIRE
	PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, SIZE AND CONDUCTORS AS INDICATED

NOTES:

1. REFER TO ROADWAY LIGHTING NOTES ON SHEET 301.
2. SEE "HANDHOLE, COMPOSITE CONCRETE" SPECIAL PROVISION FOR HANDHOLE SIZES.



USER NAME = Jason Dove	DESIGNED - AS	REVISED - 04/17/2012
FILE NAME: 0264515-shr-light105.dgn	DRAWN - JWD	REVISED -
PLOT SCALE = 20.0000' / 1" =	CHECKED - AB	REVISED -
PLOT DATE = 4/18/2012 - 7:00:43 PM	DATE - 01/25/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ROADWAY LIGHTING PLAN
F.A.P. 742 (IL RTE 2)**

SCALE: 1" = 20' SHEET 5 OF 20 SHEETS STA. 324+00 TO STA. 330+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	34R	WINNEBAGO	491	305
CONTRACT NO. 64515				ILLINOIS FED. AID PROJECT

DIRECTORY = L:\PROJECTS\126004\Drawings\CADD_Sheets\0264515_Misc\main\...