



LEGEND

- EXISTING ROADWAY LIGHTPOLE AND LUMINAIRE TO BE REMOVED, SALVAGE
- PROPOSED DECORATIVE LIGHT POLE AND LUMINAIRE ALUMINUM, 40 FT. M.H., PULSE START METAL HALIDE, HORIZONTAL MOUNT 400 WATT (SEE NOTE 13 ON SHEET 301)
- IC — PROPOSED UNDERGROUND CONDUIT, HDPE SDR-11, 1/2" DIA. WITH PULL STRING AND TRACER WIRE
- PROPOSED UTILITY POLE (BY OTHERS)
- PROPOSED LIGHTING CONTROLLER, 100 AMP, 480V
- HH = PROPOSED HANDHOLE PER IDOT STD 814001
- CHH = PROPOSED HANDHOLE, COMPOSITE CONCRETE TYPE AS INDICATED
- L — PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, BORED AND PULLED, SIZE AND CONDUCTORS AS INDICATED.
- L — PROPOSED UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1/4" DIA. POLYETHYLENE
- FO — PROPOSED UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA. WITH PULL STRING AND TRACER WIRE
- FO — PROPOSED UNDERGROUND CONDUIT, GALVANIZED STEEL, SIZE AND CONDUCTORS AS INDICATED

NOTES:

1. REFER TO ROADWAY LIGHTING NOTES ON SHEET 301.

| | | | |
|--|-------------------------------------|-------------------|----------------------|
| <p>CMT CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS License No. 184-000613</p> | USER NAME = Jason Dave | DESIGNED - AS | REVISED - 04/17/2012 |
| | FILE NAME: D264515-sht-light107.dgn | DRAWN - JWD | REVISED - |
| | PLOT SCALE = 20.0000' / 1in. | CHECKED - AB | REVISED - |
| | PLOT DATE = 4/18/2012 - 6:14:57 PM | DATE - 01/25/2012 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROADWAY LIGHTING PLAN
F.A.P. 742 (IL RTE 2)

SCALE: 1" = 20' SHEET 7 OF 20 SHEETS STA. 336+00 TO STA. 341+00

| | | | | |
|--------------------|---------|-----------|---------------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 742 | 34R | WINNEBAGO | 491 | 307 |
| CONTRACT NO. 64515 | | | ILLINOIS FED. AID PROJECT | |

DIRECTORY = L:\R00K\F0RD\1126084\1D-ex-CADD_Sheets\026-0515_Misman\