

PAY CODE	TABULATION OF QUANTITIES		UNIT	PECATONICA RD	WINNEBAGO RD	TOTAL QUANTITY	90% Fed 10% State 0021
	ITEM						
6010074	SHOULDER REMOVAL AND REPLACEMENT, 8"		FOOT	8	8	16	
67100100	MOBILIZATION		L SUM	0.5	0.5	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701		L SUM	0.5	0.5	1	
73000100	WOOD POST SUPPORT		FOOT	40	40	80	
78000100	THERMOPLASTIC PAVEMENT MARKING LETTERS & SYMBOLS		SQ FT	375	375	750	
78000200	THERMOPLASTIC PAVEMENT MARKING LINE 4"		FOOT	1131	2636	3767	
78000500	THERMOPLASTIC PAVEMENT MARKING LINE 8"		FOOT	1495	1646	3141	
78000600	THERMOPLASTIC PAVEMENT MARKING LINE 12"		FOOT	275	476	751	
78000650	THERMOPLASTIC PAVEMENT MARKING LINE 24"		FOOT	218	222	440	
78300100	PAVEMENT MARKING REMOVAL		SQ FT	2207	3105	5312	
80300100	LOCATING UNDERGROUND CABLE		FOOT	4689	2802	7491	
80500100	SERVICE INSTALLATION, TYPE A		EACH	1	1	2	
81028720	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1" DIA.		FOOT	80	80	160	
81028740	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/2" DIA.		FOOT	400	400	800	
81400700	HANDHOLE, PORTLAND CONCRETE CEMENT		EACH	2	2	4	
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION		EACH	1	1	2	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION		EACH	1	1	2	
86200200	UNINTERRUPTIBLE POWR SUPPLY, STANDARD		EACH	0	1	1	
87900200	DRILL EXISTING HANDHOLE		EACH	2	4	6	
88500100	INDUCTIVE LOOP DETECTOR		EACH	0	1	1	
88600100	DETECTOR LOOP, TYPE I		FOOT	96	192	288	
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE		EACH	2	2	4	
X0325714	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION		EACH	4	4	8	
X0325469	MODIFY EXISTING TRAFFIC SIGNAL BACKPLATE		EACH	14	23	37	
X8809005	LED SIGNAL FACE LENS COVER		EACH	0	50	50	

FILE NAME =	USER NAME = h11k1	DESIGNED -	REVISED -
\\d2srw2\users\HILLKLV\Projects\us 28	peo and winn 2011\64H15.dgn	DRAWN -	REVISED -
	PLOT SCALE = 42.485' / in.	CHECKED -	REVISED -
	PLOT DATE = Wed Mar 14 10:39:26 2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE: _____	SHEET NO. ___ OF ___ SHEETS
STA. _____ TO STA. _____	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	17. 40M-3	WINNEBAGO	20	2
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64H15	