

44004250 PAVED SHOULDER REMOVAL

BR 20	SQ YD	REMARKS
STA 266+99.3 TO STA 268+67.1	56.6	PRESTAGE
STA 272+59 TO STA 274+52.5	64.5	PRESTAGE
STA 267+12.5 TO STA 269+01	62.8	STAGE 1
STA 272+93 TO STA 274+67.6	58.2	STAGE 1

TOTAL 242.1

70300100 SHORT TERM PAVEMENT MARKING

IL-251	FOOT	REMARKS
NORTH BOUND	120	TO BE USED AS DIRECTED BY RE
SOUTH BOUND	120	TO BE USED AS DIRECTED BY RE
BR 20		
STAGE 1	138	TO BE USED AS DIRECTED BY RE
STAGE 2	138	TO BE USED AS DIRECTED BY RE

TOTAL 516

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

IL-251	FOOT	REMARKS
PRESTAGE		
STA 215+13.9 TO STA 233+86.4	1873	TO BE USED AS DIRECTED BY RE
STA 203+84.9 TO STA 223+57.4	1973	TO BE USED AS DIRECTED BY RE

STAGE 1	FOOT	REMARKS
STA 215+13.9 TO STA 233+86.4	1872.5	NB (YELLOW)
STA 215+40.6 TO STA 222+99.8	759.2	NB (WHITE)
STA 203+84.4 TO STA 223+57.4	1973	SB (YELLOW)
STA 215+71.6 TO STA 223+30.7	759.1	SB (WHITE)
	5363.8	

STAGE 2	FOOT	REMARKS
STA 215+56.3 TO STA 223+12.8	756.5	NB (YELLOW)
STA 215+49.3 TO STA 233+86.3	1837	NB (WHITE)
STA 215+44.9 TO STA 223+15.1	770.2	SB (YELLOW)
STA 203+84.4 TO STA 223+22.0	1937.6	SB (WHITE)
	5301.3	

BR 20	FOOT	REMARKS
STAGE 1		
STA 266+34.6 TO STA 275+71.6	1874	(WHITE)
STA 267+22.5 TO STA 274+39.6	1434.2	(WHITE)
	3308.2	

STAGE 2	FOOT	REMARKS
STA 261+82.5 TO STA 265+74.6	1568.4	SB LANE SHIFT
STA 265+74.6 TO STA 275+42.6	1936	(WHITE)
STA 267+37.5 TO STA 274+42.6	1410.2	(WHITE)
	4914.6	

TOTAL 22733.9

70300280 TEMPORARY PAVEMENT MARKING-LINE 24"

BR 20	FOOT	REMARKS
STA 265+74.6	24	SB STOP BAR
STA 276+02.6	24	NB STOP BAR

TOTAL 48

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

IL-251	SQ FOOT	REMARKS
PLACED IN PRESTAGE		
STA 215+13.9 TO STA 233+86.4	624.3	TO BE USED AS DIRECTED BY RE
STA 204+84.9 TO STA 223+57.4	657.7	TO BE USED AS DIRECTED BY RE
	1282.0	

PLACED IN STAGE 1	FOOT	REMARKS
STA 215+13.9 TO STA 233+86.4	624.2	NB
STA 215+40.6 TO STA 222+99.8	253.1	NB
STA 203+84.4 TO STA 223+57.4	657.7	SB
STA 215+71.6 TO STA 223+30.7	253.0	SB
	1788.0	

PLACED IN STAGE 2	FOOT	REMARKS
STA 215+56.3 TO STA 223+12.8	252.2	NB
STA 215+49.3 TO STA 233+86.3	612.3	NB
STA 215+44.9 TO STA 223+15.1	255.7	SB
STA 203+84.4 TO STA 223+22.0	645.9	SB
	1767.1	

BR 20	FOOT	REMARKS
PLACED IN STAGE 1		
STA 261+82.5 TO STA 265+74.6	261.4	SB LANE SHIFT
STA 266+34.6 TO STA 275+71.6	312.3	
STA 267+22.5 TO STA 274+39.6	239	
STA 265+74.6	24	SB STOP BAR
STA 276+02.6	24	NB STOP BAR
	860.7	

PLACED IN STAGE 2	FOOT	REMARKS
STA 265+74.6 TO STA 275+42.6	322.7	
STA 267+37.5 TO STA 274+42.6	235	
	557.7	

TOTAL 6255.5

70400100 TEMPORARY CONCRETE BARRIER

IL-251	FOOT	REMARKS
STA 217+18.2 TO STA 222+63.0	544.8	NB STAGE 1
STA 216+08.3 TO STA 221+40.4	532.1	SB STAGE 1
BR 20		
STA 267+43.7 TO STA 274+15.1	671.4	

TOTAL 1748.3

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

IL-251	FOOT	REMARKS
STA 217+18.2 TO STA 222+63.0	544.8	NB STAGE 2
STA 216+08.3 TO STA 221+40.4	532.1	SB STAGE 2
BR 20		
STA 267+43.7 TO STA 274+15.1	671.4	

TOTAL 1748.3

FILE NAME = CrJoint Repair_84H75\64H75.PLAN.dgn	USER NAME = igora	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	VAR.	(1B, 1BR, 1BR-2R)M	VARIOUS	31	5
		CHECKED -	REVISED -									
		DATE -	REVISED -									
PLOT SCALE = 1/4" = 100'			PLOT DATE = Thu Apr 05 08:32:16 2012							CONTRACT NO. 64H75		
										FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT		