

EARTHWORK SCHEDULE

LOCATION	20200100	20400800	EARTH EXCAVATION	EMBANKMENT	EARTHWORK BALANCE
	EARTH EXCAVATION	FURNISHED EXCAVATION	ADJUSTED FOR SHRINKAGE		WASTE (+) SHORTAGE (-)
	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
39 + 00.00 TO 40 + 50.00	23.9		17.9	0.0	17.9
85 + 50.00 TO 89 + 50.00	15.0		11.3	686.6	-675.4
181 + 25.00 TO 185 + 75.00	17.1		12.8	664.7	-651.9
253 + 50.00 TO 257 + 25.00	11.8		8.9	461.9	-453.1
299 + 75.00 TO 301 + 50.00	27.9		20.9	0.0	20.9
370 + 50.00 TO 371 + 75.00	19.9		14.9	0.0	14.9
433 + 50.00 TO 439 + 75.00	32.8		24.6	1101.6	-1077.0
541 + 25.00 TO 542 + 75.00	23.9		17.9	0.0	17.9
559 + 75.00 TO 561 + 00.00	19.9		14.9	0.0	14.9
631 + 75.00 TO 635 + 75.00	0.0		0.0	1275.8	-1275.8
702 + 50.00 TO 706 + 75.00	0.0		0.0	1445.3	-1445.3
803 + 75.00 TO 807 + 50.00	0.0		0.0	1183.2	-1183.2
868 + 50.00 TO 872 + 50.00	5.3		4.0	763.9	-759.9
972 + 25.00 TO 976 + 75.00	3.3		2.5	645.5	-643.0
1107 + 00.00 TO 1110 + 75.00	0.0		0.0	1262.3	-1262.3
1357 + 75.00 TO 1359 + 25.00	23.9		17.9	0.0	17.9
1488 + 50.00 TO 1489 + 75.00	19.9		14.9	0.0	14.9
1669 + 50.00 TO 1672 + 25.00	10.6		8.0	65.3	-57.4
1795 + 50.00 TO 1796 + 50.00	16.0		12.0	0.0	12.0
1910 + 50.00 TO 1912 + 25.00	27.8		20.9	0.0	20.9
1983 + 75.00 TO 1985 + 00.00	19.9		14.9	0.0	14.9
2055 + 00.00 TO 2056 + 25.00	19.9		14.9	0.0	14.9
2120 + 75.00 TO 2122 + 00.00	19.9		14.9	0.0	14.9
2172 + 75.00 TO 2174 + 50.00	27.8		20.9	0.0	20.9
2325 + 00.00 TO 2326 + 50.00	23.9		17.9	0.0	17.9
418 + 49.00 TO 597 + 78.00	14.5	116.0	10.9		
68 + 80.00 TO 758 + 60.00	100.0	376.5	75.0		
TOTALS	524.9	10338.5	393.7	9556.1	-9248.3

* Henry County Various Guardrail Locations
 ** Rock Island Various Guardrail Locations

*
**

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EARTHWORK SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cs:\pw\work\p1dot\cushmanbw\d8292974\0205212-sht-500.dgn		DRAWN -	REVISED -			*	D2 SAFETY 2012-2	**	151	18	
PLOT SCALE = 50.0000' / in.		CHECKED -	REVISED -			SCALE: SHEET OF SHEETS STA. TO STA.					
PLOT DATE = Thu May 24 14:32:21 2012		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					

Rev. 6-4-12