

# INDEX OF SHEETS

1. Cover Sheet
2. General Notes & Standards
3. Summary of Quantities
3. Schedule of Quantities
4. Existing Bridge Plans
- 5.-8. Cross Sections
9. Dist. Stand 94.2

# HIGHWAY STANDARDS

- 701101-02 OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM EDGE OF PAVEMENT
- 701106-02 OFF-ROAD OPERATIONS, MULTILANE, LESS THAN 4.5M (15') AWAY, FOR SPEEDS GREATER/EQUAL TO 45-55 MPH
- 701421-04 LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS GREATER/EQUAL TO 45-55 MPH
- 701901-02 TRAFFIC CONTROL DEVICES
- 720011-01 METAL POSTS (signs, markers and delineators)
- 728001-01 TELESCOPING STEEL SIGN SUPPORT
- 729001-01 APPLICATION OF TYPE A AND B METAL POSTS

# GENERAL NOTES

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthwork activities, including temporary stockpiling outside the limits of construction.

The contractor shall seed all disturbed areas within the project limits, seeding class 4 shall be used. The work will be included in the contract unit price per Ton for Stone Riprap.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the Stone Riprap.

Culvert & bridge flows must be maintained throughout the project. Normal flow shall be allowed to pass at the rate it enters the jobsite. High flows shall be allowed to pass without causing damage to upstream properties.

Sand-Filled Geotextile Containers shall be placed under the Stone Riprap. They will be included in the contract unit price per Ton for Stone Riprap.

Work on this project may potentially conflict with work on other contracts in the area. The contractor should be prepared to plan for potential delays and cooperate with contractors on the other projects.

Fertilizer Nutrients shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Section 250 and 252 of the Standard Specifications. This work shall be included in the cost of STONE RIPRAP.

FILE NAME =	USER NAME = Kronshneljg	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
C:\2007\CORS\B-ridge\SCOVER\PLAN\eng.dgn	PLOT SCALE = 50.0000' / in.	DRAWN -	REVISED -			73B	5B-2M-1	WINNEBAGO	9	2	
	PLOT DATE = 2/9/2012	CHECKED -	REVISED -			CONTRACT NO. 64H93					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					