

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FEDERAL	20% STATE
				ROADWAY	
				0005	
				URBAN	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2030	2030	
40600300	AGGREGATE (PRIME COAT)	TON	62	62	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9	
40600527	LEVELING BINDER (HAND METHOD), 1L-9.5FG, N50	TON	9	9	
40600627	LEVELING BINDER (MACHINE METHOD), 1L-9.5FG, N50	TON	384	384	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600990	TEMPORARY RAMP	SQ YD	700	700	
40603080	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N50	TON	687	687	
40603510	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1227	1227	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	143	143	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3646	3646	
42400800	DETECTABLE WARNINGS	SQ FT	432	432	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1693	1693	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	9118	9118	

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -
et\pwwork\pwwork\duncanbd\0285100\036882-sht-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF	TOTAL SHEETS
	1	OF	4 SHEETS
	STA.		TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
653	7RS-3 & 8RS-4	LASALLE	23	3
CONTRACT NO. 66B82				
ILLINOIS FED. AID PROJECT				