

90% FED.  
10% STATE

SUMMARY OF QUANTITIES			CONSTR. CODE	
CODE NO.	ITEM	UNIT	LASALLE COUNTY ROADWAY	0021 RURAL
20200100	EARTH EXCAVATION	CU YD	498	
20400800	FURNISHED EXCAVATION	CU YD	1924	
25000210	SEEDING, CLASS 2A	ACRE	14.4	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1290	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1290	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1290	
25100630	EROSION CONTROL BLANKET	SQ YD	69667	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1440	
28000305	TEMPORARY DITCH CHECKS	FOOT	180	
28000400	PERIMETER EROSION BARRIER	FOOT	7500	
28000500	INLET AND PIPE PROTECTION	EACH	2	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1100	
50300225	CONCRETE STRUCTURES	CU YD	52	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5070	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4	
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	30	
64301090	ATTENUATOR BASE	SQ YD	819	
67100100	MOBILIZATION	L SUM	1	
<del>70106800</del>	<del>CHANGEABLE MESSAGE SIGN</del>	<del>CAL MO</del>	<del>2</del>	
X6015000	REMOVE CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4	
X6310214	TRAFFIC BARRIER TERMINAL TYPE 6 SPECIAL	EACH	1	

TRAFFIC BARRIER

FILE NAME =	USER NAME = fergusonse	DESIGNED -	REVISED -
ct:\p\work\p\dot\fergusonse\0294370\066899\shl-500.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/30/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	D3 IMPACT ATTENUATOR 2012-2	LASALLE	94	3
CONTRACT NO. 66899			ILLINOIS FED. AID PROJECT	

Rev