

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS 100% STATE STRUCTURE 0014 RURAL
20200100	EARTH EXCAVATION	CU YD	68	68
35101400	AGGREGATE BASE CSE, TYPE B	TON	64	64
35501326	HOT-MIX ASPHALT BASE CSE. 10 1/2"	SQ YD	401	401
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	126	126
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	117	117
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1210	1210
50102400	CONCRETE REMOVAL	CU YD	5.7	5.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	5.7	5.7
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2880	2880
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2030	2030
50800515	BAR SPLICERS	EACH	32	32
52000110	PREFORMED JOINT STRIP SEAL	FOOT	115	115
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	16	16
52100530	ANCHOR BOLTS, 1 1/4"	EACH	32	32
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	1195	1195
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	1210	1210
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1795	1795
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1