INDEX OF SHEETS

- 1. COVER SHEET
- 2-3. GENERAL NOTES/JOB SPECIFIC NOTES/COMMITMENTS
- 4-9. SUMMARY OF QUANTITIES
- 10-14. TYPICAL SECTIONS
- 15-20. SCHEDULE OF QUANTITIES
 - 21. ALIGNMENT, TIES & BENCHMARKS
- 22-23. HORIZONTAL CONTROL
 - 24. PROPOSED LAYOUT
- 25-27. PLAN & PROFILE (RAMP D)
- 28-30. PLAN & PROFILE (FRONTAGE ROAD)
- 31-33. DITCH PROFILE (RAMP D)
- 34-36. DITCH PROFILE (FRONTAGE ROAD)
- 37-38. SUPER ELEVATION RATES (RAMP D)
 - 39. STAGE CONSTRUCTION
- 40-41. CROSSOVER PLAN VIEW
 - 42. TRAFFIC CONTROL FOR IL 6
- 43-46. REMOVAL PLAN VIEW
- 47-48. EROSION CONTROL PLAN VIEW
- 49-50. ROW SHEETS
 - 51. PAVT MARKING DETAIL
- 52-53. OUTLET SPECIAL TYPE I, II, & III DETAILS
- 54-60. DISTRICT STANDARDS
- 61-101. CROSS SECTIONS
- 102-117. CROSSOVER CROSS SECTIONS

GENERAL NOTES

UTILITIES - LOCATIONS /INFORMATION ON PLANS

The locations of existing water mains, gas mains, sewers, electric power lines, telephone lines and other utilities as shown on the plans are based on careful field investigation and the best information available, but they are not guaranteed. Unless elevations are shown —— all utility locations shown on the cross sections are based on the approximate depth supplied by the utility company. It shall be the Contractor's responsibility to ascertain their exact location from the utility companies and by field inspection.

CLEARING

At locations where clearing is indicated on the plans beyond the limits of the proposed excavation or embankment, the Contractor shall restore the disturbed earth by blading and shaping to blend with the adjacent ground. The clearing will not be paid for separately but shall be included in the cost of excavation pay items in the plans. Payment for reseeding or resodding will be as provided in the plans.

SEEDING - SIDE SLOPE RIPPING

All slopes steeper than 3 to 1 and over 15 ft (4.5 m) in height shall be ripped. This shall consist of ripping between 18 inches to 24 inches (450 mm to 600 mm) deep normal to the slope. The interval of ripping along the slope shall be 12 ft. (3.6 m). This work shall be done after the seed bed has been prepared but before any fertilizer or seed has been applied. The fertilizer and seed shall be applied within a 24—hour period after the ripping has been done. This work will not be paid for separately but will be included in the cost of the various items of seeding involved.

ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run—arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

- * BDE Form 2289 (Environmental Survey Request)
- * A location map showing the size limits and location of the use area
- * Signed property owner agreement form-D4 Pl0100
- * Color photographs depicting the use area
- * Borrow Area Entry Agreement form-D4 PI0101

Please note that a minimum of two weeks shall be allowed for the District to obtain the required environmental clearances.

ILE NAME =	USER NAME = cousings	DESIGNED -	REVISED ~								
468A30-sht-plan.dgn		DRAWN -	REVISED ~	STATE OF ILLINOIS							
	PLOT SCALE = 50.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION							
	DI OY DATE - 0.45 (2012	DATE -	prvisen -								

					F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET	SHEET NO.	
GENERAL NOTES/JOB SPECIFIC			NOTES/COMMITMENTS		318	(72~6)R	PEORIA	117	2	
								CONTRACT	NO.	68A30
SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.		ILLINOIS FED. AI	D PROJECT		