

TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
LOCATION	30+22 TO 68+45	
SIZE	QUANTITY	UNIT
6	40	240
8	1	8
10	8	80
12	3	36
15	8	120
TOTAL	60	484

TREE REMOVAL (15 UNITS AND LARGER)		
LOCATION	30+22 TO 68+45	
SIZE	QUANTITY	UNIT
18	4	72
20	1	20
24	5	120
30	1	30
36	1	36
48	1	48
60	1	60
TOTAL	14	386

TRENCH BACKFILL	
LOCATION	CU. YD.
STA. 35+00	2.7
STA. 40+00	2.7
STA. 48+50	19.8
TOTAL	25

MULCH, METHOD 2	
LOCATION	ACRE
STA. 33+00 TO 68+45	11.4
TOTAL	11.4

NITROGEN FERTILIZER NUTRIENT		
LOCATION	ACRE	LB
STA. 33+00 TO 68+45	11.4	1026
TOTAL	11.4	1026

SEEDING, CLASS 2A	
LOCATION	ACRE
STA. 33+00 TO 68+45	9.9
TOTAL	9.9

PHOSPHOROUS FERTILIZER NUTRIENT		
LOCATION	ACRE	LB
STA. 33+00 TO 68+45	11.4	1026
TOTAL	11	1026

TEMPORARY EROSION CONTROL SEEDING	
LOCATION	LB
STA. 33+00 TO 68+45	1140
TOTAL	1140

SEEDING CLASS, 3A	
USE SEEDING CLASS 3A FOR SLOPES STEEPER THEN 1:4	
LOCATION	ACRE
STA. 33+00 TO 68+45	1.5
TOTAL	1.5

POTASSIUM FERTILIZER NUTRIENT		
LOCATION	ACRE	LB
STA. 33+00 TO 68+45	11.4	1026
TOTAL	11.4	1026

EARTHWORK TABLE					
LOCATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EX W/ SHRINKAGE 25%	EMBANKMENT	EXCESS EXCAVATION
	CU YD	CUYD	CU YD	CU YD	CU YD
STA. 20+25 TO 23+40	163		123	0	123
STA. 29+60 TO 34+00	647		485	22	463
STA. 34+00 TO 37+00	2677		2008	1562	446
STA. 37+00 TO 41+00	3617		2713	760	1953
STA. 41+00 TO 44+00	6534	1066	4101	854	3247
STA. 44+00 TO 48+57	8717		6538	2510	4028
STA. 48+57 TO 54+00	9346		7009	3309	3700
STA. 54+00 TO 58+00	4500		3375	474	2902
STA. 58+00 TO 64+00	869		652	70	582
STA. 64+00 TO 68+45	59		44	15	29
TOTAL	37129	1066	27047	9575	17472

TOPSOIL FURNISH & PLACE		
LOCATION	4"	6"
	SQ YD	SQ YD
STA. 33+00 TO 38+00	6556.5	
STA. 38+00 TO 41+00	3492.0	
STA. 41+00 TO 44+00	4161.6	899
STA. 44+00 TO 48+00	9925.2	
STA. 48+00 TO 53+00	16796.7	
STA. 53+00 TO 58+00	11403.9	
STA. 58+00 TO 65+00	2535.3	
TOTAL	54871	899

EROSION CONTROL BLANKET		
LOCATION	SQ FT	SQ YD
STA. 36+00 TO 37+00	800	89
TOTAL	800	89

TEMPORARY DITCH CHECK		
LOCATION	FOOT	FOOT
	BETWEEN RAMP AND FRONTAGE	RIGHT OF FRONTAGE
RT 33+00 TO 65+00	154	143
TOTAL	297	