

AGGREGATE BASE COURSE TYPE B 14"				
LOCATION	LENGTH	WIDTH	AREA	
			SQ FT	SQ YD
STA. 20+25 TO 22+40	215	12	2580	287
TOTAL			2580	287

PATCHING QUANTITIES				
LOCATION	NUMBER OF PATCHES	CLASS B PATCHES, TYPE II, 10 INCH	DOWEL BARS 1 1/2"	SAW CUTS
	EACH	SQ YD	EACH	FOOT
RAMP B	40	427	1120	2400
TOTAL	40	427	1120	2400

POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)			TEMPORARY PAVEMENT	
LOCATION	SQ YD	TON	SQ FT	SQ YD
STA. 20+25 TO 22+40	346.4	0.15	3118	346.4
STA. 44+95 TO 47+81	283.3	0.12	2550	283.3
STA. 54+00 TO 55+00	204.4	0.09	1840	204.4
TOTAL	834.2	0.4	7508	834

PAVED SHOULDERS REMOVAL		
LOCATION	SQ FT	SQ YD
STA. 30+22 TO 68+45	27886	3098
STA. 53+90 TO 57+17	3125	347
TOTAL	31011	3446

AGGREGATE SHOULDERS, TYPE B 8"			
LOCATION	LENGTH	WIDTH	AREA
	FOOT	FOOT	SQ YD
STA. 30+22 TO 68+45	3823	2	850
LT STA. 40+61 TO 57+17	1656	2	368
RPC STA. 40+61 TO 47+70	709	2	158
TOTAL			1375

COMB. CONC. CURB AND GUTTER, TYPE B-6.12	
LOCATION	FOOT
STA. 20+25 TO 22+40	430
RT STA. 30+24 TO 40+61	1037
TOTAL	1467

PAVEMENT REMOVAL			
LOCATION		SQ FT	SQ YD
RAMP D REMOVAL	STA. 30+22 TO 68+45	53949	5994
EXISTING FRONTAGE REMOVAL	STA. 62+35 TO 66+35	11017	1224
MEDIAN TEMPORARY PAVEMENT REMOVAL	STA. 20+25 TO 22+40	3118	346
TEMPORARY CROSS OVER	STA. 44+12 TO 48+00	2550	283
	STA. 54+00 TO 55+0	7508	834
TOTAL		78142	8682

COMBINATION CURB AND GUTTER REMOVAL	
LOCATION	FOOT
STA. 20+25 TO 22+40	430
RT STA. 30+24 TO 40+61	1037
STA. 40+61 TO 44+12	702
TOTAL	2169

HOT-MIX ASPHALT SHOULDERS				
LOCATION	LENGTH	WIDTH	AREA	AREA
	FOOT	FOOT	SQ FT	TON
STA. 30+22 TO 68+45	3823	6	22938	1142
RT STA. 40+61 TO 57+20	1659	4	6636	330
RPC STA. 40+61 TO 47+70	709	4	2836	141
IL6 STA. 732+04 TO 734+76	272	10	2720	135
TOTAL				1749