

CONCRETE MEDIAN SURFACE, 4 INCH	
LOCATION	SQ FT
STA. 20+25 TO 23+40	3308
STA. 30+22 TO 40+61	15066
TOTAL	18374

PIPE CULVERT, CLASS A, TYPE 1 18"	
LOCATION	FOOT
STA. 35+00	38
STA. 40+00	40
TOTAL	78

PRECAST REINFORCED CONCRETE FLARED END SECTION 18"	
LOCATION	EACH
STA. 35+00	1
STA. 40+00	1
TOTAL	2

INLET AND PIPE PROTECTION	
LOCATION	EACH
STA. 48+20	1
STA. 48+42	1
STA. 57+20	1
STA. 66+30	1
FRONTAGE ROAD	
STA. 72+00	1
STA. 76+00	1
TOTAL	6

MEDIAN SURFACE REMOVAL	
LOCATION	SQ FT
STA. 20+25 TO 23+40	3780
STA. 30+32 TO 40+61	9066
STA. 40+61 TO 44+12	3565
TOTAL	16411

PIPE CULVERTS, CLASS A, TYPE 1 36"	
LOCATION	FOOT
STA. 48+25	125
TOTAL	125

PRECAST REINFORCED CONCRETE FLARED END SECTION 36"	
LOCATION	EACH
STA. 48+50	2
TOTAL	2

PIPE UNDERDRAIN 4"	
LOCATION	FOOT
STA. 30+22 TO 68+45	5517
TOTAL	5517

CONCRETE HEADWALL REMOVAL	
LOCATION	EACH
RT STA. 48+20	1
RT STA. 48+80	1
TOTAL	2

PIPE CULVERT, CLASS D, TYPE 1 24"	
LOCATION	FOOT
FRONTAGE STATIONS	
STA. 66+00	88
STA. 72+00	90
STA. 76+00	64
TOTAL	242

METAL END SECTIONS 24"	
FRONTAGE CULVERTS	
LOCATION	EACH
FRONTAGE STA. 66+00	2
FRONTAGE STA. 72+00	2
FRONTAGE STA. 76+00	2
TOTAL	6

PIPE UNDERDRAIN 4" (SPECIAL)	
LOCATION	FOOT
RT STA. 30+22	16
RT STA. 33+00	16
RT STA. 35+00	16
RT & LT STA. 43+00	32
RT & LT STA. 47+80	32
RT & LT STA. 47+80	32
RT & LT STA. 51+00	32
RT STA. 56+00	16
RT STA. 61+00	16
RT STA. 66+00	16
RT STA. 68+45	16
TOTAL	240

PIPE CULVERT REMOVAL	
LOCATION	LENGTH (FEET)
LT STA. 35+00	56
LT STA. 40+00	53
LT STA. 44+84	55.9
LT STA. 48+20	76.2
LT STA. 48+80	105.9
TOTAL	347

INLETS TYPE G1 SPECIAL		
LOCATION	EACH	GRATE TYPE R-3246-AL RT
STA. 35+00	1	
STA. 40+00	1	
TOTAL	2	

REMOVING INLETS	
LOCATION	EACH
LT STA. 35+00	1
LT STA. 40+00	1
LT STA. 44+84	1
TOTAL	3