



UNDRGRD C MD  
745 FT.

A COMBINATION OF PUSHED AND TRENCHED CONDUIT WILL BE REQUIRED IN THIS AREA OF ROUGH TERRAIN. THE CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS PRIOR TO BIDDING.

I-74 EB

I-74 WB

UNDRGRD C MD  
847 FT. (PUSHED)  
ALONG ROUGH TERRAIN  
AND TREE GROVES

COMMUNICATIONS VAULT  
1.0 EACH

SCHEDULE OF QUANTITIES ITS FIBER (WOODHULL TO MOLINE) - SHEET 7		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1592.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1642.0
COMMUNICATIONS VAULT	EACH	1.0

© 2011 Google

Google earth

Imagery Date: 9/12/2011 1993

41°12'05.30" N 90°19'56.60" W elev 804 ft

Eye alt 2791 ft

FILE NAME =	USER NAME = howalder	DESIGNED -	REVISED -
S:\GEN\DRAW\ITS Fiber Project\68B04\68B04 - Woodhull to Moline (1-95) - Final 4-30-12.dwg		DRAWN -	REVISED -
	PLOT SCALE = 164.7568' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/23/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT  
I-74 (FROM WOODHULL TO MOLINE) CONTINUED  
SCALE: SHEET NO. 7 OF 62 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2013	HENRY/ROCK ISL	96	10
CONTRACT NO. 68B04				
ILLINOIS FED. AID PROJECT				