



DESCRIPTION	STATION	NORTHING	EASTING
PC #1004	956+44.82	1,257,755.3129	1,084,544.1335
PI #613	962+69.00	1,257,751.0476	1,085,168.2989
PT #1005	968+93.12	1,257,761.8821	1,085,792.3849
PC #1006	1051+80.04	1,257,905.6512	1,094,078.0595
PI #534	1066+32.73	1,257,930.8432	1,095,530.5256
PT #1007	1080+71.81	1,258,296.2728	1,096,936.4964
PC #1008	1102+70.78	1,258,849.3560	1,099,064.7760
PI #537	1117+50.83	1,259,222.9230	1,100,496.9060
PT #1009	1132+17.27	1,259,253.0664	1,101,976.6492

BENCHMARKS

BM 4906-1
 1.72' LT STA. 1606+98.16 EL. 639.69'
 TO REACH FROM THE INTERSECTION OF I-74 AND
 THE OVERHEAD AT OAKWOOD GO EAST ON I-74 FOR
 1.85 MILES TO THE MARK ON THE LEFT. SAID MARK
 IS A CHISELED SQUARE SET ON THE TOP CENTER
 OF THE NORTH HEADWALL OF A DROP BOX IN THE
 MEDIAN. SOUTH OF REST AREA.

NOTE:
 ADDITIONAL TEMPORARY BENCHMARKS REQUIRED BY THE
 RESIDENT ENGINEER WILL BE SET BY DISTRICT 5 SURVEY
 PERSONNEL PRIOR TO CONSTRUCTION. PLEASE CONTACT
 BETH SABLTONY AT 217-465-7282.

•CHAMPAIGN & VERMILION

McDonough-Whitlow, P.C.
Consulting Engineers & Land Surveyors
 138 East Wood Street
 Hillboro, IL 62049
 Phone: 217.532.9233
 Fax: 217.532.6300
 PROFESSIONAL DESIGN NO. 184-002754

FILE NAME = D570966-xxx-ALIGNMENT	USER NAME = RCJ	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ALIGNMENT AND BENCH MARKS			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50	DRAWN - RCJ	REVISED - _____		74	MEDIAN CABLE 2012-1	•	130	10			
	PLOT DATE = 3/20/2012	CHECKED - TMM	REVISED - _____		CONTRACT NO. 70966							
		DATE - _____	REVISED - _____		SCALE:	SHEET NO. 1 OF 3 SHEETS	STA. 760+00.00 TO STA. 1051+00.00	ILLINOIS FED. AID PROJECT				