

SCHEDULE OF QUANTITIES

IL 54 PATCHING SCHEDULE										
STATION	DIRECTION	LANE	LENGTH	WIDTH	44200934	44200944	44201299	44213200	44213208	44213100
					CLASS B PATCHES, TYPE II, 8.0" (SQ YD)	CLASS B PATCHES, TYPE IV, 8.0" (SQ YD)	DOWEL BARS 1 1/2" (EACH)	SAW CUTS (FT)	TIE BARS 1 1/4" (EACH)	PAVEMENT FABRIC (SQ YD)
			(FT)	(FT)						
344+00.00	EB		6	12	8.0	0.0	20	48.0	0	0.0
344+50.00	EB		6	12	8.0	0.0	20	48.0	0	0.0
345+50.00	EB		6	12	8.0	0.0	20	48.0	0	0.0
346+00.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
346+15.00	EB		6	17	11.3	0.0	30	63.0	0	0.0
347+00.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
347+50.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
348+00.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
348+50.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
349+00.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
351+00.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
351+50.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
352+75.00	EB		30	18	0.0	60.0	48	114.0	15	60.0
353+30.00	EB	LT TURN	6	12	8.0	0.0	20	54.0	0	0.0
353+50.00	EB		6	16	10.7	0.0	28	60.0	0	0.0
353+85.00	EB		6	16	10.7	0.0	28	60.0	0	0.0
354+00.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
354+00.00	EB	LT TURN	6	11	7.3	0.0	18	51.0	0	0.0
354+30.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
354+30.00	EB	LT TURN	6	11	7.3	0.0	18	51.0	0	0.0
354+80.00	EB		6	16	10.7	0.0	28	60.0	0	0.0
354+80.00	EB	LT TURN	6	11	7.3	0.0	18	51.0	0	0.0
355+00.00	EB	LT TURN	6	12	8.0	0.0	20	54.0	0	0.0
355+20.00	WB		6	16	10.7	0.0	28	60.0	0	0.0
355+25.00	EB	LT TURN	6	12	8.0	0.0	20	54.0	0	0.0
355+30.00	EB		6	15	10.0	0.0	26	57.0	0	0.0
356+89.00	WB	LT TURN	6	17	11.3	0.0	30	69.0	0	0.0
356+91.00	WB		6	17	11.3	0.0	30	63.0	0	0.0
356+92.00	EB		6	19	12.7	0.0	34	69.0	0	0.0
357+20.00	WB		6	15	10.0	0.0	26	57.0	0	0.0
357+50.00	EB		6	14	9.3	0.0	24	54.0	0	0.0
357+50.00	WB	LT TURN	6	12	8.0	0.0	20	48.0	0	0.0
357+80.00	WB	LT TURN	6	11	7.3	0.0	18	45.0	0	0.0
SUB TOTALS					304.0 (SQ YD)	60.0 (SQ YD)	832.0 (EACH)	1908.0 (FT)	15.0 (EACH)	60.0 (SQ YD)