

# SCHEDULE OF QUANTITIES

IL 10 PATCHING SCHEDULE											
STATION	DIRECTION	LANE	LENGTH	WIDTH	44200934	44200942	44200944	44201299	44213200	44213208	44213100
					CLASS B PATCHES, TYPE II, 8.0" (SQ YD)	CLASS B PATCHES, TYPE III, 8.0" (SQ YD)	CLASS B PATCHES, TYPE IV, 8.0" (SQ YD)	DOWEL BARS 11/2" (EACH)	SAW CUTS (FT)	TIE BARS 1 1/4" (EACH)	PAVEMENT FABRIC (SQ YD)
			(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(EACH)	(FT)	(EACH)	(SQ YD)
2353+51.00	EB		6	12	8.0	0.0	0.0	20	48.0	0	0.0
2354+12.00	EB		6	14.5	9.7	0.0	0.0	25	55.5	0	0.0
2354+24.00	EB		6	15	10.0	0.0	0.0	26	57.0	0	0.0
2354+72.00	EB		6	15	10.0	0.0	0.0	26	57.0	0	0.0
2355+30.00	EB		6	21	14.0	0.0	0.0	38	75.0	0	0.0
2355+80.00	WB		15	14	0.0	23.3	0.0	24	72.0	0	23.3
2356+00.00	EB		6	15	10.0	0.0	0.0	26	57.0	0	0.0
2356+30.00	EB		6	15	10.0	0.0	0.0	26	57.0	0	0.0
2357+62.00	EB		6	15	10.0	0.0	0.0	26	57.0	0	0.0
2359+00.00	EB		21	16	0.0	0.0	37.3	42	90.0	11	37.3
2360+00.00	EB	LT TURN	8	11.5	10.2	0.0	0.0	19	58.5	0	0.0
2360+00.00	WB		11	14	0.0	17.1	0.0	24	64.0	0	17.1
2360+52.00	EB	RT TURN	7	9	7.0	0.0	0.0	14	48.0	0	0.0
2361+00.00	WB		6	14	9.3	0.0	0.0	24	54.0	0	0.0
2361+34.00	WB		6	14	9.3	0.0	0.0	24	54.0	0	0.0
2361+45.00	WB	RT TURN	42	6	0.0	0.0	28.0	16	102.0	21	28.0
2361+50.00	WB		6	14	9.3	0.0	0.0	24	54.0	0	0.0
2363+00.00	WB	LT TURN	6	11	7.3	0.0	0.0	18	57.0	0	0.0
2364+00.00	EB		6	14	9.3	0.0	0.0	24	54.0	0	0.0
2364+50.00	WB	LT TURN	6	11	7.3	0.0	0.0	18	57.0	0	0.0
2364+83.00	WB		6	15	10.0	0.0	0.0	26	57.0	0	0.0
2364+83.00	WB	LT TURN	6	11	7.3	0.0	0.0	18	57.0	0	0.0
2365+00.00	WB	LT TURN	6	11	7.3	0.0	0.0	18	60.0	0	0.0
2365+50.00	WB	LT TURN	6	11	7.3	0.0	0.0	18	51.0	0	0.0
2365+73.00	WB	LT TURN	6	11	7.3	0.0	0.0	18	60.0	0	0.0
2366+00.00	WB	LT TURN	6	9	6.0	0.0	0.0	14	45.0	0	0.0
2366+30.00	WB	LT TURN	6	8	5.3	0.0	0.0	12	75.0	0	0.0
2366+68.00	EB		6	14	9.3	0.0	0.0	24	54.0	0	0.0
2368+20.00	EB		6	14	9.3	0.0	0.0	24	54.0	0	0.0
2369+23.00	EB		6	14	9.3	0.0	0.0	24	54.0	0	0.0
2370+75.00	CL	REMOVE RUMBLE	33	3	11.0	0.0	0.0	3	75.0	34	0.0
SUB TOTALS					240.6 (SQ YD)	40.4 (SQ YD)	65.3 (SQ YD)	683.0 (EACH)	1870.0 (FT)	66.0 (EACH)	105.7 (SQ YD)